



ADDENDUM NO. 1 BID OPPORTUNITY NO. 122-2004

ROOF REPLACEMENT AT PAN-AM POOL – 25 POSEIDON BAY

URGENT

**PLEASE FORWARD THIS DOCUMENT TO
WHOEVER IS IN POSSESSION OF THE BID
OPPORTUNITY**

ISSUED: May 18, 2004
BY: Coleen Groening /clg
TELEPHONE NO. (204) 986-2491

**THIS ADDENDUM SHALL BE INCORPORATED
INTO THE BID OPPORTUNITY AND SHALL
FORM A PART OF THE CONTRACT
DOCUMENTS**

Template Version: 20040128

Please note the following and attached changes, corrections, additions, deletions, information and/or instructions in connection with the Bid Opportunity, and be governed accordingly. Failure to acknowledge receipt of this Addendum in Paragraph 8 of Form A: Bid may render your Bid Submission non-responsive.

PART B – BIDDING PROCEDURES

Revise: B2.1 to read:

B2.1 The Submission Deadline is 12:00 noon Winnipeg time, **May 28, 2004**.

PART E – SPECIFICATIONS

Revise: E4.06 to read

E4.06 The existing roof hatch and access ladder is to be removed and discarded. Remove the old ladder anchor bolts and discard. Install 18 ga. Sheet metal overtop of the hatch opening and secure in place with bent pin fasteners. The new vapour barrier is to be carried overtop of this old opening. Once the vapour barrier is installed ¾" fir plywood is to be installed overtop to provide structural strength. The plywood is to extend a minimum of 6" onto the deck on all sides of the opening.

Revise: E4.11 to read

E4.11 Install the new drains in the locations indicated on the roof plan. Confirm drain locations with the Contract Administrator. The north drain is to be approximately 4' from the north high wall and the south drain location will be determined on site. There is some deflection in the existing deck and as such it is important to install the south drain in the proper location. The existing drain is to be closed off and the plumbing properly repaired. Tie the new plumbing into the existing plumbing.