



THE CITY OF WINNIPEG

BID OPPORTUNITY

BID OPPORTUNITY NO. 138-2004

2004 MAIN STREET – ROADWAY RECONSTRUCTION (SOUTHBOUND) AND
STREETSCAPING (WESTSIDE) – LOMBARD AVENUE TO DISRAELI FREEWAY



**Canada-Manitoba
Infrastructure
Program**

**Programme
Infrastructures
Canada-Manitoba**

Canada 

Manitoba 

TABLE OF CONTENTS (R1)

PART A - BID SUBMISSION

Form A: Bid	1
Form B: Prices	4
Subtotal:	
Form G1: Bid Bond and Agreement to Bond	12
Form G2: Irrevocable Standby Letter of Credit and Undertaking	14

PART B - BIDDING PROCEDURES

B1. Project Title	1
B2. Submission Deadline	1
B3. Enquiries	1
B4. Addenda	1
B5. Substitutes	2
B6. Bid Submission	2
B7. Bid	3
B8. Prices	4
B9. Qualification	4
B10. Bid Security	5
B11. Opening of Bids and Release of Information	5
B12. Irrevocable Bid	6
B13. Withdrawal of Bids	6
B14. Evaluation of Bids	7
B15. Award of Contract	7
B16. Federal / Provincial Clauses	8

PART C - GENERAL CONDITIONS

C1. General Conditions	1
------------------------	---

PART D - SUPPLEMENTAL CONDITIONS

General

D1. General Conditions	1
D2. Scope of Work	1
D3. Contract Administrator	2
D4. Contractor's Supervisor	2
D5. Notices	2
D6. Furnishing of Documents	3

Submissions

D7. Performance Security	3
D8. Insurance	3
D9. SubContractor List	4
D10. Detailed Work Schedule	4

Schedule of Work

D11. Commencement	4
D12. Restricted Work Hours	4
D13. Work by Others	5
D14. Sequence of Work	5
D15. Critical Stages	6
D16. Substantial Performance	6
D17. Total Performance	6
D18. Liquidated Damages	7

Control of Work

D19. Job Meetings	7
D20. Prime Contractor – The Workplace Safety and Health Act (Manitoba)	7

Warranty

D21. Warranty	8
Form H1: Performance Bond	9
Form H2: Irrevocable Standby Letter of Credit	11
Form J: SubContractor List	13
Form L: Detailed Work Schedule	14

PART E - SPECIFICATIONS

General

E1. Applicable Specifications, Standard Details And Drawings	1
E2. Office Facilities	2
E3. Protection Of Existing Trees	3
E4. Traffic Control	4
E5. Pedestrian Safety	4
E6. Water Used By Contractor	4
E7. Infrastructure Signs	4
E8. Traffic Diversions	5
E9. Archaeological Investigation	5
E10. Subdrain Insulation	6
E11. Intersection Construction / Staging	6
E12. Joint Details	6
E13. Connection To Existing Manhole	6
E14. Modified Bullnose	7
E15. Sawcutting Pavement	7
E16. Replacement Of Catchbasin Hoods	7
E17. Manhole Or Catchbasin Steps	7
E18. Abandoning Existing Catchbasin Leads	7
E19. Sign Support Clamps And Parking Meter Poles	8
E20. Winnipeg Transit Bus Stops	8
E21. Manhole Isolations	8
E22. Proposed Manitoba Hydro Works And Allstream Manholes	8
E23. Existing Street Car Tracks	9
E24. Construction Facilities And Staging	10
E25. Contractor Employee Parking	10
E26. All-Weather Dump Site	10
E27. Transit Sign Removal	10
E28. Boulevard Restoration	10
E29. Matching Existing Grades	11
E30. Exposing Existing Underground Services And Utilities	11
E31. Layout Of Streetscaping Works	11
E32. Private Sidewalks, Side Street Sidewalks	11
E33. Existing Curb Stop Boxes	12
E34. Areaways	12
E35. Removal Of Existing Interlock Paving Stone	13
E36. Removal Of Tree Wells And Grates And Miscellaneous Items	14
E37. Trenching And Backfilling	14
E38. Concrete Formwork	15
E39. Steel Screw Anchor Foundation	16
E40. Deleted	19
E41. Concrete Reinforcement	19
E42. Cast In Place Concrete	21
E43. Protective Graffiti Coating	26

E44. Concrete Collars	27
E45. 100 Mm Concrete Sidewalk With Paving Stone, Coloured Concrete, Medallion And Brick Inset	27
E46. Palomino Yellow Concrete Sidewalk Infill Wave	28
E47. Interlocking Paving Stone And Brick Pavers	30
E48. Cultural Medallion And Stepping Stone Paving	35
E49. Plant Material	36
E50. Preparation Of Tree Wells	43
E51. Preparation Of Planters And Planting Beds	45
E52. Extended Maintenance Of Street Trees And Plant Material	47
E53. Concrete Tree Covers And Sidewalk Panels	49
E54. Project Carry-Over In 2005	51
E55. Cast-In-Place Concrete Light Standard Piles	51
E56. Structural Steel	56
E57. Remove Existing Asphalt On New Concrete	60
E58. Construction Of 250mm Concrete Pavement For Crosswalks	61