

FORM B: PRICES (UNIT PRICE) (R1)
(SEE B9)

Project Title: 2004 Combined Sewer Renewals by CIPP Lining - Contract No. 11

ITEM	DESCRIPTION	SPEC. REF.	UNIT	APPROX. QUANTITY	UNIT PRICE	AMOUNT
A. 1	Mobilization and Demobilization		lump sum	1.0		
		Mobilization and Demobilization - Sub-Total				
B	Burnell Street (Sewer I.D. 8770): 1st MH N of Portage Avenue (MH I.D. 8771) to MH at Portage Avenue (MH I.D. 8302)					
B 1	Sewer Cleaning	E2				
a)	600mm					
i)	Pre-lining Cleaning		m	114.2		
ii)	Warranty Cleaning		m	114.2		
B 2	Sewer Inspection	E2				
a)	600mm					
i)	Pre-lining Inspection		m	114.2		
ii)	Post Lining Inspection		m	114.2		
iii)	Warranty Inspection		m	114.2		
B 3	Flow Control	E2				
a)	600mm		each	1.0		
B 4	Full Segment CIPP	E2				
a)	600mm		m	114.2		
B 5	Reinstatement of sewer services	E2	each	10.0		
B 6	Catch Basin Lead Cleaning	E4				
a)	200 mm		m	30.0		
B 7	Catch Basin Lead Inspection	E4				
a)	200 mm		m	30.0		
B 8	Internal Host Pipe Repairs	E3				
a)	Removal of solid debris					
i)	at services or joints		each	6.0		
ii)	along pipe 3m or less		each	2.0		
b)	Removal of Intruding Connections		each	3.0		
		Burnell Street (Sewer I.D. 8772) - Sub-Total				

Name of Bidder

FORM B: PRICES (UNIT PRICE) (R1)
(SEE B9)

Project Title: 2004 Combined Sewer Renewals by CIPP Lining - Contract No. 11

ITEM	DESCRIPTION	SPEC. REF.	UNIT	APPROX. QUANTITY	UNIT PRICE	AMOUNT
C	Burnell Street (Sewer I.D. 8772): 1st MH N. of Portage Avenue (MH I.D. 8771) to MH at Einarson Avenue (MH I.D. 8773)					
C 1	Sewer Cleaning	E2				
a)	600mm					
i)	Pre-lining Cleaning		m	114.0		
ii)	Warranty Cleaning		m	114.0		
C 2	Sewer Inspection	E2				
a)	600mm					
i)	Pre-lining Inspection		m	114.0		
ii)	Post Lining Inspection		m	114.0		
iii)	Warranty Inspection		m	114.0		
C 3	Flow Control	E2				
a)	600mm		each	1.0		
C 4	Full Segment CIPP	E2				
a)	600mm		m	114.0		
C 5	Reinstatement of sewer services	E2				
			each	15.0		
C 6	Catch Basin Lead Cleaning	E4				
a)	200 mm		m	15.0		
C 7	Catch Basin Lead Inspection	E4				
a)	200 mm		m	15.0		
C 8	Internal Host Pipe Repairs	E3				
a)	Removal of solid debris					
i)	at services or joints		each	7.0		
b)	Removal of Intruding Connections		each	2.0		
		Burnell Street (Sewer I.D. 8772) - Sub-Total				
D	Burnell Street (Sewer I.D. 8781): 2nd MH S. of St. Matthews (MH I.D. 8780) to MH at St. Paul Avenue (MH I.D. 8775)					
D 1	Sewer Cleaning	E2				
a)	600mm					

 Name of Bidder

FORM B: PRICES (UNIT PRICE) (R1)
(SEE B9)

Project Title: 2004 Combined Sewer Renewals by CIPP Lining - Contract No. 11

ITEM	DESCRIPTION	SPEC. REF.	UNIT	APPROX. QUANTITY	UNIT PRICE	AMOUNT	
	i) Pre-lining Cleaning		m	57.9			
	ii) Warranty Cleaning		m	57.9			
D 2	Sewer Inspection	E2					
	a) 600mm						
	i) Pre-lining Inspection		m	57.9			
	ii) Post Lining Inspection		m	57.9			
	iii) Warranty Inspection		m	57.9			
D 3	Flow Control	E2					
	a) 600mm		each	1.0			
D 4	Full Segment CIPP	E2					
	a) 600mm		m	57.9			
D 5	Reinstatement of sewer services	E2	each	8.0			
D 6	Catch Basin Lead Cleaning	E4					
	a) 200 mm		m	15.0			
D 7	Catch Basin Lead Inspection	E4					
	a) 200 mm		m	15.0			
D 8	Internal Host Pipe Repairs	E3					
	a) Removal of Solid Debris						
	i) At Services or Joints		each	4.0			
	b) Removal of Intruding Connections		each	1.0			
		Burnell Street (Sewer I.D. 8781) Sub-Total					
E	Burnell Street (Sewer I.D. 8779): 1st MH S of St. Matthews Avenue (MH I.D. 8778) to 2nd MH S of St. Matthews Avenue (MH I.D. 8780)						
E 1	Sewer Cleaning	E2					
	a) 600mm						
	i) Pre-lining Cleaning		m	59.4			
	ii) Warranty Cleaning		m	59.4			
E 2	Sewer Inspection	E2					
	a) 600mm						

Name of Bidder

FORM B: PRICES (UNIT PRICE) (R1)
(SEE B9)

Project Title: 2004 Combined Sewer Renewals by CIPP Lining - Contract No. 11

ITEM	DESCRIPTION	SPEC. REF.	UNIT	APPROX. QUANTITY	UNIT PRICE	AMOUNT	
	i) Pre-lining Inspection		m	59.4			
	ii) Post Lining Inspection		m	59.4			
	iii) Warranty Inspection		m	59.4			
E 3	Flow Control	E2					
a)	600mm		each	1.0			
E 4	Full Segment CIPP	E2					
a)	600mm		m	59.4			
E 5	Reinstatement of sewer services	E2	each	6.0			
E 6	Internal Host Pipe Repairs	E3					
a)	Removal of solid debris						
i)	at services or joints		each	5.0			
ii)	Along Pipe 3m or Less		each	5.0			
		Burnell Street (Sewer I.D. 8779) - Sub-Total					
F	Burnell Street (Sewer I.D. 8776): MH at St. Matthews Avenue (MH I.D. 8777) to 1st MH S of St. Matthews Avenue (MH I.D. 8778)						
F 1	Sewer Cleaning	E2					
a)	600 mm						
i)	Pre-lining Cleaning		m	117.9			
ii)	Warranty Cleaning		m	117.9			
F 2	Sewer Inspection	E2					
a)	600 mm						
i)	Pre-lining Inspection		m	117.9			
ii)	Post Lining Inspection		m	117.9			
iii)	Warranty Inspection		m	117.9			
F 3	Flow Control	E2					
a)	600 mm		each	1.0			
F 4	Full Segment CIPP	E2					
a)	600 mm		m	117.8			
F 5	Reinstatement of sewer services	E2	each	15.0			

Name of Bidder

FORM B: PRICES (UNIT PRICE) (R1)
(SEE B9)

Project Title: 2004 Combined Sewer Renewals by CIPP Lining - Contract No. 11

ITEM	DESCRIPTION	SPEC. REF.	UNIT	APPROX. QUANTITY	UNIT PRICE	AMOUNT
F 6	Catch Basin Lead Cleaning a) 200 mm	E4	m	30.0		
F 7	Catch Basin Lead Inspection a) 200 mm	E4	m	30.0		
F 8	Internal Host Pipe Repairs a) Removal of Solid Debris i) at services or joints b) Removal of Intruding Connections	E3	each each	8.0 2.0		
G Cumberland Ave. (Sewer I.D. 2377): MH at Carlton St. by E PL (MH I.D. 2376) to 1st MH E of Carlton St. (MH I.D. 2378)						
G 1	Sewer Cleaning a) 375mm i) Pre-lining Cleaning ii) Warranty Cleaning	E2	m m	69.3 69.3		
G 2	Sewer Inspection a) 375mm i) Pre-lining Inspection ii) Post Lining Inspection iii) Warranty Inspection	E2	m m m	69.3 69.3 69.3		
G 3	Flow Control a) 375mm	E2	each	1.0		
G 4	Full Segment CIPP a) 375mm	E2	m	69.3		
G 5	Reinstatement of sewer services	E2	each	11.0		
G 6	Catch Basin Lead Cleaning a) 200 mm	E4	m	30.0		
G 7	Catch Basin Lead Inspection a) 200 mm	E4	m	30.0		

 Name of Bidder

FORM B: PRICES (UNIT PRICE) (R1)

(SEE B9)

Project Title: 2004 Combined Sewer Renewals by CIPP Lining - Contract No. 11

ITEM	DESCRIPTION	SPEC. REF.	UNIT	APPROX. QUANTITY	UNIT PRICE	AMOUNT
G 8	Internal Host Pipe Repairs	E3				
	a) Removal of Solid Debris					
	i) at services or joints		each	1.0		
	b) Removal of Intruding Connections		each	5.0		
Cumberland Avenue (Sewer I.D. 2377) - Sub-Total						
H	<u>Alverstone (Sewer I.D. 9487) MH</u> <u>South of McIntyre (MH I.D. 9485) to</u> <u>MH at Sargent Ave. (MH I.D. 9487)</u>					
H 1	Sewer Cleaning	E2				
	a) 450mm					
	i) Pre-lining Cleaning		m	94.6		
	ii) Warranty Cleaning		m	94.6		
H 2	Sewer Inspection	E2				
	a) 450mm					
	i) Pre-Sewer Repair Inspection		m	94.6		
	ii) Pre-lining Inspection		m	94.6		
	iii) Post Lining Inspection		m	94.6		
	iv) Warranty Inspection		m	94.6		
H 3	Flow Control	E2				
	a) 450mm		each	1.0		
H 4	Full Segment CIPP	E2				
	a) 450mm		m	94.6		
H 5	Reinstatement of sewer services	E2	each	10.0		
H 6	Internal Host Pipe Repairs	E3				
	a) Removal of Intruding Connections		each	1.0		
H 7	External Sewer Repair (Class 3 backfill)					
	a) 450 mm					
	i) Up to 3 metres long		each	2.0		
	ii) In Addition to the First 3.0 metres		m	1.8		

Name of Bidder

FORM B: PRICES (UNIT PRICE) (R1)
(SEE B9)

Project Title: 2004 Combined Sewer Renewals by CIPP Lining - Contract No. 11

ITEM	DESCRIPTION	SPEC. REF.	UNIT	APPROX. QUANTITY	UNIT PRICE	AMOUNT
H 8	Connect existing sewer service to new sewer	CW 2130				
a)	150 mm		each	3.0		
H 9	Full Depth Partial Slab Patches					
a)	Removal					
i)	150 mm reinforced concrete pavement		m ²	25.0		
b)	Installation					
i)	150 mm reinforced concrete pavement for early opening (24 hours)		m ²	25.0		
H 10	Construction of Asphaltic Concrete Overlays Type 1A	CW 3410	tonne	8.0		
Alverstone Street. (Sewer I.D. 9487) Sub-Total						

Name of Bidder

FORM B: PRICES (UNIT PRICE) (R1)
(SEE B9)

Project Title: 2004 Combined Sewer Renewals by CIPP Lining - Contract No. 11

ITEM	DESCRIPTION	SPEC. REF.	UNIT	APPROX. QUANTITY	UNIT PRICE	AMOUNT
I	Provisional Items					
I 1	Manhole and Catchbasin Repair	CW 2130				
	a) Supply and Install Manhole Rungs		each	10.0		
	b) Replace Existing Manhole Solid Cover		each	1.0		
	c) Grout Manhole Base		each	2.0		
	d) Grout Catchbasin		each	1.0		
	e) Supply and Install Catchbasin Hood		each	1.0		
I 2	Internal Host Pipe Repairs	E3				
	a) Removal of solid debris					
	i) at services or joints		each	2.0		
	ii) along pipe 3m or less		each	2.0		
	iii) along pipe additional metres		m	3.0		
	b) Removal of Intruding Connections		each	2.0		
I 3	Full Segment CIPP - CB lead	E2				
	a) 200 mm		m	10.0		
I 4	Internal Point Repair CIPP - CB lead	E2				
	a) 200 mm		m	3.0		
Provisional Items - Sub-Total						
<p>TOTAL BID PRICE (GST extra) (in figures)\$</p> <p>(in words)</p> <hr/> <hr/>						

Name of Bidder