

FORM B (R1): PRICES
 (See B:8)

UNIT PRICES						
ITEM NO.	DESCRIPTION	SPEC. REF.	UNIT	APPROX. QUANTITY	UNIT PRICE	AMOUNT
A	Mobilization and Demobilization	E:3/E:4	each	1		
B	Archibald St. (Sewer ID 7351) from MH (ID 7350) at Kavanagh St. to 1st MH (ID 7352) North of Kavanagh St.					
B.1	Sewer Cleaning a) 1200x900mm Egg	CW 2140				
	i) Pre-Lining Cleaning		m	76.1		
	ii) Warranty Cleaning		m	76.1		
B.2	Sewer Inspection a) 1200x900mm Egg	CW 2145				
	i) Pre-Lining Inspection		m	76.1		
	ii) Post-Lining Inspection		m	76.1		
	iii) Warranty Inspection		m	76.1		
B.3	New Manhole on Existing Sewers a) 1800mm Ø x 2.44m base (MH.7350)	E:3/E:4	each	1		
B.4	Concrete Pavement (Removal) a) 200mm Pavement	CW2130	m ²	16		
B.5	Concrete Pavement (Replacement) a) 200mm Pavement (24 hour early opening)	CW2130	m ²	16		
B.6	Hot Mix Asphaltic Concrete Pavement Type 1A a) Patching	CW2130	m ²	16		
B.7	Flow Control	E:3/E:4	each	1		
B.8	Liner Installation a) 1200x900mm Egg	E:3/E:4	m	76.1		
B.9	Reinstatement of Sewer Services	E:3/E:4	each	2		
	Sub-Total					
C	Burnell St. (Sewer ID 26019) from 1st MH (ID 26020) North of Ellice Ave. to 1st MH (ID 26021) South of Ellice Ave.					
C.1	Sewer Cleaning a) 2591mm	CW 2140				
	i) Pre-Lining Cleaning		m	117.3		
	ii) Warranty Cleaning		m	117.3		

 Name of Bidder

FORM B (R1): PRICES
 (See B:8)

UNIT PRICES						
ITEM NO.	DESCRIPTION	SPEC. REF.	UNIT	APPROX. QUANTITY	UNIT PRICE	AMOUNT
C.2	Sewer Inspection	CW 2145				
	a) 2591mm					
	i) Pre-Lining Inspection		m	117.3		
	ii) Post-Lining Inspection		m	117.3		
	iii) Warranty Inspection		m	117.3		
C.3	Manhole Repairs	E:3/E:4				
	a) Replace Existing Risers (MH 26020) (1200mm dia.)		each	1		
C.4	Flow Control	E:4	each	1		
C.5	Liner Installation	E:4				
	a) 2591mm		m	30.0		
C.6	Reinstatement of Sewer Services	E:4	each	1		
	Sub-Total					
D	De La Morenie St. (Sewer ID 19261) from 1st MH (ID 19260) South of Hamel Ave. to 2nd MH (ID 19262) South of Hamel Ave.					
D.1	Sewer Cleaning	CW2140				
	a) 1200x700mm Egg					
	i) Pre-Lining Cleaning		m	106.4		
	ii) Warranty Cleaning		m	106.4		
D.2	Sewer Inspection	CW2145				
	a) 1200x700mm Egg					
	i) Pre-Lining Inspection		m	106.4		
	ii) Post-Lining Inspection		m	106.4		
	iii) Warranty Inspection		m	106.4		
D.3	Catchbasin Lead Cleaning	E:6				
	a) Pre-Sewer Lining Installation					
	i) CB 01		m	7		
	ii) CB 02		m	5		
D.4	Catchbasin Lead Inspection	E:6				
	a) Pre-Sewer Lining Installation					
	i) CB 01		m	7		
	ii) CB 02		m	5		
D.5	New Manhole on Existing Sewers	E:3/E:4				
	a) 1500mm Ø x 2.44m base (MH.19260)		each	1		

 Name of Bidder

FORM B (R1): PRICES
 (See B:8)

UNIT PRICES						
ITEM NO.	DESCRIPTION	SPEC. REF.	UNIT	APPROX. QUANTITY	UNIT PRICE	AMOUNT
D.6	Manhole Repairs a) Patching	CW2130	v.m.	0.2		
D.7	Concrete Pavement (Removal) a) 200mm Pavement	CW2130	m ²	16		
D.8	Concrete Pavement (Replacement) a) 200mm Pavement (24 hour early opening)	CW2130	m ²	16		
D.9	Hot Mix Asphaltic Concrete Pavement Type 1A a) Patching	CW2130	m ²	16		
D.10	Internal Sewer Repairs a) Up to 1.0 metre long b) In Excess of 1.0 metres	E:5	each m	1 15		
D.11	Solid Debris Cutting a) First 3 metres b) Additional	CW2140	each m	1 1		
D.12	Removal of Intruding Sewer Services	CW2140	each	2		
D.13	Sewer Service Grouting a) prior to lining b) after lining	E:3/E:4	each each	7 5		
D.14	Flow Control	E:3/E:4	each	1		
D.15	Liner Installation a) 1200x700mm Egg	E:3/E:4	m	106.4		
D.16	Reinstatement of Sewer Services	E:3/E:4	each	23		
	Sub-Total					
E	Polson Ave. (Sewer ID 16757) from 1st MH (ID 16756) East of Airlies St. to 2nd MH (ID 16758) East of Airlies St.					
E.1	Sewer Cleaning a) 1550x1200mm Egg i) Pre-Lining Cleaning ii) Warranty Cleaning	CW2140	m m	100.4 100.4		

 Name of Bidder

FORM B (R1): PRICES
 (See B:8)

UNIT PRICES						
ITEM NO.	DESCRIPTION	SPEC. REF.	UNIT	APPROX. QUANTITY	UNIT PRICE	AMOUNT
E.2	Sewer Inspection	CW2145				
	a) 1550x1200mm Egg					
	i) Pre-Lining Inspection		m	100.4		
	ii) Post-Lining Inspection		m	100.4		
	iii) Warranty Inspection		m	100.4		
E.3	Catchbasin Lead Cleaning	E:6				
	a) Pre-Sewer Lining Installation					
	i) CB 07		m	40		
	ii) CB 08		m	8		
	iii) CB 09		m	8		
E.4	Catchbasin Lead Inspection	E:6				
	a) Pre-Sewer Lining Installation					
	i) CB 07		m	40		
	ii) CB 08		m	8		
	iii) CB 09		m	8		
E.5	New Manhole on Existing Sewers	E:3/E:4				
	a) 2100mm Ø x 2.44m base (MH.16756)		each	1		
E.6	Manhole Repairs	CW2130				
	a) Patching (MH 16758)		v.m.	1.9		
E.7	Concrete Pavement (Removal)	CW2130				
	a) 200mm Pavement		m ²	16		
E.8	Concrete Pavement (Replacement)	CW2130				
	a) 200mm Pavement (24 hour early opening)		m ²	16		
E.9	Internal Sewer Repairs	E:5				
	a) Up to 1.0 metre long		each	1		
	b) In Excess of 1.0 metres		m	18		
E.10	Solid Debris Cutting	CW2140				
	a) First 3 metres		each	1		
	b) Additional		m	4		
	c) remove pieces of pipe		each	1		
E.11	Sewer Service Grouting	E:3/E:4				
	a) prior to lining		each	1		
	b) after lining		each	1		
E.12	Flow Control	E:3/E:4				
			each	1		
E.13	Liner Installation	E:3/E:4				
	a) 1550x1200mm Egg		m	100.4		

 Name of Bidder

FORM B (R1): PRICES
 (See B:8)

UNIT PRICES						
ITEM NO.	DESCRIPTION	SPEC. REF.	UNIT	APPROX. QUANTITY	UNIT PRICE	AMOUNT
E.14	Reinstatement of Sewer Services	E:3/E:4	each	20		
	Sub-Total					
F	Polson Ave. (Sewer ID 16768) from 3rd MH (ID 16767) East of Airlies St. to MH (ID 16769) at Sinclair St. (E PL)					
F.1	Sewer Cleaning	CW2140				
	a) 1550x1200mm Egg					
	i) Pre-Lining Cleaning		m	100.6		
	ii) Warranty Cleaning		m	100.6		
F.2	Sewer Inspection	CW2145				
	a) 1550x1200mm Egg					
	i) Pre-Lining Inspection		m	100.6		
	ii) Post-Lining Inspection		m	100.6		
	iii) Warranty Inspection		m	100.6		
F.3	Catchbasin Lead Cleaning	E:6				
	a) Pre-Sewer Lining Installation					
	i) CB 10		m	6		
	ii) CB 11		m	6		
F.4	Catchbasin Lead Inspection	E:6				
	a) Pre-Sewer Lining Installation					
	i) CB 10		m	6		
	ii) CB 11		m	6		
F.5	New Manhole on Existing Sewers	E:3/E:4				
	a) 2100mm Ø x 2.44m base (MH.16767)		each	1		
F.6	Manhole Repairs	CW2130				
	a) Replace Existing Risers (MH 16769) (750mm dia.)		v.m.	0.7		
F.7	Concrete Pavement (Removal)	CW2130				
	a) 200mm Pavement		m ²	20		
F.8	Concrete Pavement (Replacement)	CW2130				
	a) 200mm Pavement (24 hour early opening)		m ²	20		
F.9	Internal Sewer Repairs	E:5				
	a) Up to 1.0 metre long		each	1		
	b) In Excess of 1.0 metres		m	9		

 Name of Bidder

FORM B (R1): PRICES
 (See B:8)

UNIT PRICES						
ITEM NO.	DESCRIPTION	SPEC. REF.	UNIT	APPROX. QUANTITY	UNIT PRICE	AMOUNT
F.10	Solid Debris Cutting a) First 3 metres b) Additional c) remove pieces of pipe	CW2140	each m each	1 5 1		
F.11	Sewer Service Grouting a) after lining	E:3/E:4	each	4		
F.12	Flow Control	E:3/E:4	each	1		
F.13	Liner Installation a) 1550x1200mm Egg	E:3/E:4	m	100.6		
F.14	Reinstatement of Sewer Services	E:3/E:4	each	19		
	Sub-Total					
TOTAL BID PRICE (GST extra) (in figures)					\$	
(in words)						

 Name of Bidder