



257-2005 ADDENDUM 2

REDWOOD BRIDGE, REHABILITATIVE MAINTENANCE AND RELATED WORKS

URGENT

PLEASE FORWARD THIS DOCUMENT TO WHOEVER IS IN POSSESSION OF THE BID OPPORTUNITY

ISSUED: August 11, 2005
BY: Barry Biswanger
TELEPHONE NO. (204) 284-0580

THIS ADDENDUM SHALL BE INCORPORATED INTO THE BID OPPORTUNITY AND SHALL FORM A PART OF THE CONTRACT DOCUMENTS

Template Version: A20050506

Please note the following and attached changes, corrections, additions, deletions, information and/or instructions in connection with the Bid Opportunity, and be governed accordingly. Failure to acknowledge receipt of this Addendum in Paragraph 10 of Form A: Bid may render your Bid non-responsive.

PART D – SUPPLEMENTAL CONDITIONS

D23 TRAFFIC CONTROL:

Replace with the following:

“D23 COOPERATION WITH OTHERS ON SITE

- 23.1 Further to Clause GC.6.25 of the General Conditions, the Contractor is advised that other Contractors of the City and of Utilities may be working on and/or adjacent to the site during the execution of this Contract. It will be the Contractor’s responsibility to cooperate to the fullest extent with other personnel working in the area and such cooperation is an obligation of the Contractor under the terms of this Contract.
- 23.2 Additional project work contracts being carried out by others will be in progress both in the vicinity of the Works and within the Work areas for this Contract. The scope of Work, the limits of Work described, or the number of contractors of other contracts may change as Work progresses. Other contracts include:
 - (a) Roadway Rehabilitation of Hespeler from Henderson to Glenwood Crescent.

D24.3: Revise “10 foot candles” to “2 foot candles”.

PART E - SPECIFICATIONS

E4.2.4 Traffic Gates:

Add the following: “The provision of traffic protection/accommodation outside of the area protected by the traffic gates will be provided by the City.”

E14.1 Description:

Add the following to the first paragraph “This shall also include the repositioning of Span 4 superstructure for the new bearings on Piers 4 and 5.

E14.3.1(e):

Add this clause worded as follows: “Repositioning of Span 4 superstructure for the new bearings on Piers 4 and 5. This requires moving Span 4 superstructure 150 mm to the west as noted on the drawings.”

10.6 Method of Measurement

Shall be changed to "E14.6 Method of Measure" unit and add the following: "The repositioning of Span 4 superstructure shall be considered incidental to the bearing works."

10.7 Basis of Payment

Shall be changed to "E14.7 Basis of Payment".

E18.3.2 Coating Application Equipment:

Add the following: "If the Contractor cannot obtain equipment to apply metallizing to specified thicknesses to all surfaces inside small members, then the Contractor is to provide equivalent protection utilizing "Zinga" or equal."

E18.4.6.4 Surface Testing and Inspection:

Add the following to the last paragraph: "Any costs for additional surface preparation shall be included as part of the tendered price for structural steel for miscellaneous bridge repairs."

E18.5.1 General:

Add the following to the second paragraph: "The minimum number of site visits by a representative of the coating manufacturer shall be three (3) with one (1) at startup and the others as directed by the Contract Administrator."

E18.5.2 Guarantee: Deleted.

E19.4.1 (a):

Add the following: "Should the Contractor want to have this waste stream reclassified as non-hazardous waste, the Contractor shall provide additional testing to prove that at their own cost and submit test results to the Contract Administrator for acceptance. Until these test results are found acceptable to the Contract Administrator this waste stream shall be treated as hazardous waste."

E19.4.1 (c):

Add this clause worded as follows: "Containment, collection and disposal of water used for washing the structure prior to blast cleaning to prevent erosion damage to existing grade and existing riverbanks. Any erosion damage shall be repaired immediately at the Contractor's own cost."

E19.5 Quality Control:

Add the following to the first paragraph: "The Contractor shall provide and pay for monitoring within the enclosure to suit the requirements at Workplace Health and Safety. Any waste stream that is not contained, collected and disposed of shall be cleaned up immediately by the Contractor at their own cost."

DRAWINGS

Replace: Drawing B113-05-15 with Drawing B-113-05-15-R1.

Replace: Drawing B113-05-17 with Drawing B-113-05-17-R1.

Replace: Drawing B113-05-18 with Drawing B-113-05-18-R1.

Replace: Drawing B113-05-42 with Drawing B-113-05-42-R1.