

FORM B: PRICES
 (See B9)

NORTHEAST INTERCEPTOR – STAGE VII

UNIT PRICES

ITEM NO.	DESCRIPTION	SPEC. REF.	UNIT	APPROX. QUANTITY	UNIT PRICE	AMOUNT
A.1	Interceptor Sewers	CW 2130				
a)	1200mm, C76 CLV RCP					
i)	trenchless installation, Class B sand bedding, Class 3 backfill		m	200.0		
ii)	trenchless installation, Class B sand bedding, Class 5 backfill,		m	1624.0		
a)	1350mm, C76 CLV RCP					
i)	trenchless installation, Class B sand bedding, Class 5 backfill		m	3.0		
A.2	Wastewater Sewer	CW 2130				
a)	250mm, SDR 35 PVC					
i)	trenchless installation, Class B sand bedding, Class 5 backfill		m	16.0		
A.3	Land Drainage Sewer	CW 2130				
a)	1050mm, C76 CLV RCP					
i)	trenchless installation, Class B sand bedding, Class 3 backfill		m	10.0		
b)	1350mm, C76 CLV RCP					
i)	trenchless installation, Class B sand bedding, Class 3 backfill		m	14.0		
A.4	Connecting to Existing Sewer	CW 2130				
a)	250mm to 250mm WWS		each	4		
c)	1050mm to 1050mm LDS		each	2		
c)	1350mm to 1350mm LDS		each	2		
d)	1350mm to 1350mm Interceptor		each	1		
A.5	Manholes	CW 2130				
a)	SD-010					
i)	1800mm dia. base - Interceptor		vert. m	81.0		
ii)	2700mm dia. base - Interceptor		vert. m	14.0		
iii)	1800mm dia. base – Land Drainage		vert. m	18.0		
iv)	2100mm dia. base – Land Drainage		vert. m	21.0		

FORM B: PRICES
 (See B9)

NORTHEAST INTERCEPTOR – STAGE VII

UNIT PRICES

ITEM NO.	DESCRIPTION	SPEC. REF.	UNIT	APPROX. QUANTITY	UNIT PRICE	AMOUNT
A.6	Abandon Existing Sewers with Flowable Fill	CW 2130	m ³	50.0		
A.7	Abandonment of existing manholes	CW 2130	each	2		
A.8	Sewer Inspection	CW 2130				
i)	1200mm Interceptor Sewer		m	1820.0		
ii)	1050mm Land Drainage Sewer		m	7.0		
iii)	1350mm Land Drainage Sewer		m	11.0		
A.9	Forcemain Renewal	CW 2130				
a)	250mm, C900 PVC Forcemain trenchless installation, Class B sand bedding, Class 5 backfill		m	10.0		
A.10	Connecting to Existing Forcemain					
e)	250mm to 250mm		each	1		
A.11	Fittings - Forcemain					
a)	Bends					
i)	250mm – 22.5° bend		each	1		
A.12	Watermain Renewal	CW 2110				
a)	200mm trenchless installation, Class B sand bedding, Class 3 backfill		m	30.0		
A.13	Fittings - Watermain	CW 2110				
a)	Tees					
i)	200mm X 200mm X 200mm		each	1		
b)	Bends					
i)	200mm - 45° bend		each	2		
c)	Reducers					
i)	200mm - 150mm		each	1		

FORM B: PRICES
 (See B9)

NORTHEAST INTERCEPTOR – STAGE VII

UNIT PRICES

ITEM NO.	DESCRIPTION	SPEC. REF.	UNIT	APPROX. QUANTITY	UNIT PRICE	AMOUNT
A.14	Connecting to Existing Watermains and Large Diameter Water Services	CW 2110				
a)	plug not existing (in-line connection)					
i)	150mm		each	1		
ii)	200mm		each	2		
A.15	Full Depth Partial Slab Patches	CW 2130				
a)	Removal					
i)	150mm reinforced concrete pavement		m ²	100.0		
ii)	200mm reinforced concrete pavement		m ²	100.0		
b)	Installation					
i)	150mm reinforced concrete pavement		m ²	100.0		
ii)	200mm reinforced concrete pavement		m ²	100.0		
A.16	Miscellaneous Concrete Slab Renewal	CW 3235				
a)	Sidewalk		m ²	200.0		
b)	Monolithic Median Slab		m ²	30.0		
A.17	Concrete Curb Renewal	CW 3240				
a)	Barrier curb		m	100.0		
b)	Ramp curb		m	30.0		
A.18	Construction of Asphaltic Concrete Overlays Type 1A	CW 3410	tonne	20.0		
A.19	Construction of Asphaltic Concrete Pavement Type 1A	CW 3410	tonne	20.0		
A.20	Crushed Sub-Base Material	CW 3110				
i)	50mm Limestone		tonne	115.0		
A.21	Supply and Placing Base Course Material	CW 3110	m ³	20.0		
A.22	Granular backfill	E5	m ³	50.0		

FORM B: PRICES
 (See B9)

NORTHEAST INTERCEPTOR – STAGE VII

UNIT PRICES

ITEM NO.	DESCRIPTION	SPEC. REF.	UNIT	APPROX. QUANTITY	UNIT PRICE	AMOUNT
A.23	Cement Stabilized Fill	E5	m ³	50.0		
A.24	Regrading Existing Sewer Service – Up to 1.5 Metres Long	CW 2110				
a)	150mm		each	15		
b)	250mm		each	10		
A.25	Regrading Existing Interlocking Paving Stone Installations	CW 3330	m ²	20.0		
A.26	Adjustment of Precast Sidewalk Blocks	CW 3235	m ²	10.0		
A.27	Supply of Precast Sidewalk Blocks	CW 3235	m ²	10.0		
A.28	Supply of Extendible Curb Stop Sections	CW 3210	each	5		
A.29	Sodding	CW 3510	m ²	500.0		
A.30	Surfacing Material	CW 3150				
a)	Granular		tonne	10.0		
b)	Limestone		tonne	10.0		
A.31	Remove and Replace Chain Link Fence	E10				
a)	1.83 metres		m	50.0		
A.32	Installation of Interior Drop Sections	E12	each	4		
Part A Subtotal:						
TOTAL BID PRICE (GST extra) (in figures) \$ _____						
(in words) _____						

 Name of Bidder