CP-H11A	Generator Communication Panel					
Rev.	Comments	Jumper or Internal Cable	Conductor #	Cable	Cable Infor	
		F	PP1			
0	Plant Control Network Receive	Switch 1: 07	01 01	C-CP-H11A-C01	24-Strand 5	
0	Plant Control Network Transmit	Switch 1: 07	02 02			
2	Remote I/O Network Receive	RIO Repeater 1: 01	03 03			
2	Remote I/O Network Transmit	RIO Repeater 1: 01	04 04			
0	Plant Monitoring Network Receive	Switch 2: 07	05 05			
0	Plant Monitoring Network Transmit	Switch 2: 07	06 06			
0	Spare		07 07			
0	Spare		08 08			
3	City of Winnipeg LAN		09 09			
3	City of Winnipeg LAN		10 10			
3	Fire Alarm		11 11			
3	Fire Alarm		12 12			
3	Security		13 13			
3	Security		14 14			
5	Remote I/O Network Receive	RIO Repeater 2: 01	15 15			
5	Remote I/O Network Transmit	RIO Repeater 2: 01	16 16			
2	Spare		17 17			
2	Spare		18 18			
2	Spare		19 19			
2	Spare		20 20			
2	Spare		21 21			
2	Spare		22 22			
2	Spare		23 23			
2	Spare		24 24			

NOTES: 1. Panel and Cabling are not in Contract 742-2005. Drawing Issued for Information Only. 2. Panel and Cabling are in Contract 498-2006.	B.M. ELEV.			CH2MHILL Frederickson Cooper		EarthTech		ENGINEER'S SEAL ORIGINAL SIGNED BY	THE CITY OF WINNIPEG water and waste department engineering division		
	4 498-20 3 FOR C	06 ADDENDUM 2 CONSTRUCTION	06/09/22 BT 06/07/28 BT	DESIGNED BY S DRAWN BY	SWT	CHECKED BY SWT S.W. TORMEY 2006/03/29 APPROVED PY AHL		WATER TREATMENT PLANT PLANT UTILITIES MECHANICAL AND ELECTRICAL	CITY FILE NUMBER SHEET OF 115 130		
Certificate of Authorization Earth Tech Canada Inc. No. 730 Expiry: April 30, 2006.	1 742-20 0 ISSUEI	05 ADDENDUM 6 D FOR TENDER	06/03/29	SWT		NTS	RELEASED FO CONSTRUCTIO R. SOROK	ON BY: KOWSKI	CONSULTANT DRAWING NO.	AUTOMATION / I AND C PLANT COMMUNICATION CABLE	CITY DRAWING NUMBER
	NO. REVIS	SIONS	DATE	BY	DATE	2006/03/29	DATE 20	006/03/29	WH-A0615	TERMINATION DIAGRAMS	1-0601H-J-A0615-001-05

Friday, October 13, 2006

formation

1 50/125/250 um Multi-mode TO LCP-T11A