

269-2007 ADDENDUM 1

Supply & Install Tiles in Transcona Pool–1101 Wabasha

URGENT

**PLEASE FORWARD THIS DOCUMENT TO
WHOEVER IS IN POSSESSION OF THE BID
OPPORTUNITY**

ISSUED: May 7, 2007
BY: Stu McConnell
TELEPHONE NO. (204) 794-4416

**THIS ADDENDUM SHALL BE INCORPORATED
INTO THE BID OPPORTUNITY AND SHALL
FORM A PART OF THE CONTRACT
DOCUMENTS**

Template Version: A20070419

Please note the following and attached changes, corrections, additions, deletions, information and/or instructions in connection with the Bid Opportunity, and be governed accordingly. Failure to acknowledge receipt of this Addendum in Paragraph 8 of Form A: Bid may render your Bid non-responsive.

PART E – SPECIFICATIONS

- Revise: E1.3 (a) Contractor will sand blast entire vertical surface and shot blast horizontal surfaces to remove any and all old painted surfaces to clean substrate. Extra caution must be used to remove any and all old painted surfaces to clean substrate. Extra caution must be used to remove areas of loose "shot". In addition, pool openings (eg: drains, return diffusers, vacuum plugs, etc.) will be plugged by contractor to avoid blockages from shot media or paint. When sandblasting, the pool should be tented or covered to contain the sand and dust. All sand, residue and dust must be removed from the entire pool area upon completion of the project.
- Revise: E1.3 (f) Contractor must erect a snow fence barrier around perimeter of pool. The fence barrier around the perimeter of the pool should be securely anchored at the corners and every 15 ft. o.c.
- Revise: E1.3 (g) Contractor will supply 2"x2" Unglazed (dot mount) Mosaic Porcelain Pool Tile equal to Dal Keystones, White D317 (Colour Group 1) as the field colour and Dal Keystones, Ebony D311 (Colour Group 3) for the Black Lane markings as per existing to cover the surface of the pool in it's entirety. Supply and install new black bull nosing and new tiles to match the pool tiles to the pool apron around the perimeter of the pool edge. Extend the black line at the deep end vertical wall to the floor level and create a "cross" at the top in tile. Create a 4' wide tiled line at the deep end drop off which goes across the width of the pool. Tile the interior of the scuppers. Tiled depth marks, in 1" black tiled lettering must be in meters and addition depth marker signs must be installed on the pool wall above the water line in accordance to Public Health Act P210_R.M. 132/97 Sect 7(4) and Sections 20 (1), (2) and (2)(b). "no diving" in 1" black tile lettering must be supplied and installed in accordance to the Act. Locations to be discussed with the Contract Administrator.
- Revise: E1.3 (k) Contractor will remove existing paint and coatings by shot blast (Blastrac) down to sound, clean concrete and a skim coat (s) of Thinset Mortar with Polymer Additive equal to Mapei Kerabond White with Keraply Additive to provide a smooth, sound substrate for the tile and Polymer Modified Grout equal to Mapei KER 700 Ultra/Colour (White).
- Revise: E1.3 (n) Setting Mortar Use White Kerabond c/w Keraply Additive for the Latex_Portland Thinset Mortar: to ANSI A118.4, two component, liquid latex mixed with factory-blended dry-set mortar.
- Add: E1.3 (p) "The Contractor will be responsible to repair or replace the control joint between the floor and the wall of the pool with an acceptable grout conducive to pool work.