



MAIN FLOOR PLAN - PLUMBING RENOVATION
 SCALE: 1/4"=1'-0"

PLUMBING DEMOLITION NOTES

REMOVE ALL EXISTING PLUMBING LINES, FIXTURES AND VALVES BACK TO SOURCE.

PLUMBING RENOVATION NOTES:

SUPPLY & INSTALL, UNLESS OTHERWISE NOTED.

- 1 CONTINUE ON DRAWING M5.
- 2 NEW PLUMBING VENT THROUGH ROOF. PENETRATION THROUGH ROOF SHALL BE WATER TIGHT AND IN ACCORDANCE TO THE LATEST BUILDING CODE AND ROOFING STANDARD.
- 3 PLUMBING DWV STACK SHALL BE PLUMBED AND CENTERED WITH NEW BASEMENT SHOWER WALL & MAIN FLOOR WASHROOM WALL TO CONNECT TO EXISTING VENT STACK AT ROOF. TRANSITION CONNECTION FROM BASEMENT WALL INTO MAIN FLOOR WALL.

NOTES :
 SEE NOTES ON DRAWING M1.

ORIGINAL STAMPED BY: DOUG PALEY, P. ENG.
 DATE: 2007.11.15

1 SEE ADDENDUM 4, BID OPPORTUNITY 629-2007. ADDED P-15 & REVISED SANITARY SEWER AND VENT. DTA 2007.11.15

NO.	REVISION/DESCRIPTION	BY	DATE

DRAWN BY	RCPI/DTA	CHECKED BY	APPROVED

CITY OF WINNIPEG
 PLANNING, PROPERTY & DEVELOPMENT DEPARTMENT
 CIVIC ACCOMMODATIONS DIVISION
 300 - 65 GARRY ST. R3C 4K4

PROJECT
 COMMUNITY POLICE SERVICE CENTRE

1400 HENDERSON HWY.

SHEET TITLE
 MAIN FLOOR PLAN
 PLUMBING
 DEMOLITION AND RENOVATION

SCALE	PROJECT NO.	SHEET NO.
AS SHOWN	2004-023	M6R1