



699-2007 ADDENDUM 1

CITY OF WINNIPEG PLAYGROUND RENOVATIONS – PLAY EQUIPMENT

URGENT

**PLEASE FORWARD THIS DOCUMENT TO
WHOEVER IS IN POSSESSION OF THE BID
OPPORTUNITY**

ISSUED: October 23, 2007
BY: Derek Murray
TELEPHONE NO. (204) 927-3444

**THIS ADDENDUM SHALL BE INCORPORATED
INTO THE BID OPPORTUNITY AND SHALL
FORM A PART OF THE CONTRACT
DOCUMENTS**

Template Version: A20070419

Please note the following and attached changes, corrections, additions, deletions, information and/or instructions in connection with the Bid Opportunity, and be governed accordingly. Failure to acknowledge receipt of this Addendum in Paragraph 8 of Form A: Bid may render your Bid non-responsive.

PART A – BID SUBMISSION

Replace: 699-2007 Bid Submission with 699-2007 Addendum 1 - Bid Submission. The following is a summary of changes incorporated in the replacement Bid Submission:

Form B(R1): Revise unit of measure for Items A3, B5 and C2.

Page numbering on some forms may be changed as a result.

PART D – SUPPLEMENTAL CONDITIONS

Revise: D3.1(b) to read:

(b) "CSA" means "**Canadian** Standards Association".

PART E – SPECIFICATIONS

Revise: E20.3.2(a)(ii) to read:

(ii) Contact for FibarSystem 300:

The Fibar Group LLC

80 Business Park Drive, Suite 300

Armonk, NY 10504-1705

USA

Ph: (800) 342-2721

Fax: (914) 273-8659

info@FibarPlaygrounds.com

Revise: E20.3.3 to read:

E20.3.3 Construction Methods

(a) Wood Fibre shall be installed within the play area, as defined by the timber edging (supplied and installed by others), to a minimum depth of 200 mm (**after compaction**). In play areas where maximum fall height is greater than 2.4m (8'), depth of material to directly correspond to maximum fall height of play equipment in accordance with manufacturer's specifications.

- (b) The installation of the Wood Fibre shall be done immediately after the play equipment has been installed.
- (c) Installation of entire system, including fibre, filter cloth, subsurface drainage and mats shall be done according manufacturer's instructions. Adequate drainage within play equipment area must be ensured as per same.
- (d) Installation shall be done by equipment sized to suit the Work being done and the Wood Fibre shall be spread by hand as necessary in the immediate vicinity of the play equipment so as not to damage same. The play equipment shall be swept clean to the satisfaction of the Contract Administrator after installation of the Wood Fibre.

Revise: E20.4.1 to read:

E20.4.1 Method of Measurement shall be as follows:

- (a) Protective Surfacing will be measured on a cubic metre basis for Items A.1, B.3, C.4 and D.4 listed as "Play stone...." on Form B: Prices.
- (b) Protective Surfacing will be measured on a **square** metre basis for Items A.3, B.5 and C.2 listed as "Wood Fibre Surfacing System" on Form B: Prices.