TABLE OF CONTENTS (R3)

Section No.Description01 33 00Submittal Procedures01 42 00References06 10 10Rough Carpentry07 59 60Existing Roof Modification for New Work07 44 00Firestopping and Smoke Seals07 92 10Joint Sealants08 11 14Steel Doors and Frames08 70 00Finish Hardware09 25 00Gypsum Board09 67 60Epoxy Floorings09 91 00Finish Painting21 13 13Wet-Pipe Sprinkler Systems21 24 16Dry-Chemical Fire-Extinguishing Equipment22 05 20Valves and Strainers22 05 21Valves and Strainers22 05 22Valves and Strainers22 05 23Valves and Strainers22 06 00Common Work Results for Plumbing Pulping and Equipment22 06 10.13Plumbing Pulping Schedule22 08 00Commissioning of Plumbing22 13 33Packaged, Submersible Severage Pump23 05 01Common Work Results for Mechanical30 51 6Expansion Fittings and Loops for HVAC Piping33 05 19Meters and Gauges for HVAC Piping and Equipment23 05 29Hangers and Supports for HVAC Piping30 62 0.16 (R1)Circuit Balancing Valve Schedule30 62 0.16 (R1)Circuit Balancing Valve Schedule30 62 0.16 (R1)Circuit Balancing Valve Schedule30 63 0.19Air Outlet and Inlet Schedule30 63 0.19Air Outlet and Inlet Schedule30 63 0.10Air Outlet and Inlet Schedule30 63 0.11Air Outlet an		
01 42 00References06 10 10Rough Carpentry07 59 60Existing Roof Modification for New Work07 84 00Firestopping and Smoke Seals07 92 10Joint Sealants08 11 14Steel Doors and Frames08 70 00Finish Hardware09 25 00Gypsum Board09 67 60Epoxy Floorings09 91 00Finish Painting21 13 13Wet-Pipe Sprinkler Systems21 24 16Dry-Chemical Fire-Extinguishing Equipment22 05 23Valves and Strainers22 05 24Valves and Strainers22 05 25Hangers and Supports for Plumbing22 05 26Valves and Strainers22 05 27Hangers and Supports for Plumbing Piping and Equipment22 05 00Commos Work Results for Plumbing22 13 16Sanitary Waste and Vent Piping23 00Plumbing Equipment23 05 01Common Work Results for Mechanical23 05 10Common Work Results for Mechanical23 05 29Hangers and Supports for HVAC Piping23 05 29Hangers and Supports for HVAC Piping23 05 29Hangers and Supports for HVAC Piping23 05 20:13 (R1)Hydronic Pump Schedule23 06 20:16 (R1)Circuit Balancing Valve Schedule23 06 20:16 (R1)Circuit Balancing Valve Schedule23 06 20:13 (R1)Hydronic Pump Schedule23 06 20:13 (R1)	Section No.	Description
06 10 10Rough Carpentry07 59 60Existing Roof Modification for New Work07 84 00Firestopping and Smoke Seals07 92 10Joint Sealants08 11 14Steel Doors and Frames08 70 00Finish Hardware09 25 00Gypsum Board09 97 60Epoxy Floorings21 13 13Wet-Pipe Sprinkler Systems21 24 16Dry-Chemical Fire-Extinguishing Equipment22 05 01Common Work Results for Plumbing22 05 23Valves and Strainers22 06 101Ommon Work Results for Plumbing Piping and Equipment22 06 20Common Work Results for Plumbing Piping and Equipment22 06 101Ommon Work Results for Mechanical20 800Commissioning of Plumbing21 13 13Packaged, Submersible Severage Pump22 13 23Packaged, Submersible Severage Pump23 05 01Common Work Results for Mechanical23 05 16Expansion Fittings and Loops for HVAC Piping23 05 17Meters and Gauges for HVAC Piping and Equipment23 05 29Hangers and Supports for HVAC Piping23 06 20.13 (R1)Hydronic Pump Schedule23 06 20.13 (R1)Hydronic Pump Schedule23 06 20.13 (R1)Condensing Boiler Schedule23 06 21.19Tank Schedule23 06 20Air Coil Schedule23 07 19HVAC Piping Insulation23 08 00Commissioning of Mechanical23 08 02Cleaning Of Mechanical23 09 03Sequence of Operations for HVAC23 09 33 13Controls Points List <td>01 33 00</td> <td>Submittal Procedures</td>	01 33 00	Submittal Procedures
07 59 60Existing Roof Modification for New Work07 84 00Firestopping and Smoke Seals07 92 10Joint Sealants08 11 14Steel Doors and Frames08 70 00Finish Hardware09 25 00Gypsum Board09 67 60Epoxy Floorings09 91 00Finish Painting21 13 13Wet-Pipe Sprinkler Systems21 24 16Dry-Chemical Fire-Extinguishing Equipment22 05 01Common Work Results for Plumbing20 52Valves and Strainers22 05 12Valves and Strainers22 05 20Hangers and Supports for Plumbing Piping and Equipment22 06 10.13Plumbing Pump Schedule22 08 00Commissioning of Plumbing23 13 16Sanitary Waste and Vent Piping23 05 01Common Work Results for Mechanical23 05 10Common Work Results for Mechanical23 05 11Common Work Results for Mechanical23 05 12Hangers and Supports for HVAC Piping23 05 29Hangers and Supports for HVAC Piping23 05 29Hangers and Supports for HVAC Piping23 06 20.13 (R1)Hydronic Pump Schedule23 06 20.13 (R1)Circuit Balancing Valve Schedule23 06 20.13 (R1)Condensing Boiler Schedule23 06 80.23Air Coil Schedule23 06 80.23Air Coil Schedule23 06 80.23Air Coil Schedule23 06 80.23Air Coil Schedule23 07 19HVAC Piping Insulation23 08 20Cleaning of HVAC Piping23 08 20Cleaning of HVAC Piping<	01 42 00	References
07 84 00Firestopping and Smoke Seals07 92 10Joint Sealants08 11 14Steel Doors and Frames08 70 00Finish Hardware09 25 00Gypsum Board09 67 60Epoxy Floorings09 91 00Finish Painting21 13 13Wet-Pipe Sprinkler Systems21 24 16Dry-Chemical Fire-Extinguishing Equipment22 05 01Common Work Results for Plumbing22 05 23Valves and Strainers22 05 29Hangers and Supports for Plumbing Piping and Equipment22 06 10.13Plumbing Pump Schedule22 08 00Commissioning of Plumbing22 13 16Sanitary Waste and Vent Piping23 05 01Common Work Results for Mechanical23 05 01Common Work Results for Mcchanical23 05 16Expansion Fittings and Loops for HVAC Piping23 05 19Meters and Gauges for HVAC Piping and Equipment23 05 29Hangers and Supports for HVAC Piping and Equipment23 05 20Sangers and Supports for HVAC Piping23 06 20.13 (R1)Hydronic Pump Schedule23 06 21.16Plate and Frame Heat Exchanger Schedule23 06 22.13 (R1)Condensing Boiler Schedule23 06 30.13 (R1)Condensing Boiler Schedule23 06 30Air Coil Schedule23 07 19HVAC Piping23 08 00Commissioning of Mechanical23 09 00Instrumentation and Control for HVAC23 09 33 (R2)Electric and Electronic Control Systems for HVAC23 09 33 (R2)Electric and Electronic Control Systems for HVAC </td <td>06 10 10</td> <td>Rough Carpentry</td>	06 10 10	Rough Carpentry
07 92 10Joint Sealants08 11 14Steel Doors and Frames08 70 00Finish Hardware09 25 00Gypsum Board09 97 00Finish Painting21 13 13Wet-Pipe Sprinkler Systems21 24 16Dry-Chemical Fire-Extinguishing Equipment22 05 01Common Work Results for Plumbing22 05 23Valves and Strainers22 05 29Hangers and Supports for Plumbing Piping and Equipment22 05 20Common Work Results for Plumbing Piping and Equipment22 06 10.13Plumbing Pump Schedule23 00Commissioning of Plumbing23 13 16Sanitary Waste and Vent Piping23 05 01Common Work Results for Mechanical23 05 01Common Work Results for Mechanical23 05 01Common Work Results for HVAC Piping23 05 10Meters and Gauges for HVAC Piping23 05 29Hangers and Supports for HVAC Piping23 06 20.13 (R1)Hydronic Pump Schedule23 06 20.16 (R1)Circuit Balancing Valve Schedule23 06 20.13 (R1)Gomesing Boiler Schedule23 06 80.23Air Coil Schedule23 07 19HVAC Piping Insulation23 08 00Commissioning of Mechanical23 09 00Instrumentation and Control for HVAC23 09 33.13Controls Points List23 09 33.13Controls Points List23 09 33.13Hydronic Pumps23 11 23Natural Gas Piping23 21 13.1Hydronic Pumps23 21 14Hydronic Pumps23 21 13Hydronic Pumps <td>07 59 60</td> <td>Existing Roof Modification for New Work</td>	07 59 60	Existing Roof Modification for New Work
08 11 14Steel Doors and Frames08 70 00Finish Hardware09 25 00Gypsum Board09 67 60Epoxy Floorings09 91 00Finish Painting21 13 13Wet-Pipe Spinkler Systems21 24 16Dry-Chemical Fire-Extinguishing Equipment22 05 20Valves and Strainers22 05 23Valves and Strainers22 05 29Hangers and Supports for Plumbing Piping and Equipment22 05 00Common Work Results for Plumbing Piping and Equipment22 05 01Sanitary Waste and Vent Piping21 13 16Sanitary Waste and Vent Piping21 33Packaged, Submersible Sewerage Pump22 30 00Plumbing Equipment23 05 01Common Work Results for Mechanical23 05 16Expansion Fittings and Loops for HVAC Piping23 05 29Hangers and Supports for HVAC Piping and Equipment23 05 20Hangers and Supports for HVAC Piping and Equipment23 05 20Hangers and Supports for HVAC Piping and Equipment23 05 23Testing, Adjusting and Balancing for HVAC23 06 20.13 (R1)Hydronic Pump Schedule23 06 20.13 (R1)Condensing Boiler Schedule23 06 30.13 (R1)Condensing Boiler Schedule23 07 19HVAC Piping Insulation23 08 00Commissioning of Mechanical23 09 33 (R2)Electric and Electronic Control Systems for HVAC23 09 33 (R2)Electric and Electronic Control Systems for HVAC23 09 33 (R2)Electric and Strainers23 11 23Natural Gas Piping23 21 13 <td>07 84 00</td> <td>Firestopping and Smoke Seals</td>	07 84 00	Firestopping and Smoke Seals
0870Finish Hardware099200Gypsum Board099100Finish Painting2113Wet-Pipe Spinkler Systems212416Dry-Chemical Fire-Extinguishing Equipment220501Common Work Results for Plumbing220523Valves and Strainers220523Valves and Strainers220523Valves and Strainers220529Hangers and Supports for Plumbing Piping and Equipment220520Commissioning of Plumbing2113Sanitary Waste and Vent Piping2213Sanitary Waste and Vent Piping2300Plumbing Equipment2300Plumbing Equipment230516Expansion Fittings and Loops for HVAC Piping230519Meters and Gauges for HVAC Piping230529Hangers and Supports for HVAC Piping and Equipment230529Testing, Adjusting and Balancing for HVAC230620.16 (R1)Circuit Balancing Valve Schedule230621.16Plate and Frame Heat Exchanger Schedule230620.13 (R1)Hydronic Pump Schedule230620.13 (R1)Condensing Boller Schedule230621.16Plate and Frame Heat Exchanger Schedule230621.16Plate and Frame Heat230800Cormisioning of Mechanical <td>07 92 10</td> <td>Joint Sealants</td>	07 92 10	Joint Sealants
0925 00Gypsum Board0991 00Finish Painting2113Wet-Pipe Sprinkler Systems21 1313Wet-Pipe Sprinkler Systems21 24 16Dry-Chemical Fire-Extinguishing Equipment22 05 01Common Work Results for Plumbing22 05 23Valves and Strainers22 05 29Hangers and Supports for Plumbing Piping and Equipment22 05 11Commissioning of Plumbing22 13 16Sanitary Waste and Vent Piping23 13 16Sanitary Waste and Vent Piping23 00Plumbing Equipment23 05 01Common Work Results for Mechanical23 05 16Expansion Fittings and Loops for HVAC Piping23 05 17Common Work Results for Mechanical23 05 29Hangers and Supports for HVAC Piping23 05 29Hangers and Supports for HVAC Piping and Equipment23 05 29Testing, Adjusting and Balancing for HVAC23 06 20.13 (R1)Circuit Balancing Valve Schedule23 06 21.16Piate and Frame Heat Exchanger Schedule23 06 80.23Air Coil Schedule23 06 80.23Air Coil Schedule23 07 19HVAC Piping Insulation23 08 00Commissioning of Mechanical23 09 20Instrumentation and Control for HVAC23 09 33Requence of Operations for HVAC Piping23 09 33Sequence of Operations for HVAC23 09 33Requence of Operations for HVAC23 09 33Sequence of Operations for HVAC23 09 33Sequence of Operations for HVAC23 09 33	08 11 14	Steel Doors and Frames
0925 00Gypsum Board0991 00Finish Painting2113Wet-Pipe Sprinkler Systems21 1313Wet-Pipe Sprinkler Systems21 24 16Dry-Chemical Fire-Extinguishing Equipment22 05 01Common Work Results for Plumbing22 05 23Valves and Strainers22 05 29Hangers and Supports for Plumbing Piping and Equipment22 05 11Commissioning of Plumbing22 13 16Sanitary Waste and Vent Piping23 13 16Sanitary Waste and Vent Piping23 00Plumbing Equipment23 05 01Common Work Results for Mechanical23 05 16Expansion Fittings and Loops for HVAC Piping23 05 17Common Work Results for Mechanical23 05 29Hangers and Supports for HVAC Piping23 05 29Hangers and Supports for HVAC Piping and Equipment23 05 29Testing, Adjusting and Balancing for HVAC23 06 20.13 (R1)Circuit Balancing Valve Schedule23 06 21.16Piate and Frame Heat Exchanger Schedule23 06 80.23Air Coil Schedule23 06 80.23Air Coil Schedule23 07 19HVAC Piping Insulation23 08 00Commissioning of Mechanical23 09 20Instrumentation and Control for HVAC23 09 33Requence of Operations for HVAC Piping23 09 33Sequence of Operations for HVAC23 09 33Requence of Operations for HVAC23 09 33Sequence of Operations for HVAC23 09 33Sequence of Operations for HVAC23 09 33	08 70 00	Finish Hardware
09 67 60Epoxy Floorings09 91 00Finish Painting21 13 13Wet-Pipe Sprinkler Systems21 24 16Dry-Chemical Fire-Extinguishing Equipment22 05 23Valves and Strainers22 05 23Valves and Supports for Plumbing Piping and Equipment22 06 10.13Plumbing Pump Schedule20 800Common Work Results for Plumbing21 13 13Packaged, Submersible Sewerage Pump22 13 33Packaged, Submersible Sewerage Pump23 000Plumbing Equipment23 05 01Common Work Results for McCanical23 05 16Expansion Fittings and Loops for HVAC Piping23 05 29Hangers and Supports for HVAC Piping and Equipment23 05 29Hangers and Supports for HVAC Piping23 06 20.13 (R1)Hydronic Pump Schedule23 06 20.13 (R1)Circuit Balancing Valve Schedule23 06 21.16Plate and Frame Heat Exchanger Schedule23 06 20.16 (R1)Condensing boiler Schedule23 06 30.19Air Coil Schedule23 07 19HVAC Piping23 08 00Commissioning of Mechanical23 08 02Cleaning of HVAC Piping23 09 33Sequence o		Gypsum Board
09 91 00Finish Painting21 13 13Wet-Pipe Sprinkler Systems21 24 16Dry-Chemical Fire-Extinguishing Equipment22 05 01Common Work Results for Plumbing22 05 23Valves and Strainers22 05 29Hangers and Supports for Plumbing Piping and Equipment22 06 10.13Plumbing Pump Schedule22 08 00Commissioning of Plumbing23 13 16Sanitary Waste and Vent Piping24 13 33Packaged, Submersible Sewerage Pump23 00Plumbing Equipment23 05 01Common Work Results for Mechanical23 05 11Common Work Results for Mechanical23 05 29Hangers and Supports for HVAC Piping23 05 29Hangers and Supports for HVAC Piping and Equipment23 05 29Hangers and Supports for HVAC Piping and Equipment23 06 20.13 (R1)Hydronic Pump Schedule23 06 21.16Plate and Frame Heat Exchanger Schedule23 06 21.17Tank Schedule23 06 80.23Air Outlet and Inlet Schedule23 06 80.23Air Outlet and Inlet Schedule23 07 19HVAC Piping23 08 00Commissioning of Mechanical23 09 90Instrumentation and Control for HVAC23 09 93Sequence of Operations for HVAC Controls23 11 23Natural Gas Piping23 21 13.13Hydronic Piping23 21 13.14Hydronic Piping23 21 13.15Fire Dampers23 21 13.16Fire Dampers23 21 13.13Hydronic Piping23 21 13.14Filters23 21 13.1		
2113Wet-Pipe Sprinkler Systems212416Dry-Chemical Fire-Extinguishing Equipment220501Common Work Results for Plumbing220523Valves and Strainers220529Hangers and Supports for Plumbing Piping and Equipment220529Hangers and Supports for Plumbing211316Sanitary Waste and Vent Piping221333Packaged, Submersible Sewerage Pump2300Plumbing Equipment230516Expansion Fittings and Loops for HVAC Piping230516Expansion Fittings and Loops for HVAC Piping23059Hangers and Supports for HVAC Piping and Equipment23059Testing, Adjusting and Balancing for HVAC23060.13 (R1)Hydronic Pump Schedule230620.16 (R1)Circuit Balancing Valve Schedule230621.16Plate and Frame Heat Exchanger Schedule230630.19Air Coultet and Inlet Schedule230630.13 (R1)Condensing Boiler Schedule230630.13 (R1)Condensing of Mechanical23080Commissioning of Mechanical23080Commissioning of Mechanical23080Commissioning of Mechanical23080Commissioning of Mechanical23080Commissioning of Mechanical2308		
21 24 16Dry-Chemical Fire-Extinguishing Equipment22 05 01Common Work Results for Plumbing22 05 23Valves and Strainers22 05 29Hangers and Supports for Plumbing Piping and Equipment22 06 10.13Plumbing Pump Schedule22 08 00Commissioning of Plumbing22 13 16Sanitary Waste and Vent Piping22 13 33Packaged, Submersible Sewerage Pump23 05 01Common Work Results for Mechanical23 05 16Expansion Fittings and Loops for HVAC Piping23 05 19Meters and Gauges for HVAC Piping and Equipment23 05 29Hangers and Supports for HVAC Piping and Equipment23 05 29Hangers and Supports for HVAC Piping and Equipment23 05 20Testing, Adjusting and Balancing for HVAC23 06 20.13 (R1)Hydronic Pump Schedule23 06 21.16Plate and Frame Heat Exchanger Schedule23 06 20.13 (R1)Condensing Boiler Schedule23 06 80.23Air Coli Schedule23 07 19HVAC Piping Insulation23 08 00Commissioning of Mechanical23 08 02Cleaning of HVAC Piping23 09 33.13Controls Points List23 09 93Sequence of Operations for HVAC Controls23 11 23Natural Gas Piping23 21 13.13Hydronic Valves and Strainers23 21 13.13Hydronic Specialties23 21 13.13Hydronic Piping23 21 13.13Hydronic Piping23 21 13.13Hydronic Palers23 21 13.14Fire Dampers23 21 13.15Fire Dampers <td< td=""><td></td><td>5</td></td<>		5
22 05 01Common Work Results for Plumbing22 05 23Valves and Strainers22 05 29Hangers and Supports for Plumbing Piping and Equipment22 06 10.13Plumbing Pump Schedule22 08 00Commissioning of Plumbing22 13 31Packaged, Submersible Sewerage Pump22 30 00Plumbing Equipment23 05 01Common Work Results for Mechanical23 05 01Common Work Results for Mechanical23 05 01Common Work Results for HVAC Piping23 05 16Expansion Fittings and Loops for HVAC Piping23 05 29Hangers and Supports for HVAC Piping and Equipment23 05 29Hangers and Supports for HVAC Piping and Equipment23 06 20.13 (R1)Hydronic Pump Schedule23 06 20.16 (R1)Circuit Balancing Valve Schedule23 06 30.19Air Cottle Balancing Valve Schedule23 06 30.19Air Cottle Balancing Valve Schedule23 07 19HVAC Piping Insulation23 08 00Commissioning of Mechanical23 08 00Commissioning of Mechanical23 08 00Commissioning of Mechanical23 09 33 (R2)Electric and Electronic Control Systems for HVAC23 09 33 (R2)Electric and Strainers23 11 3Hydronic Piping23 21 13.13Hydronic Valves and Strainers23 21 13.14Hydronic Valves and Strainers23 21 13.15Filters23 25 16.13Condensing Boilers23 25 71 9.13Plate and Frame Heat Exchangers		
22 05 23Valves and Strainers22 05 29Hangers and Supports for Plumbing Piping and Equipment22 06 10.13Plumbing Pump Schedule22 08 00Commissioning of Plumbing22 13 16Sanitary Waste and Vent Piping22 13 33Packaged, Submersible Sewerage Pump23 00Plumbing Equipment23 05 01Common Work Results for Mechanical23 05 16Expansion Fittings and Loops for HVAC Piping23 05 19Meters and Gauges for HVAC Piping and Equipment23 05 29Hangers and Supports for HVAC Piping and Equipment23 05 29Hangers and Supports for HVAC Piping and Equipment23 05 20Testing, Adjusting and Balancing for HVAC23 06 20.13 (R1)Hydronic Pump Schedule23 06 20.16 (R1)Circuit Balancing Valve Schedule23 06 20.13 (R1)Hydronic Pump Schedule23 06 30.19Air Outlet and Inlet Schedule23 06 30.19Air Coull Schedule23 07 19HVAC Piping Insulation23 08 00Commissioning of Mechanical23 09 33 (R2)Electric and Electronic Control Systems for HVAC23 09 33 (R2)Electric and Electronic Soft HVAC Controls23 11 23Natural Gas Piping23 21 13.1Hydronic Pumps23 21 13.1Hydronic Pumps23 31 13Metal Ducts23 33 13.16Fire Dampers23 41 13Panel Air Filters23 57 19.13Plate and Frame Heat Exchangers		
22Use of 29Hangers and Supports for Plumbing Piping and Equipment220610.13Plumbing Pump Schedule220800Commissioning of Plumbing221331Packaged, Submersible Sewerage Pump233000Plumbing Equipment230501Common Work Results for Mechanical230516Expansion Fittings and Loops for HVAC Piping230529Hangers and Supports for HVAC Piping and Equipment230529Hangers and Supports for HVAC Piping230529Hangers and Supports for HVAC Piping230620.13 (R1)Circuit Balancing Valve Schedule230621.16Plate and Frame Heat Exchanger Schedule230620.13 (R1)Condensing Boiler Schedule230680.23Air Coil Schedule230680.23Air Coil Schedule230719HVAC Piping Insulation230800Instrumentation and Control for HVAC230933Sequence of Operations for HVAC Controls		
22 06 10.13Plumbing Pump Schedule20 8 00Commissioning of Plumbing21 3 16Sanitary Waste and Vent Piping21 3 33Packaged, Submersible Sewerage Pump23 00Plumbing Equipment23 05 01Common Work Results for Mechanical23 05 16Expansion Fittings and Loops for HVAC Piping23 05 19Meters and Gauges for HVAC Piping and Equipment23 05 29Hangers and Supports for HVAC Piping and Equipment23 05 29Testing, Adjusting and Balancing for HVAC23 06 20.13 (R1)Hydronic Pump Schedule23 06 20.16 (R1)Circuit Balancing Valve Schedule23 06 20.13 (R1)Plate and Frame Heat Exchanger Schedule23 06 30.19Air Outlet and Inlet Schedule23 06 30.19Air Outlet and Inlet Schedule23 06 80.23Air Coil Schedule23 07 19HVAC Piping Insulation23 08 00Commissioning of Mechanical23 09 00Instrumentation and Control for HVAC23 09 33 (R2)Electroic and Electronic Control Systems for HVAC23 09 33 (R2)Electroic and Electronic Control Systems for HVAC23 09 33Sequence of Operations for HVAC Controls23 11 23Natural Gas Piping23 21 13.1Hydronic Pumps23 11 3Metal Ducts23 11 3Metal Ducts23 11 3Ait Ducts23 21 13.1Panel Air Filters23 25 16.13Condensing Boilers23 57 19.13Plate and Frame Heat Exchangers		
22 08 00Commissioning of Plumbing22 13 16Sanitary Waste and Vent Piping22 13 33Packaged, Submersible Sewerage Pump23 00Plumbing Equipment23 05 01Common Work Results for Mechanical23 05 16Expansion Fittings and Loops for HVAC Piping23 05 17Meters and Gauges for HVAC Piping23 05 29Hangers and Supports for HVAC Piping and Equipment23 05 29Testing, Adjusting and Balancing for HVAC23 06 20.13 (R1)Hydronic Pump Schedule23 06 20.16 (R1)Circuit Balancing Valve Schedule23 06 21.16Plate and Frame Heat Exchanger Schedule23 06 20.13 (R1)Condensing Boiler Schedule23 06 21.19Tank Schedule23 06 50.13 (R1)Condensing Boiler Schedule23 06 60.23Air Cutlet and Inlet Schedule23 07 19HVAC Piping Insulation23 08 00Commissioning of Mechanical23 09 00Instrumentation and Control for HVAC23 09 33 (R2)Electric and Electronic Control Systems for HVAC23 09 33 (R2)Electric and Electronics for HVAC Controls23 11 23Natural Gas Piping23 21 13.11Hydronic Pumps23 11 13Hydronic Pumps23 11 13Metal Ducts23 21 13.13Metal Ducts23 21 13.14Filterrs23 25 26.13Condensing Boilers23 35 7 19.13Plate and Frame Heat Exchangers		
22 13 16Sanitary Waste and Vent Piping22 13 33Packaged, Submersible Sewerage Pump23 05 00Plumbing Equipment23 05 01Common Work Results for Mechanical23 05 16Expansion Fittings and Loops for HVAC Piping23 05 19Meters and Gauges for HVAC Piping23 05 29Hangers and Supports for HVAC Piping and Equipment23 05 59Testing, Adjusting and Balancing for HVAC23 06 20.13 (R1)Hydronic Pump Schedule23 06 20.16 (R1)Circuit Balancing Valve Schedule23 06 20.16 (R1)Circuit Balancing Valve Schedule23 06 20.13 (R1)Plate and Frame Heat Exchanger Schedule23 06 30.19Air Outlet and Inlet Schedule23 06 50.13 (R1)Condensing Boiler Schedule23 07 19HVAC Piping Insulation23 08 00Commissioning of Mechanical23 08 02Cleaning of HVAC Piping23 09 00Instrumentation and Control for HVAC23 09 93Sequence of Operations for HVAC Controls23 11 23Natural Gas Piping23 21 13.Hydronic Piping23 21 13.Hydronic Piping23 21 13.Hydronic Pumps23 31 13Metal Ducts23 21 13.Hydronic Pumps23 31 13Metal Ducts23 31 13Panel Air Filters23 52 16.13Condensing Boilers23 57 19.13Plate and Frame Heat Exchangers <td></td> <td></td>		
22 13 33Packaged, Submersible Sewerage Pump22 30 00Plumbing Equipment23 05 01Common Work Results for Mechanical23 05 16Expansion Fittings and Loops for HVAC Piping23 05 19Meters and Gauges for HVAC Piping and Equipment23 05 29Hangers and Supports for HVAC Piping and Equipment23 05 29Testing, Adjusting and Balancing for HVAC23 06 20.13 (R1)Hydronic Pump Schedule23 06 20.16 (R1)Circuit Balancing Valve Schedule23 06 21.16Plate and Frame Heat Exchanger Schedule23 06 21.19Tank Schedule23 06 50.13 (R1)Condensing Boiler Schedule23 06 80.23Air Coil Schedule23 06 80.23Air Coil Schedule23 08 00Commissioning of Mechanical23 09 00Instrumentation and Control for HVAC23 09 33 (R2)Electric and Electronic Control Systems for HVAC23 09 93Sequence of Operations for HVAC Controls23 11 23Natural Gas Piping23 21 13Hydronic Pumps23 21 13Hydronic Pumps <td></td> <td>v v</td>		v v
22 30 00Plumbing Equipment23 05 01Common Work Results for Mechanical23 05 01Common Work Results for Mechanical23 05 16Expansion Fittings and Loops for HVAC Piping23 05 19Meters and Gauges for HVAC Piping and Equipment23 05 29Hangers and Supports for HVAC Piping and Equipment23 05 20Testing, Adjusting and Balancing for HVAC23 06 20.13 (R1)Hydronic Pump Schedule23 06 20.16 (R1)Circuit Balancing Valve Schedule23 06 20.16 (R1)Circuit Balancing Valve Schedule23 06 20.17 (R1)Tank Schedule23 06 20.13 (R1)Outlet and Inlet Schedule23 06 50.13 (R1)Condensing Boiler Schedule23 06 80.23Air Coil Schedule23 08 00Commissioning of Mechanical23 08 00Cleaning of HVAC Piping23 09 33 (R2)Electric and Electronic Control Systems for HVAC23 09 93Sequence of Operations for HVAC Controls23 11 23Natural Gas Piping23 21 13Hydronic Valves and Strainers23 21 13Hydronic Pumps23 31 13Metal Ducts23 31 13Metal Ducts23 35 7 19.13Plate and Frame Heat Exchangers		
23 05 01Common Work Results for Mechanical23 05 16Expansion Fittings and Loops for HVAC Piping23 05 19Meters and Gauges for HVAC Piping23 05 29Hangers and Supports for HVAC Piping and Equipment23 05 93Testing, Adjusting and Balancing for HVAC23 06 20.13 (R1)Hydronic Pump Schedule23 06 20.16 (R1)Circuit Balancing Valve Schedule23 06 21.16Plate and Frame Heat Exchanger Schedule23 06 20.13 (R1)Condensing Boiler Schedule23 06 21.19Tank Schedule23 06 50.13 (R1)Condensing Boiler Schedule23 06 50.13 (R1)Condensing Boiler Schedule23 07 19HVAC Piping Insulation23 08 00Commissioning of Mechanical23 09 00Instrumentation and Control for HVAC23 09 33 (R2)Electric and Electronic Control Systems for HVAC23 09 93Sequence of Operations for HVAC Controls23 11 23Natural Gas Piping23 21 13.13Hydronic Valves and Strainers23 21 13.13Mydronic Pumps23 21 13.13Mydronic Pumps23 31 13Metal Ducts23 31 13Metal Ducts23 31 13Metal Ducts23 35 7 19.13Plate and Frame Heat Exchangers		
23 05 16Expansion Fittings and Loops for HVAC Piping23 05 19Meters and Gauges for HVAC Piping23 05 29Hangers and Supports for HVAC Piping and Equipment23 05 93Testing, Adjusting and Balancing for HVAC23 06 20.13 (R1)Hydronic Pump Schedule23 06 20.16 (R1)Circuit Balancing Valve Schedule23 06 21.16Plate and Frame Heat Exchanger Schedule23 06 21.19Tank Schedule23 06 30.19Air Outlet and Inlet Schedule23 06 50.13 (R1)Condensing Boiler Schedule23 06 6 80.23Air Coil Schedule23 07 19HVAC Piping Insulation23 08 00Commissioning of Mechanical23 09 00Instrumentation and Control for HVAC23 09 33 (R2)Electric and Electronic Control Systems for HVAC23 09 93Sequence of Operations for HVAC Controls23 11 23Natural Gas Piping23 21 13.13Hydronic Valves and Strainers23 21 13.13Metal Ducts23 21 13.13Metal Ducts23 21 13.13Panel Air Filters23 23 11.3Panel Air Filters23 35 7 19.13Plate and Frame Heat Exchangers		
23 05 19Meters and Gauges for HVAC Piping23 05 29Hangers and Supports for HVAC Piping and Equipment23 05 93Testing, Adjusting and Balancing for HVAC23 06 20.13 (R1)Hydronic Pump Schedule23 06 20.16 (R1)Circuit Balancing Valve Schedule23 06 21.16Plate and Frame Heat Exchanger Schedule23 06 21.19Tank Schedule23 06 30.19Air Outlet and Inlet Schedule23 06 50.13 (R1)Condensing Boiler Schedule23 06 80.23Air Coil Schedule23 07 19HVAC Piping Insulation23 08 00Commissioning of Mechanical23 09 00Instrumentation and Control for HVAC23 09 33 (R2)Electric and Electronic Control Systems for HVAC23 09 33.13Controls Points List23 21 13Hydronic Piping23 21 13Hydronic Valves and Strainers23 21 13Hydronic Valves and Strainers23 21 13Hydronic Specialties23 21 13Metal Ducts23 31 13Metal Ducts23 31 13Panel Air Filters23 52 16.13Condensing Boilers23 57 19.13Plate and Frame Heat Exchangers		
23 05 29Hangers and Supports for HVAC Piping and Equipment23 05 93Testing, Adjusting and Balancing for HVAC23 06 20.13 (R1)Hydronic Pump Schedule23 06 20.16 (R1)Circuit Balancing Valve Schedule23 06 21.16Plate and Frame Heat Exchanger Schedule23 06 21.19Tank Schedule23 06 30.19Air Outlet and Inlet Schedule23 06 80.23Air Coil Schedule23 07 19HVAC Piping Insulation23 08 00Commissioning of Mechanical23 09 00Instrumentation and Control for HVAC23 09 33 (R2)Electric and Electronic Control Systems for HVAC23 09 93Sequence of Operations for HVAC Controls23 11 23Natural Gas Piping23 21 13.13Hydronic Valves and Strainers23 21 13.13Hydronic Pumps23 21 13Metal Ducts23 31 13Metal Ducts23 31 13Panel Air Filters23 35 7 19.13Plate and Frame Heat Exchangers		
23 05 93Testing, Adjusting and Balancing for HVAC23 06 20.13 (R1)Hydronic Pump Schedule23 06 20.16 (R1)Circuit Balancing Valve Schedule23 06 21.16Plate and Frame Heat Exchanger Schedule23 06 21.19Tank Schedule23 06 21.19Tank Schedule23 06 30.19Air Outlet and Inlet Schedule23 06 50.13 (R1)Condensing Boiler Schedule23 07 19HVAC Piping Insulation23 08 00Commissioning of Mechanical23 09 00Instrumentation and Control for HVAC23 09 33 (R2)Electric and Electronic Control Systems for HVAC23 09 93Sequence of Operations for HVAC Controls23 11 23Natural Gas Piping23 21 13Hydronic Piping23 221 14Hydronic Piping23 23 13Metal Ducts23 33 13.16Fire Dampers23 34 13Panel Air Filters23 35 7 19.13Plate and Frame Heat Exchangers		
23 06 20.13 (R1)Hydronic Pump Schedule23 06 20.16 (R1)Circuit Balancing Valve Schedule23 06 21.16Plate and Frame Heat Exchanger Schedule23 06 21.19Tank Schedule23 06 30.19Air Outlet and Inlet Schedule23 06 50.13 (R1)Condensing Boiler Schedule23 06 80.23Air Coil Schedule23 07 19HVAC Piping Insulation23 08 00Commissioning of Mechanical23 09 00Instrumentation and Control for HVAC23 09 33 (R2)Electric and Electronic Control Systems for HVAC23 09 93Sequence of Operations for HVAC Controls23 11 23Natural Gas Piping23 21 13Hydronic Pumps23 21 13.13Hydronic Pumps23 21 13.13Hydronic Pumps23 31 13Metal Ducts23 33 13.16Fire Dampers23 41 13Panel Air Filters23 52 16.13Condensing Boilers23 57 19.13Plate and Frame Heat Exchangers		
23 06 20.16 (R1)Circuit Balancing Valve Schedule23 06 21.16Plate and Frame Heat Exchanger Schedule23 06 21.19Tank Schedule23 06 30.19Air Outlet and Inlet Schedule23 06 50.13 (R1)Condensing Boiler Schedule23 06 80.23Air Coil Schedule23 07 19HVAC Piping Insulation23 08 00Commissioning of Mechanical23 09 00Instrumentation and Control for HVAC23 09 33 (R2)Electric and Electronic Control Systems for HVAC23 09 93Sequence of Operations for HVAC Controls23 11 23Natural Gas Piping23 21 13Hydronic Piping23 21 13.13Hydronic Pumps23 11 3Metal Ducts23 21 13Hydronic Pumps23 11 3Metal Ducts23 23 13.16Fire Dampers23 41 13Panel Air Filters23 52 16.13Condensing Boilers23 57 19.13Plate and Frame Heat Exchangers		
23 06 21.16Plate and Frame Heat Exchanger Schedule23 06 21.19Tank Schedule23 06 30.19Air Outlet and Inlet Schedule23 06 50.13 (R1)Condensing Boiler Schedule23 06 80.23Air Coil Schedule23 07 19HVAC Piping Insulation23 08 00Commissioning of Mechanical23 09 00Instrumentation and Control for HVAC23 09 33 (R2)Electric and Electronic Control Systems for HVAC23 09 93Sequence of Operations for HVAC Controls23 11 23Natural Gas Piping23 21 13Hydronic Piping23 22 113Hydronic Valves and Strainers23 23 13Metal Ducts23 33 13.16Fire Dampers23 41 13Panel Air Filters23 52 16.13Condensing Boilers23 57 19.13Plate and Frame Heat Exchangers	. ,	
23 06 21.19Tank Schedule23 06 30.19Air Outlet and Inlet Schedule23 06 50.13 (R1)Condensing Boiler Schedule23 06 80.23Air Coil Schedule23 07 19HVAC Piping Insulation23 08 00Commissioning of Mechanical23 08 02Cleaning of HVAC Piping23 09 00Instrumentation and Control for HVAC23 09 33 (R2)Electric and Electronic Control Systems for HVAC23 09 93Sequence of Operations for HVAC Controls23 11 23Natural Gas Piping23 21 13Hydronic Piping23 21 14Hydronic Specialties23 21 23Hydronic Pumps23 31 13Metal Ducts23 33 13.16Fire Dampers23 41 13Panel Air Filters23 57 19.13Plate and Frame Heat Exchangers	. ,	•
23 06 30.19Air Outlet and Inlet Schedule23 06 50.13 (R1)Condensing Boiler Schedule23 06 80.23Air Coil Schedule23 07 19HVAC Piping Insulation23 08 00Commissioning of Mechanical23 08 02Cleaning of HVAC Piping23 09 00Instrumentation and Control for HVAC23 09 33 (R2)Electric and Electronic Control Systems for HVAC23 09 93Sequence of Operations for HVAC Controls23 11 23Natural Gas Piping23 21 13Hydronic Piping23 21 14Hydronic Specialties23 21 23Hydronic Pumps23 31 13Metal Ducts23 31 13Fire Dampers23 31 13Panel Air Filters23 35 21 6.13Condensing Boilers23 11 23Panel Air Filters23 25 7 19.13Plate and Frame Heat Exchangers		
23 06 50.13 (R1)Condensing Boiler Schedule23 06 80.23Air Coil Schedule23 07 19HVAC Piping Insulation23 08 00Commissioning of Mechanical23 08 02Cleaning of HVAC Piping23 09 00Instrumentation and Control for HVAC23 09 33 (R2)Electric and Electronic Control Systems for HVAC23 09 93Sequence of Operations for HVAC Controls23 11 23Natural Gas Piping23 21 13Hydronic Piping23 21 13Hydronic Valves and Strainers23 21 13Mydronic Pumps23 11 23Metal Ducts23 21 13Metal Ducts23 31 13Fire Dampers23 31 13Panel Air Filters23 52 16.13Condensing Boilers23 57 19.13Plate and Frame Heat Exchangers		
23 06 80.23Air Coil Schedule23 07 19HVAC Piping Insulation23 08 00Commissioning of Mechanical23 08 02Cleaning of HVAC Piping23 09 00Instrumentation and Control for HVAC23 09 33 (R2)Electric and Electronic Control Systems for HVAC23 09 93Sequence of Operations for HVAC Controls23 11 23Natural Gas Piping23 21 13Hydronic Piping23 21 13Hydronic Valves and Strainers23 21 23Hydronic Pumps23 31 13Metal Ducts23 33 13.16Fire Dampers23 41 13Panel Air Filters23 52 16.13Condensing Boilers23 57 19.13Plate and Frame Heat Exchangers		
23 07 19HVAC Piping Insulation23 08 00Commissioning of Mechanical23 08 02Cleaning of HVAC Piping23 09 00Instrumentation and Control for HVAC23 09 33 (R2)Electric and Electronic Control Systems for HVAC23 09 93Sequence of Operations for HVAC Controls23 11 23Natural Gas Piping23 21 13Hydronic Piping23 21 13Hydronic Valves and Strainers23 21 23Hydronic Pumps23 31 13Metal Ducts23 33 13.16Fire Dampers23 41 13Panel Air Filters23 52 16.13Condensing Boilers23 57 19.13Plate and Frame Heat Exchangers	· · ·	
23 08 00Commissioning of Mechanical23 08 02Cleaning of HVAC Piping23 09 00Instrumentation and Control for HVAC23 09 33 (R2)Electric and Electronic Control Systems for HVAC23 09 33.13Controls Points List23 09 93Sequence of Operations for HVAC Controls23 11 23Natural Gas Piping23 21 13Hydronic Piping23 21 13Hydronic Valves and Strainers23 21 23Hydronic Specialties23 31 13Metal Ducts23 31 13Fire Dampers23 41 13Panel Air Filters23 52 16.13Condensing Boilers23 57 19.13Plate and Frame Heat Exchangers		
23 08 02Cleaning of HVAC Piping23 09 00Instrumentation and Control for HVAC23 09 33 (R2)Electric and Electronic Control Systems for HVAC23 09 33.13Controls Points List23 09 93Sequence of Operations for HVAC Controls23 11 23Natural Gas Piping23 21 13Hydronic Piping23 21 13Hydronic Valves and Strainers23 21 23Hydronic Specialties23 31 13Metal Ducts23 31 13Metal Ducts23 31 13Panel Air Filters23 52 16.13Condensing Boilers23 57 19.13Plate and Frame Heat Exchangers	23 07 19	
23 09 00Instrumentation and Control for HVAC23 09 33 (R2)Electric and Electronic Control Systems for HVAC23 09 33.13Controls Points List23 09 93Sequence of Operations for HVAC Controls23 11 23Natural Gas Piping23 21 13Hydronic Piping23 21 13.13Hydronic Valves and Strainers23 21 23Hydronic Pumps23 31 13Metal Ducts23 31 13Metal Ducts23 41 13Panel Air Filters23 52 16.13Condensing Boilers23 57 19.13Plate and Frame Heat Exchangers	23 08 00	Commissioning of Mechanical
23 09 33 (R2)Electric and Electronic Control Systems for HVAC23 09 33.13Controls Points List23 09 93Sequence of Operations for HVAC Controls23 11 23Natural Gas Piping23 21 13Hydronic Piping23 21 13.13Hydronic Valves and Strainers23 21 23Hydronic Pumps23 31 13Metal Ducts23 33 13.16Fire Dampers23 52 16.13Condensing Boilers23 57 19.13Plate and Frame Heat Exchangers	23 08 02	Cleaning of HVAC Piping
23 09 33.13Controls Points List23 09 93Sequence of Operations for HVAC Controls23 11 23Natural Gas Piping23 21 13Hydronic Piping23 21 13.13Hydronic Valves and Strainers23 21 14Hydronic Specialties23 21 23Hydronic Pumps23 31 13Metal Ducts23 33 13.16Fire Dampers23 52 16.13Condensing Boilers23 57 19.13Plate and Frame Heat Exchangers	23 09 00	Instrumentation and Control for HVAC
23 09 93Sequence of Operations for HVAC Controls23 11 23Natural Gas Piping23 21 13Hydronic Piping23 21 13.13Hydronic Valves and Strainers23 21 14Hydronic Specialties23 21 23Hydronic Pumps23 31 13Metal Ducts23 31 3.16Fire Dampers23 41 13Panel Air Filters23 52 16.13Condensing Boilers23 57 19.13Plate and Frame Heat Exchangers	23 09 33 (R2)	Electric and Electronic Control Systems for HVAC
23 11 23Natural Gas Piping23 21 13Hydronic Piping23 21 13.13Hydronic Valves and Strainers23 21 14Hydronic Specialties23 21 23Hydronic Pumps23 31 13Metal Ducts23 31 3.16Fire Dampers23 41 13Panel Air Filters23 52 16.13Condensing Boilers23 57 19.13Plate and Frame Heat Exchangers	23 09 33.13	Controls Points List
23 21 13Hydronic Piping23 21 13.13Hydronic Valves and Strainers23 21 14Hydronic Specialties23 21 23Hydronic Pumps23 31 13Metal Ducts23 33 13.16Fire Dampers23 41 13Panel Air Filters23 52 16.13Condensing Boilers23 57 19.13Plate and Frame Heat Exchangers	23 09 93	Sequence of Operations for HVAC Controls
23 21 13.13Hydronic Valves and Strainers23 21 14Hydronic Specialties23 21 23Hydronic Pumps23 31 13Metal Ducts23 33 13.16Fire Dampers23 41 13Panel Air Filters23 52 16.13Condensing Boilers23 57 19.13Plate and Frame Heat Exchangers	23 11 23	Natural Gas Piping
23 21 13.13Hydronic Valves and Strainers23 21 14Hydronic Specialties23 21 23Hydronic Pumps23 31 13Metal Ducts23 33 13.16Fire Dampers23 41 13Panel Air Filters23 52 16.13Condensing Boilers23 57 19.13Plate and Frame Heat Exchangers	23 21 13	Hydronic Piping
23 21 14Hydronic Specialties23 21 23Hydronic Pumps23 31 13Metal Ducts23 33 13.16Fire Dampers23 41 13Panel Air Filters23 52 16.13Condensing Boilers23 57 19.13Plate and Frame Heat Exchangers	23 21 13.13	
23 21 23Hydronic Pumps23 31 13Metal Ducts23 33 13.16Fire Dampers23 41 13Panel Air Filters23 52 16.13Condensing Boilers23 57 19.13Plate and Frame Heat Exchangers		
23 31 13Metal Ducts23 33 13.16Fire Dampers23 41 13Panel Air Filters23 52 16.13Condensing Boilers23 57 19.13Plate and Frame Heat Exchangers		
23 33 13.16Fire Dampers23 41 13Panel Air Filters23 52 16.13Condensing Boilers23 57 19.13Plate and Frame Heat Exchangers		
23 41 13Panel Air Filters23 52 16.13Condensing Boilers23 57 19.13Plate and Frame Heat Exchangers		
23 52 16.13Condensing Boilers23 57 19.13Plate and Frame Heat Exchangers		
23 57 19.13 Plate and Frame Heat Exchangers		
8		•

TABLE OF CONTENTS (R3)

Section No.	Description
23 82 16	Air Coils
26 05 00	Common Work Results for Electrical
26 05 20	Wire and Box Connectors 0-1000 V
26 05 21	Wire and Cables (0-1000 V)
26 05 28	Grounding – Secondary
26 05 29 (R1)	Hangers and Supports for Electrical System
26 05 31	Junction and Pull Boxes
26 05 32	Outlet Boxes, Conduit Boxes and Fittings
26 05 34 (R1)	Conduits, Conduit Fastenings and Conduit Fittings
26 24 16.01	Panelboards Breaker Type
26 24 19 (R1)	Motor Control Centres
26 27 26	Wiring Devices
26 28 16.02 (R1)	Moulded Case Circuit Breakers
26 28 22	Load Break Switches
26 28 23 (R1)	Disconnect Switches – Fused and Non-fused
26 29 03	Control Devices
26 29 10 (R1)	Motor Starters to 600 V
26 50 00	Lighting
26 52 00	Emergency Lighting
26 53 00	Exit Lights

HYDRONIC PUMP SCHEDULE

1. HYDRONIC PUMP SCHEDULE

Тад	P-8	P-10	P-11
Function	To Heat Exchanger	Building Loop	Building Loop
Location	Mechanical Room	Mechanical Room	Mechanical Room
Туре	Inline	Inline	Inline
Impeller	Brass	Brass	Brass
Casing	Cast Iron	Cast Iron	Cast Iron
Medium Pumped	Water	Water	Water
Design Pressure, kPa (psi)	1207 (175)	1207 (175)	1207 (175)
Maximum Operating Temp., °C (°F)	107 (225)	107 (225)	107 (225)
Pump Speed, RPM	1750	1750	1750
Design Flow Rate, L/s (USgpm)	2.52 (40)	6.94 (110)	6.94 (110)
Discharge Head, kPa (ft. water)	120 (40)	114 (38)	114 (38)
Suction/Discharge Sizes, mm (inch)	38/38 (1.5/1.5)	50/50 (2/2)	50/50 (2/2)
Motor Power, kW (hp)	1.1 (1.5)	1.5 (2.0)	1.5 (2.0)
Power Supply, V/ph/Hz	208/3/60	208/3/60	208/3/60
Manufacturer	Bell & Gossett	Bell & Gossett	Bell & Gossett
Model	Series "90" 1-1/2A	Series "90" 2A	Series "90" 2A
Weight, Kg (lb)	41 (90)	45 (100)	45 (100)
Remarks	ODP Motor	ODP Motor	ODP Motor

Тад	P-12	P-13
Function	To Existing Building	To pre-heating Coil
Location	Mechanical Room	Mechanical Room
Туре	Inline	Inline
Impeller	Brass	Brass
Casing	Cast Iron	Cast Iron
Medium Pumped	Water	50% Ethylene Glycol
Design Pressure, kPa (psi)	1207 (175)	1207 (175)
Maximum Operating Temp., °C (°F)	107 (225)	107 (225)
Pump Speed, RPM	1725	1750
Design Flow Rate, L/s (USgpm)	5.04 (80)	1.77 (28.1)
Discharge Head, kPa (ft. water)	48 (16)	132 (44)
Suction/Discharge Sizes, mm (inch)	50/50 (2/2)	38/38 (1.5/1.5)
Motor Power, kW (hp)	0.56 (0.75)	0.75 (1.0)
Power Supply, V/ph/Hz	230/3/60	230/3/60
Manufacturer	Bell & Gossett	Bell & Gossett
Model	Series "90" 2AA	Series "90" 1-1/2A
Weight, Kg (lb)	30 (67)	39 (85)
Remarks	ODP Motor	ODP Motor

1. CIRCUIT BALANCING VALVE

Тад	CBV-B-1	CBV-B-2	CBV-1-1
Related Equipment	Heat Pump B-1	Heat Pump B-2	Heat Pump 1-1
Connection Type	NPT	NPT	NPT
Maximum Working Pressure, kPa (psi)	2068 (300)	2068 (300)	2068 (300)
Operating Temperature Range, ^o C (^o F)	-20 to150	-20 to150	-20 to150
	(-4 to 300)	(-4 to 300)	(-4 to 300)
Medium Handled	Water	Water	Water
Flow Rate Setpoint, L/s (USgpm)	0.95 (15.0)	0.95 (15.0)	0.66 (10.5)
Pipe Connection Size, mm (in)	40 (1.5)	40 (1.5)	30 (1.25)
Manufacturer	Armstrong	Armstrong	Armstrong
Model	CBV150VT	CBV150VT	CBV-125VT

Тад	CBV-1-2	CBV-1-3	CBV-1-4
Function	Heat Pump 1-2	Heat Pump 1-3	Heat Pump 1-4
Connection Type	NPT	NPT	NPT
Maximum Working Pressure, kPa (psi)	2068 (300)	2068 (300)	2068 (300)
Operating Temperature Range, ^o C (^o F)	-20 to150	-20 to150	-20 to150
	(-4 to 300)	(-4 to 300)	(-4 to 300)
Medium Handled	Water	Water	Water
Flow Rate Setpoint, L/s (USgpm)	0.66 (10.5)	0.28 (4.4)	0.28 (4.4)
Pipe Connection Size, mm (in)	30 (1.25)	25 (1.0)	25 (1.0)
Manufacturer	Armstrong	Armstrong	Armstrong
Model	CBV-125VT	CBV-100VT	CBV-100VT

Тад	CBV-1-5	CBV-1-6	CBV-1-7
Function	Heat Pump 1-5	Heat Pump 1-6	Heat Pump 1-7
Connection Type	NPT	NPT	NPT
Maximum Working Pressure, kPa (psi)	2068 (300)	2068 (300)	2068 (300)
Operating Temperature Range, ^o C (^o F)	-20 to150	-20 to150	-20 to150
	(-4 to 300)	(-4 to 300)	(-4 to 300)
Medium Handled	Water	Water	Water
Flow Rate Setpoint, L/s (USgpm)	0.57 (9.0)	0.38 (6.0)	0.28 (4.4)
Pipe Connection Size, mm (in)	30 (1.25)	25 (1.0)	25 (1.0)
Manufacturer	Armstrong	Armstrong	Armstrong
Model	CBV-125VT	CBV-100VT	CBV-100VT

Тад	CBV-P-8a	CBV-P-8b	CBV-B-3
Function	High temp. loop supply to low temp. loop	High temp. loop supply to low temp. loop	Boiler B-3
Connection Type	NPT	NPT	NPT
Maximum Working Pressure, kPa (psi)	2068 (300)	2068 (300)	2068 (300)
Maximum Operating Temperature, °C (°F)	110 (230)	110 (230)	110 (230)
Medium Handled	Water	Water	Water
Flow Rate Setpoint, L/s (USgpm)	1.26 (20)	1.26 (20)	1.4 (22)
Pipe Connection Size, mm (in)	40 (1.5)	40 (1.5)	40 (1.5)
Manufacturer	Armstrong	Armstrong	Armstrong
Model	CBV-150VT	CBV-150VT	CBV-150VT

Тад	CBV-B-4	CBV-F-1	CBV-F-2
Function	Boiler B-4	Future Heat Pump	Future Heat Pump
Connection Type	NPT	NPT	NPT
Maximum Working Pressure, kPa (psi)	2068 (300)	2068 (300)	2068 (300)
Operating Temperature Range, °C (°F)	110 (230)	-20 to150	-20 to150
		(-4 to 300)	(-4 to 300)
Medium Handled	Water	Water	Water
Flow Rate Setpoint, L/s (USgpm)	1.4 (22)	0.95 (15.0)	0.95 (15.0)
Pipe Connection Size, mm (in)	40 (1.5)	40 (1.5)	40 (1.5)
Manufacturer	Armstrong	Armstrong	Armstrong
Model	CBV-150VT	CBV-150VT	CBV-150VT

Тад	CBV-HX-1	CBV-HX-2
Function	HX-1 Source 1	HX-1 Source 2
Connection Type	NPT	NPT
Maximum Working Pressure, kPa (psi)	2068 (300)	2068 (300)
Operating Temperature Range, °C (°F)	110 (230)	110 (230)
Medium Handled	Water	Water
Flow Rate Setpoint, L/s (USgpm)	0.89 (14.1)	1.63 (25.9)
Pipe Connection Size, mm (in)	40 (1.5)	40 (1.5)
Manufacturer	Armstrong	Armstrong
Model	CBV-150VT	CBV-150VT

1. AIR OUTLET AND INLET SCHEDULE

Туре	Specifications	Manufacturer	Model
SA-1	Steel louvered face four directional diffusers, adjustable air pattern, removable core, surface mount frame and white powder coat finish. Frame design shall limit ceiling opening to have at most a 25 mm border around the nominal duct diameter of the diffuser.	E.H. PRICE	SMDA
RA-1	Egg crate face return/exhaust diffuser, aluminum 13x13x13 grid, formed steel border and mounting frame, hinge-tab mechanism allows hinging or removal of grill from frame.	E.H. PRICE	80FF
TA-1	As per 23 33 13.16		

2. AIR OUTLET AND INLET ACCESSORIES SCHEDULE

Note: All Outlet and Inlet air openings through fire rated ceilings shall have a fire damper rated minimum 2 hrs, have a square to round transition to fit existing ductwork, and a thermal blanket.

Accessory	Specifications	Manufacturer	Model
Ceiling Fire Damper	Square, non-asbestos damper with one round transition, curtain style spring blades with replaceable 100°C (212°F) fusible link.	E.H. PRICE	CFSR-1
Thermal Blanket	Lightweight, non-asbestos fabric to be fit around fire damper round transition piece.	E.H. PRICE	CK-2000

1. CONDENSING BOILER SCHEDULE

Тад	B-3	B-4	
Manufacturer	LAARS	LAARS	
Model	NT 399	NT 399	
Heating Input, kW (MBH)	117(399)	117(399)	
Rated Heating Output, kW (MBH)	112 (382)	112 (382)	
Operating Pressure, kPa (psi)	1034 (150)	1034 (150)	
EWT, °C (°F)	40.1 (105)	40.1 (105)	
LWT, °C (°F)	60 (140)	60 (140)	
Flow Rate, L/s (gpm)	1.4 (22)	1.4 (22)	
Pressure drop, kPa (Ft Hd)	32.9 (11)	32.9 (11)	
Fuel Source	Natural Gas	Natural Gas	
Turn Down Ratio	5:1	5:1	
Gas Connections (NPT), mm (in)	20 (0.75)	20 (0.75)	
Water Connections (NPT), mm (in)	30 (1.25)	30 (1.25)	
Air Intake Size, mm (in)	100 (4)	100 (4)	
Vent Size, mm (in)	100 (4)	100 (4)	
Electrical, V/ph/Hz	120/1/60	120/1/60	
Electrical Circuit Required	Minimum 15 amp	Minimum 15 amp	
Gross Weight, kg (lbs)	(405)	(405)	
WxDxH, mm (in)	800x480x970 (31.5x19x38)	800x480x970 (31.5x19x38)	
Remarks	ASME Approved, Supplied with boiler pump, 150 psi pressure relief valve, water flow switch, low water cutoff and air terminal kit (#2400-102 or 40D5025).	ASME Approved, Supplied with boiler pump, 150 psi pressure relief valve, water flow switch, low water cutoff and air terminal kit (#2400-102 or 40D5025)	

1.1 General Intent and related information

- .1 All work of this Section shall be coordinated and provided by a single Controls Contractor.
- .2 The City has a central monitoring system in place, and is currently monitoring building points at 457 Main St., Winnipeg, Manitoba (Confederation Building). These existing points are being monitored using the Johnson Controls N2 communications protocol DDC controllers, via the City supplied leased line modem network. Unless otherwise stated, these points shall remain as-is.
- .3 Where new DDC points are identified in this specification to be centrally monitored points, the Controls Contractor shall provide and install the required N2 protocol capable hardware and software to interface these points, and where required, extended the existing N2 trunk to any new DDC controllers. It is the Controls Contractor's responsibility to integrate any new DDC points into the City's existing Johnson Controls Metasys EA servers and workstations. These servers and workstations are located at 510 Main St. Winnipeg, MB. <u>No new operator work stations are required under this Contract</u>.

1.2 Definitions

- .1 Analog: A continuously variable system or value not having discrete levels. Typically exists within a defined range of limiting values.
- .2 Binary: A two-state system where an "ON" condition is represented by one discrete signal level and an "OFF" condition is represented by a second discrete signal level.
- .3 Building Management System (BMS): The total integrated system of fully operational and functional elements, including equipment, software, programming, and associated materials, to be provided by this Section and to be interfaced to the associated work of other related trades.
- .4 Controls Contractor: The Contractor or Subcontractor to provide the work of this Section. The Controls Contractor shall be the primary manufacturer, installer, commissioner and ongoing service provider for the BMS work.
- .5 Control Sequence: An BMS pre-programmed arrangement of software algorithms, logical computation, target values and limits as required to attain the defined operational control objectives.
- .6 Direct Digital Control: The digital algorithms and pre-defined arrangements included in the BMS software to provide direct closed-loop control for the designated equipment and controlled variables. Inclusive of Proportional, Derivative and Integral control algorithms together with target values, limits, logical functions, arithmetic functions, constant values, timing considerations and the like.
- .7 BMS Network: The total digital on-line real-time interconnected configuration of BMS digital processing units, workstations, panels, sub-panels, controllers, devices and associated elements individually known as network nodes. May exist as one or more fully interfaced and integrated sub-networks, LAN, WAN or the like.

- .8 Node: A digitally programmable entity existing on the BMS network.
- .9 BMS Integration: The complete functional and operational interconnection and interfacing of all BMS work elements and nodes in compliance with all applicable codes, standards and ordinances so as to provide a single coherent BMS as required by this Section.
- .10 Provide: The term "Provide" and its derivatives when used in this Section shall mean to furnish, install in place, connect, calibrate, test, commission, warrant, document and supply the associated required services ready for operation.
- .11 PC: IBM-compatible Personal Computer from a recognized major manufacturer
- .12 Furnish: The term "Furnish" and its derivatives when used in this Section shall mean supply at the Control Contractor's cost to the designated third party trade contractor for installation. Control Contractor shall connect furnished items to the BMS, calibrate, test, commission, warrant and document.
- .13 Wiring: The term "Wiring" and its derivatives when used in this Section shall mean provide the BMS wiring and terminations.
- .14 Install: The term "Install" and its derivatives when used in this Section shall mean receive at the jobsite and mount.
- .15 Protocol: The term "protocol" and its derivatives when used in this Section shall mean a defined set of rules and standards governing the on-line exchange of data between BMS network nodes.
- .16 Software: The term "software" and its derivatives when used in this Section shall mean all of programmed digital processor software, preprogrammed firmware and Work specific digital process programming and database entries and definitions as generally understood in the BMS industry for real-time, on-line, integrated BMS configurations.
- .17 The following abbreviations and acronyms may be used in describing the work of this Section:

ADC	-	Analog to Digital Converter
AI	-	Analog Input
AN	-	Application Node
AO	-	Analog Output
AWG	-	American Wire Gauge
CPU	-	Central Processing Unit
CRT	-	Cathode Ray Tube
DAC	-	Digital to Analog Converter
DDC	-	Direct Digital Control
DI	-	Digital Input
DO	-	Digital Output
EEPROM	-	Electronically Erasable Programmable Read Only Memory
EMI	-	Electromagnetic Interference
FAS	-	Fire Alarm Detection and Annunciation System
GUI	-	Graphical User Interface
HOA	-	Hand-Off-Auto
ID	-	Identification

ELECTRIC AND ELECTRONIC CONTROL SYSTEMS FOR HVAC

I/O	-	Input/Output
LAN	-	Local Area Network
LCD	-	Liquid Crystal Display
LED	-	Light Emitting Diode
MCC	-	Motor Control Center
NC	-	Normally Closed
NIC	-	Not In Contract
NO	-	Normally Open
OWS	-	Operator Workstation
OAT	-	Outdoor Air Temperature
PC	-	Personal Computer
RAM	-	Random Access Memory
RF	-	Radio Frequency
RFI	-	Radio Frequency Interference
RH	-	Relative Humidity
ROM	-	Read Only Memory
RTD	-	Resistance Temperature Device
SPDT	-	Single Pole Double Throw
SPST	-	Single Pole Single Throw
XVGA	-	Extended Video Graphics Adapter
TBA	-	To Be Advised
TCP/IP	-	Transmission Control Protocol/Internet Protocol
TTD	-	Thermistor Temperature Device
UPS	-	Uninterruptible Power Supply
VAC	-	Volts, Alternating Current
VAV	-	Variable Air Volume
VDC	-	Volts, Direct Current
WAN	-	Wide Area Network

1.3 BMS Description

- .1 The Building Management System (BMS) shall be a complete system designed for use with the enterprise IT systems in place at the City of Winnipeg. This functionality shall extend into the equipment rooms. Devices residing on the automation network located in equipment rooms and similar shall be fully IT compatible devices that mount and communicate directly on the IT infrastructure in the facility. Coordinate with the City's IT staff to ensure that the FMS will perform in the City's environment without disruption to any of the other activities taking place on that LAN.
- .2 All points of user interface shall be on standard PCs that do not require the purchase of any special software from the BMS manufacturer for use as a building operations terminal. The primary point of interface on these PCs will be a standard Web Browser.
- .3 Where necessary and as dictated elsewhere in these Specifications, the City of Winnipeg's existing ADS/ADX Server(s) shall be used for the purpose of providing a location for extensive archiving of system configuration data, and historical data such as trend data and operator transactions.
- .4 The work of the single Controls Contractor shall be as defined individually and collectively in all Sections together with the associated Point Sheets and Drawings and the associated interfacing work as referenced in the related documents.

- .5 The BMS work shall consist of the provision of all labour, materials, tools, equipment, software, software licenses, software configurations and database entries, interfaces, wiring, tubing, installation, labeling, engineering, calibration, documentation, samples, submittals, testing, commissioning, training services, permits and licenses, transportation, shipping, handling, administration, supervision, management, insurance, temporary protection, cleaning, cutting and patching, warranties, services, and items, even though these may not be specifically mentioned in these Section documents which are required for the complete, fully functional and commissioned BMS.
- .6 Provide a complete, neat and workmanlike installation. Use only workers who are skilled, experienced, trained, and familiar with the specific equipment, software, standards and configurations to be provided for this Work.
- .7 Manage and coordinate the BMS work in a timely manner in consideration of the Work schedules. Coordinate with the associated work of other trades so as to not impede or delay the work of associated trades.
- .8 The BMS as provided shall incorporate, at minimum, the following integrated features, functions and services:
 - .1 Operator information, alarm management and control functions.
 - .2 Enterprise-level information and control access.
 - .3 Information management including monitoring, transmission, archiving, retrieval, and reporting functions.
 - .4 Diagnostic monitoring and reporting of BMS functions.
 - .5 Offsite monitoring and management access.
 - .6 Energy management
 - .7 Standard applications for terminal HVAC systems.

1.4 Quality Assurance

- .1 General
 - .1 The following companies are approved Controls Contractors:
 - .1 Johnson Controls Branch Office

1.5 References

- .1 General
 - .1 UL 864 UUKL Smoke Control
 - .2 UL 268 Smoke Detectors.
 - .3 UL 916 Energy Management

ELECTRIC AND ELECTRONIC CONTROL SYSTEMS FOR HVAC

- .4 NFPA 70 National Electrical Code.
- .5 NFPA 90A Standard for the Installation of Air Conditioning and Ventilating Systems.
- .6 NFPA 92A and 92B Smoke Purge/Control Equipment.
- .7 Federal Communications Commission (FCC) including Part 15, Radio Frequency Devices.
- .8 ANSI/EIA 909.1-A-1999 (LonWorks)
- .9 ANSI/ASHRAE Standard 195-2004 (BACnet)

1.6 Work By Others

.1 The demarcation of work and responsibilities between the Controls Contractor and other related trades shall be as outlined in the BMS RESPONSIBILITY MATRIX

BMS RESPONSIBILITY MATRIX				
Scope of Work	FURNISH		Low Volt. WIRING/TUBE	LINE POWER
BMS low voltage and communication wiring	BMS	BMS	BMS	N/A
BMS conduits and raceway	BMS	BMS	BMS	BMS
Automatic dampers	BMS	23	N/A	N/A
Manual valves	23	23	N/A	N/A
Automatic valves	BMS	23	BMS	N/A
Pipe insertion devices and taps including thermowells, flow and pressure stations.	BMS	23	BMS	BMS
BMS Current Switches.	BMS	BMS	BMS	N/A

City of Winnipeg Confederation Building Supplementary Heating Upgrades Phase 1 Bid Opportunity 757-2008 Addendum 4

ELECTRIC AND ELECTRONIC CONTROL SYSTEMS FOR HVAC

BMS	BMS	BMS	N/A
BMS	BMS	BMS	BMS
23		BMS	26
23		N/A	N/A
23		23	23
BMS	26	BMS	26
23	BMS	BMS	26
26		26	26
26		26	26
23*	BMS	BMS	26
BMS	BMS	BMS	26
26		N/A	26
BMS	BMS	BMS	26
	BMS 23 23 23 23 23 23 23 23 26 26 26 26 26 26 26 26 26 26 26 26 26	BMS BMS 23 23 23 23 23 23 23 23 23 23 BMS 26 23 26 26 26 26 26 23* BMS BMS BMS 26 26 26 26 23* BMS 26 26 26 26 26 26 26 26 26 26 26 26 26 26 26 26 26 26	BMS BMS BMS 23 23 BMS 23 23 N/A 23 23 N/A 23 23 23 23 23 23 23 23 23 BMS 26 BMS 23 26 26 23 26 26 26 26 26 26 26 26 23* BMS BMS BMS BMS BMS 23* BMS BMS 26 26 1000000000000000000000000000000000000

1.7 Submittals

- .1 Shop Drawings, Product Data, and Samples
 - .1 Submit a list of all Shop Drawings with submittals dates within thirty (30) days of contract award.
 - .2 Submittals shall be in defined packages. Each package shall be complete and shall only reference itself and previously submitted packages. The packages shall be as approved by the Contract Administrator.

- .3 Allow fifteen (15) working days for the review of each package by the Contract Administrator in the scheduling of the total BMS work.
- .4 Equipment and systems requiring approval of local authorities must comply with such regulations and be approved. Filing shall be at the expense of the Controls Contractor where filing is necessary. Provide a copy of all related correspondence and permits to the City.
- .5 Prepare an index of all submittals and shop drawings for the installation. Index shall include a Shop Drawing identification number, Contract reference and item description.
- .6 Correct any errors or omissions noted in the first review.
- .7 At a minimum, submit the following:
 - .1 BMS network architecture diagrams including all nodes and interconnections.
 - .2 Systems schematics, sequences and flow diagrams.
 - .3 Points schedule for each point in the BMS, including: Point Type, Object Name, Expanded ID, Display Units, Controller type, and Address.
 - .4 Samples of Graphic Display screen types and associated menus.
 - .5 Detailed Bill of Material list for each system or application, identifying quantities, part numbers, descriptions, and optional features.
 - .6 Control Damper Schedule including a separate line for each damper provided under this section and a column for each of the damper attributes, including: Code Number, Fail Position, Damper Type, Damper Operator, Duct Size, Damper Size, Mounting, and Actuator Type.
 - .7 Control Valve Schedules including a separate line for each valve provided under this section and a column for each of the valve attributes: Code Number, Configuration, Fail Position, Pipe Size, Valve Size, Body Configuration, Close off Pressure, Capacity, Valve CV, Design Pressure, and Actuator Type.
 - .8 Room Schedule including a separate line for each VAV box and/or terminal unit indicating location and address.
 - .9 Details of all BMS interfaces and connections to the work of other trades.
 - .10 Product data sheets or marked catalogue pages including part number, photo and description for all products including software.

1.8 Record Documentation

- .1 Operation and Maintenance Manuals
 - .1 Provide Operation and Maintenance Manuals in accordance with Division 01. The entire Operation and Maintenance Manual shall be furnished on Compact Disc media, and include the following for the BMS provided:

- .1 Table of contents.
- .2 As-built system record drawings. Computer Aided Drawings (CAD) record drawings shall represent the as-built condition of the system and incorporate all information supplied with the approved submittal.
- .3 Manufacturer's product data sheets or catalogue pages for all products including software.
- .4 System Operator's manuals.
- .5 Archive copy of all site-specific databases and sequences.
- .6 BMS network diagrams.
- .7 Interfaces to all third-party products and work by other trades.
- .2 The Operation and Maintenance Manual CD shall be self-contained, and include all necessary software required to access the product data sheets. A logically organized table of contents shall provide dynamic links to view and print all product data sheets. Viewer software shall provide the ability to display, zoom, and search all documents.

2. PRODUCTS

2.1 General Description

- .1 The Building Management System (BMS) shall use an open architecture and fully support a multi-vendor environment. To accomplish this effectively, the BMS shall support open communication protocol standards and integrate a wide variety of third-party devices and applications. The system shall be designed for use on the Internet, or intranets using off the shelf, industry standard technology compatible with other City provided networks.
- .2 The Building Management System shall consist of the following:
 - .1 Standalone Network Automation Engine(s)
 - .2 Field Equipment Controller(s)
 - .3 Input/Output Module(s)
 - .4 Local Display Device(s)
 - .5 Network processing, data storage and communications equipment
 - .6 Other components required for a complete and working BMS
- .3 The system shall be modular in nature, and shall permit expansion of both capacity and functionality through the addition of sensors, actuators, controllers and operator devices, while re-using existing controls equipment.

- .4 System architectural design shall eliminate dependence upon any single device for alarm reporting and control execution. The failure of any single component or network connection shall not interrupt the execution of control strategies at other operational devices.
- .5 Acceptable Manufacturers
 - .1 Johnson Controls Metasys Extended Architecture

2.2 BMS Architecture

- .1 Automation Network
 - .1 The automation network shall be based on a PC industry standard of Ethernet TCP/IP. Where used, LAN controller cards shall be standard "off the shelf" products available through normal PC vendor channels.
 - .2 The BMS shall network multiple user interface clients, automation engines, system controllers and application-specific controllers. Provide application and data server(s) as required for systems operation.
 - .3 The automation network shall be capable of operating at a communication speed of 100 Mbps, with full peer-to-peer network communication.
 - .4 Network Automation Engines (NAE) shall reside on the automation network.
 - .5 The automation network will be compatible with other enterprise-wide networks. Where indicated, the automation network shall be connected to the enterprise network and share resources with it by way of standard networking devices and practices.
 - .6 The City will provide all private and public telephones lines, ISDN lines and Internet Service Provider services and connections as necessary for the Controls Contractor to complete the work as contracted at the City's direct cost. The Controls Contractor shall identify the specific requirements in their Shop Drawing submittal.
- .2 Control Network
 - .1 Network Automation Engines shall provide supervisory control over the control network and shall support all three (3) of the following communication protocols:
 - .1 BACnet Standard MS/TP Bus Protocol ASHRAE SSPC-135, Clause 9.
 - .2 LonWorks enabled devices using the Free Topology Transceiver (FTT-10a).
 - .3 The Johnson Controls N2 Field Bus.
 - .2 Control networks shall provide either "Peer-to-Peer," Master-Slave, or Supervised Token Passing communications, and shall operate at a minimum communication speed of 9600 baud.
 - .3 DDC Controllers shall reside on the control network.

- .4 Control network communication protocol shall be BACnet Standard MS/TP Bus Protocol ASHRAE SSPC-135, or Johnson Controls N2 Field Bus.
- .5 A BACnet Protocol Implementation Conformance Statement shall be provided for each controller device (master or slave) that will communicate on the BACnet MS/TP Bus.
- .6 BACnet Protocol Integration BACnet
 - .1 The neutral protocol used between systems will be BACnet over Ethernet and comply with the ASHRAE BACnet standard 135-2003.
 - .2 A complete Protocol Implementation Conformance Statement (PICS) shall be provided for all BACnet system devices.
 - .3 The ability to command, share point object data, change of state (COS) data and schedules between the host and BACnet systems shall be provided.

2.3 Network Automation Engines (NAE)

- .1 Network Automation Engine (NAE)
 - .1 The Network Automation Engine (NAE) shall be a fully user-programmable, supervisory controller. The NAE shall monitor the network of distributed application-specific controllers, provide global strategy and direction, and communicate on a peer-to-peer basis with other Network Automation Engines.
 - .2 Automation network The NAE shall reside on the automation network and shall support a subnet of system controllers.
 - .3 User Interface Each NAE shall have the ability to deliver a web based User Interface (UI) as previously described. All computers connected physically or virtually to the automation network shall have access to the web based UI.
 - .1 The web based UI software shall be imbedded in the NAE. Systems that require a local copy of the system database on the user's personal computer are not acceptable.
 - .2 The NAE shall support up four (4) concurrent users.
 - .3 The web based user shall have the capability to access all system data through one NAE.
 - .4 Remote users connected to the network through an Internet Service Provider (ISP) or telephone dial up shall also have total system access through one NAE.
 - .5 Systems that require the user to address more than one NAE to access all system information are not acceptable.
 - .6 The NAE shall have the capability of generating web based UI graphics. The graphics capability shall be imbedded in the NAE.

- .7 Systems that support UI Graphics from a central database or require the graphics to reside on the user's personal computer are not acceptable.
- .8 The web based UI shall support the following functions using a standard version of Microsoft Internet Explorer:
 - .1 Configuration
 - .2 Commissioning
 - .3 Data Archiving
 - .4 Monitoring
 - .5 Commanding
 - .6 System Diagnostics
- .9 Systems that require workstation software or modified web browsers are not acceptable.
- .10 The NAE shall allow temporary use of portable devices without interrupting the normal operation of permanently connected modems.
- .4 Processor The NAE shall be microprocessor-based with a minimum word size of 32 bits. The NAE shall be a multi-tasking, multi-user, and real-time digital control processor. Standard operating systems shall be employed. NAE size and capability shall be sufficient to fully meet the requirements of this Specification.
- .5 Memory Each NAE shall have sufficient memory to support its own operating system, databases, and control programs, and to provide supervisory control for all control level devices.
- .6 Hardware Real Time Clock The NAE shall include an integrated, hardware-based, real-time clock.
- .7 The NAE shall include troubleshooting LED indicators to identify the following conditions:
 - .1 Power On/Off
 - .2 Ethernet Traffic Ethernet Traffic/No Ethernet Traffic
 - .3 Ethernet Connection Speed 10 Mbps/100 Mbps
 - .4 FC Bus Normal Communications/No Field Communications
 - .5 Peer Communication Data Traffic Between NAE Devices
 - .6 Run NAE Running/NAE In Start-up/NAE Shutting Down/Software Not Running
 - .7 Bat Fault Battery Defective, Data Protection Battery Not Installed

- .8 Fault General Fault
- .9 Modem RX NAE Modem Receiving Data
- .10 Modem TX NAE Modem Transmitting Data
- .8 Communications Ports The NAE shall provide the following ports for operation of operator Input/Output (I/O) devices, such as industry-standard computers, modems, and portable operator's terminals.
 - .1 Up to two (2) USB port
 - .2 Up to two (2) URS-232 serial data communication port
 - .3 Up to two (2) RS-485 port
 - .4 One (1) Ethernet port
- .9 Diagnostics The NAE shall continuously perform self-diagnostics, communication diagnosis, and diagnosis of all panel components. The Network Automation Engine shall provide both local and remote annunciation of any detected component failures, low battery conditions, or repeated failures to establish communication.
- .10 Power Failure In the event of the loss of normal power, The NAE shall continue to operate for a user adjustable period of up to 10 minutes after which there shall be an orderly shutdown of all programs to prevent the loss of database or operating system software.
 - .1 During a loss of normal power, the control sequences shall go to the normal system shutdown conditions. All critical configuration data shall be saved into Flash memory.
 - .2 Upon restoration of normal power and after a minimum off-time delay, the controller shall automatically resume full operation without manual intervention through a normal soft-start sequence.
- .11 Certification The NAE shall be listed by Underwriters Laboratories (UL).
- .12 Controller network The NAE shall support the following communication protocols on the controller network:
 - .1 The NAE shall support BACnet Standard MS/TP Bus Protocol ASHRAE SSPC-135, Clause 9 on the controller network.
 - .1 A BACnet Protocol Implementation Conformance Statement shall be provided for each controller device (master or slave) that will communicate on the BACnet MS/TP Bus.
 - .2 The Conformance Statements shall be submitted 10 day prior to bidding.
 - .3 The NAE shall support a minimum of 100 control devices.

- .1 All LonWorks controls devices shall be LonMark certified.
- .2 The NAE shall support a minimum of 255 LonWorks enabled control devices.
- .3 The NAE shall support the Johnson Controls N2 Field Bus.
 - .1 The NAE shall support a minimum of 100 N2 control devices.
 - .2 The Bus shall conform to Electronic Industry Alliance (EIA) Standard RS-485.
 - .3 The Bus shall employ a master/slave protocol where the NAE is the master.
 - .4 The Bus shall employ a four (4) level priority system for polling frequency.
 - .5 The Bus shall be optically isolated from the NAE.
 - .6 The Bus shall support the Metasys Integrator System.

2.4 DDC System Controllers

- .1 Digital Controller w/ extension capability (DX)
 - .1 Each DX shall operate as a standalone controller capable of performing its specified control responsibilities independently of other controllers in the network. Each DCX shall be a microprocessor-Based, multi-tasking, real-time digital control processor.
 - .2 DX controllers shall support, but not be limited to, the following configurations of systems to address current requirements described in the "Execution" portion of this Specification, and to address future expansion.
 - .1 Single boiler or chiller plants with pump logic.
 - .2 Cooling towers.
 - .3 Large, built-up Air Handling Units for special applications.
 - .4 Generic system interlocking through hardware.
 - .3 Point types Each DX shall support the following types of point inputs and outputs:
 - .1 Analog inputs shall monitor the following analog signals:
 - .1 4-20 mA Sensors
 - .2 0-10 VDC Sensors
 - .3 1000ohm RTDs

- .2 Binary inputs shall monitor dry contact closures. Input shall provide filtering to eliminate false signals resulting from input "bouncing."
- .3 Counter inputs shall monitor dry contact pulses with an input resolution of one HZ minimum.
- .4 Analog outputs shall provide the following control outputs:
 - .1 4.20 mA Sink or Source
 - .2 0-10 VDC
- .5 Binary outputs shall provide SPDT output contacts rated for 2 amps at 24 VAC. Surge and noise suppression shall be provided on all pilot relays. Inductive loads (i.e. solenoids) shall be controlled by pilot relays.
- .6 Tri-state outputs shall be paired binary outputs for use as Power Close/Power Open control output contacts rated for 2 amps at 24 VAC. Surge and noise suppression shall be provided on all pilot relays.
- .4 Controllers shall have a built-in status, and adjust panel interface to allow for the local adjustment of all setpoints, temporary override of any input or output points, and status of any points in alarm.
- .5 Power fail Protection All system setpoints, proportional bands, control algorithms, and any other programmable parameters shall be stored such that a power failure of any duration does not necessitate reprogramming the DX-9100.
- .6 The capability to extend the input and output capacity of the DX via Point Expansion Modules shall be provided.
 - .1 The Point Expansion Modules shall communicate to the DX controller over a local RS-485 expansion bus.
 - .2 The Point Expansion Modules shall have available a range of configurations of 4, 8, 12, or 16 data points:
 - .1 Analog Inputs 0-10 V, 4-20 mA, 1000 ohm RTD
 - .2 Analog Outputs 0-10 V, 4-20 mA
 - .3 Digital Inputs w/ digital counter
 - .4 Digital Outputs triacs or relay contacts
 - .3 Expansion module data points shall be available for inclusion in all DX control strategies.

- .2 Unitary Controllers (UNT)
 - .1 Each Unitary Controller shall operate as a standalone controller capable of performing its specified control responsibilities independently of other controllers in the network. Each Unitary Controller shall be a microprocessor-Based, multi-tasking, real-time digital control processor.
 - .2 Unitary Controllers shall support, but not be limited to, the following types of systems to address specific applications described in the "Execution" portion of this Specification, and to address future expansion:
 - .1 Unit Vents (ASHRAE Cycle, I, II, III, or W).
 - .2 Heat Pumps (Air-to-Air, Water-to-Air).
 - .3 Packaged Rooftops.
 - .4 Fan Coils (Two-Pipe, Four-Pipe).
 - .3 Point types Each Unitary Controller shall support the following types of point inputs and outputs:
 - .1 Analog inputs shall monitor the following analog signals:
 - .1 0-10 VDC Sensors
 - .2 1000 ohm RTDs
 - .2 Binary inputs shall monitor dry contact closures. Input shall provide filtering to eliminate false signals resulting from input "bouncing."
 - .3 Counter inputs shall monitor dry contact pulses with an input resolution of one HZ minimum.
 - .4 Analog outputs shall provide the following control outputs:
 - .1 0-10 VDC
 - .5 Binary outputs shall provide SPDT output contacts rated for 2 amps at 24 VAC. Surge and noise suppression shall be provided on all pilot relays. Inductive loads (i.e. solenoids) shall be controlled by pilot relays.
 - .6 Tri-state outputs shall be paired binary outputs for use as Power Close/Power Open control output contacts rated for 2 amps at 24 VAC. Surge and noise suppression shall be provided on all pilot relays.
 - .7 Pneumatic outputs shall provide a 3-15 PSI pneumatic output. Gradual override capability and output pressure gauge shall be provided.
 - .4 Unitary Controllers shall have a library of control routines and program logic to perform the sequence of operations specified in the "Execution" portion of this Specification.

- .5 Unitary Controllers shall directly support the temporary use of a portable service terminal that can be connected to the UNT via zone temperature or directly at the controller.
- .6 Power fail Protection All system setpoints, proportional bands, control algorithms, and any other programmable parameters shall be stored such that a power failure of any duration does not necessitate reprogramming the UNT.
- .3 VAV Modular Assembly (VMA)
 - .1 The VAV Modular Assembly shall provide both standalone and networked direct digital control of pressure-independent, variable air volume terminal units. It shall address both single and dual duct applications.
 - .2 The VAV Modular Assembly shall be a configurable digital controller with integral differential pressure transducer and damper actuator. All components shall be connected and mounted as a single assembly that can be removed as one piece.
 - .3 The integral damper actuator shall be a fast response stepper motor capable of stroking 90 degrees in 30 seconds for quick damper positioning to speed commissioning and troubleshooting tasks.
 - .4 The controller shall determine airflow by dynamic pressure measurement using an integral dead-ended differential pressure transducer. The transducer shall be maintenance-free and shall not require air filters.
 - .5 Each controller shall have the ability to automatically calibrate the flow sensor to eliminate pressure transducer offset error due to ambient temperature / humidity effects.
 - .6 The controller shall utilize a proportional plus integration (PI) algorithm for the space temperature control loops.
 - .7 Each controller shall continuously, adaptively tune the control algorithms to improve control and controller reliability through reduced actuator duty cycle. In addition, this tuning reduces commissioning costs, and eliminates the maintenance costs of manually re-tuning loops to compensate for seasonal or other load changes.
 - .8 The controller shall provide the ability to download and upload VMA configuration files, both locally and via the communications network. Controllers shall be able to be loaded individually or as a group using a zone schedule generated spreadsheet of controller parameters.
 - .9 Control setpoint changes initiated over the network shall be written to VMA non-volatile memory to prevent loss of setpoint changes and to provide consistent operation in the event of communication failure.
 - .10 The controller firmware shall be flash-upgradeable remotely via the communications bus to minimize costs of feature enhancements.

- .11 The VMA shall include troubleshooting LED indicators to identify the following conditions:
 - .1 Power On
 - .2 Power Off
 - .3 VMA Off Line
 - .4 VMA Replacement
 - .5 VMA Corrupted Memory
- .12 The controller shall provide fail-soft operation if the airflow signal becomes unreliable, by automatically reverting to a pressure-dependent control mode.
- .13 The controller shall interface with balancer tools that allow automatic recalculation of box flow pickup gain ("K" factor), and the ability to directly command the airflow control loop to the box minimum and maximum airflow setpoints.
- .14 Controller performance shall be self-documenting via on-board diagnostics. These diagnostics shall consist of control loop performance measurements executing at each control loop's sample interval, which may be used to continuously monitor and document system performance. The VMA shall calculate exponentially weighted moving averages (EWMA) for each of the following. These metrics shall be available to the end user for efficient management of the VAV terminals.
 - .1 Absolute temperature loop error.
 - .2 Signed temperature loop error.
 - .3 Absolute airflow loop error.
 - .4 Signed airflow loop error.
 - .5 Average damper actuator duty cycle.
- .15 The controller shall detect system error conditions to assist in managing the VAV zones. The error conditions shall consist of:
 - .1 Unreliable space temperature sensor.
 - .2 Unreliable differential pressure sensor.
 - .3 Starved box.
 - .4 Actuator stall
 - .5 Insufficient cooling.

- .6 Insufficient heating.
 - .1 The controller shall provide a flow test function to view damper position vs. flow in a graphical format. The information would alert the user to check damper position. The VMA would also provide a method to calculate actuator duty cycle as an indicator of damper actuator runtime.
- .16 The controller shall provide a compliant interface for ASHRAE Standard 62-1989 (indoor air quality), and shall be capable of resetting the box minimum airflow Based on the percent of outdoor air in the primary air stream.
- .17 The controller shall comply with ASHRAE Standard 90.1 (energy efficiency) by preventing simultaneous heating and cooling, and where the control strategy requires reset of airflow while in reheat, by modulating the box reheat device fully open prior to increasing the airflow in the heating sequence.
- .18 Inputs:
 - .1 Analog inputs with user defined ranges shall monitor the following analog signals, without the addition of equipment outside the terminal controller cabinet:
 - .1 0-10 VDC Sensors
 - .2 1000 ohm RTDs
 - .3 NTC Thermistors
 - .2 Binary inputs shall monitor dry contact closures. Input shall provide filtering to eliminate false signals resulting from input "bouncing."
 - .3 For noise immunity, the inputs shall be internally isolated from power, communications, and output circuits.
 - .4 Provide side loop application for humidity control.
- .19 Outputs
 - .1 Analog outputs shall provide the following control outputs:
 - .1 0-10 VDC
 - .2 Binary outputs shall provide a SPST Triac output rated for 500 mA at 24 VAC.
 - .3 For noise immunity, the outputs shall be internally isolated from power, communications, and other output circuits.
- .20 Application Configuration
 - .1 The VAV Modular Assembly shall be configured with a software tool that provides a simple Question/Answer format for developing applications and downloading.

ELECTRIC AND ELECTRONIC CONTROL SYSTEMS FOR HVAC

- .21 Sensor Support
 - .1 The VMA shall support an LCD display room sensor.
 - .2 The VMA shall also support standard room sensors as defined by analog input requirements.
 - .3 The VMA shall support humidity sensors defined by the AI side loop.

2.5 Input Devices

- .1 General Requirements
 - .1 Installation, testing, and calibration of all sensors, transmitters, and other input devices shall be provided to meet the system requirements.
- .2 Temperature Sensors
 - .1 General Requirements:
 - .1 Sensors and transmitters shall be provided, as outlined in the input/output summary and sequence of operations.
 - .2 The temperature sensor shall be of the resistance type, and shall be either twowire 1000 ohm nickel RTD, or two-wire 1000 ohm platinum RTD.
 - .3 The following point types (and the accuracy of each) are required, and their associated accuracy values include errors associated with the sensor, lead wire, and A to D conversion:

Point Type	Accuracy
Chilled Water	<u>+</u> .5°F.
Room Temp	<u>+</u> .5°F.
Duct Temperature	<u>+</u> .5°F.
All Others	<u>+</u> .75°F.

- .2 Room Temperature Sensors
 - .1 Room sensors shall be constructed for either surface or wall box mounting.
 - .2 Room sensors shall have the following options when specified:
 - .1 Setpoint reset slide switch providing a +3 degree (adjustable) range.
 - .2 Individual heating/cooling setpoint slide switches.
 - .3 A momentary override request push button for activation of after-hours operation.

- .4 Analog thermometer.
- .3 Room Temperature Sensors with Integral Display
 - .1 Room sensors shall be constructed for either surface or wall box mounting.
 - .2 Room sensors shall have an integral LCD display and four button keypad with the following capabilities:
 - .1 Display room and outside air temperatures.
 - .2 Display and adjust room comfort setpoint.
 - .3 Display and adjust fan operation status.
 - .4 Timed override request push button with LED status for activation of afterhours operation.
 - .5 Display controller mode.
 - .6 Password selectable adjustment of setpoint and override modes.
- .4 Thermo wells
 - .1 When thermo wells are required, the sensor and well shall be supplied as a complete assembly, including wellhead and Greenfield fitting.
 - .2 Thermo wells shall be pressure rated and constructed in accordance with the system working pressure.
 - .3 Thermo wells and sensors shall be mounted in a threadolet or 1/2 inch NFT saddle and allow easy access to the sensor for repair or replacement.
 - .4 Thermo wells shall be constructed of 316 stainless steel.
- .5 Outside Air Sensors
 - .1 Outside air sensors shall be designed to withstand the environmental conditions to which they will be exposed. They shall also be provided with a solar shield.
 - .2 Sensors exposed to wind velocity pressures shall be shielded by a perforated plate that surrounds the sensor element.
 - .3 Temperature transmitters shall be of NEMA 3R construction and rated for ambient temperatures.
- .6 Duct Mount Sensors
 - .1 Duct mount sensors shall mount in an electrical box through a hole in the duct, and be positioned so as to be easily accessible for repair or replacement.

- .2 Duct sensors shall be insertion type and constructed as a complete assembly, including lock nut and mounting plate.
- .3 For outdoor air duct applications, a weatherproof mounting box with weatherproof cover and gasket shall be used.
- .7 Averaging Sensors
 - .1 For ductwork greater in any dimension that 48 inches and/or where air temperature stratification exists, an averaging sensor with multiple sensing points shall be used.
 - .2 For plenum applications, such as mixed air temperature measurements, a string of sensors mounted across the plenum shall be used to account for stratification and/or air turbulence. The averaging string shall have a minimum of 4 sensing points per 12-foot long segment.
 - .3 Capillary supports at the sides of the duct shall be provided to support the sensing string.
- .8 Acceptable Manufacturers: Johnson Controls, Setra.
- .3 Humidity Sensors
 - .1 The sensor shall be a solid-state type, relative humidity sensor of the Bulk Polymer Design. The sensor element shall resist service contamination.
 - .2 The humidity transmitter shall be equipped with non-interactive span and zero adjustments, a 2-wire isolated loop powered, 4-20 mA, 0-100% linear proportional output.
 - .3 The humidity transmitter shall meet the following overall accuracy, including lead loss and Analog to Digital conversion. 3% between 20% and 80% RH @ 77°F unless specified elsewhere.
 - .4 Outside air relative humidity sensors shall be installed with a rain proof, perforated cover. The transmitter shall be installed in a NEMA 3R enclosure with sealtite fittings and stainless steel bushings.
 - .5 A single point humidity calibrator shall be provided, if required, for field calibration. Transmitters shall be shipped factory pre-calibrated.
 - .6 Duct type sensing probes shall be constructed of 304 stainless steel, and shall be equipped with a neoprene grommet, bushings, and a mounting bracket.
 - .7 Acceptable Manufacturers: Johnson Controls, Veris Industries, and Mamac.
- .4 Differential Pressure Transmitters
 - .1 General Air and Water Pressure Transmitter Requirements:

- .1 Pressure transmitters shall be constructed to withstand 100% pressure over-range without damage, and to hold calibrated accuracy when subject to a momentary 40% over-range input.
- .2 Pressure transmitters shall transmit a 0 to 5 VDC, 0 to 10 VDC, or 4 to 20 mA output signal.
- .3 Differential pressure transmitters used for flow measurement shall be sized to the flow sensing device, and shall be supplied with Tee fittings and shut-off valves in the high and low sensing pick-up lines to allow the balancing contractor and City permanent, easy-to-use connection.
- .4 A minimum of a NEMA 1 housing shall be provided for the transmitter. Transmitters shall be located in accessible local control panels wherever possible.
- .2 Low Differential Water Pressure Applications (0" 20" w.c.)
 - .1 The differential pressure transmitter shall be of industrial quality and transmit a linear, 4 to 20 mA output in response to variation of flow meter differential pressure or water pressure sensing points.
 - .2 The differential pressure transmitter shall have non-interactive zero and span adjustments that are adjustable from the outside cover and meet the following performance specifications:
 - .1 0.01-20" w.c. input differential pressure range.
 - .2 4-20 mA output.
 - .3 Maintain accuracy up to 20 to 1 ratio turndown.
 - .4 Reference Accuracy: +0.2% of full span.
 - .3 Acceptable Manufacturers: Setra and Mamac.
- .3 Medium to High Differential Water Pressure Applications (Over 21" w.c.)
 - .1 The differential pressure transmitter shall meet the low pressure transmitter specifications with the following exceptions:
 - .1 Differential pressure range 10" w.c. to 300 PSI.
 - .2 Reference Accuracy: +1% of full span (includes non-linearity, hysteresis, and repeatability).
 - .2 Standalone pressure transmitters shall be mounted in a bypass valve assembly panel. The panel shall be constructed to NEMA 1 standards. The transmitter shall be installed in the panel with high and low connections piped and valved. Air bleed units, bypass valves, and compression fittings shall be provided.
 - .3 Acceptable Manufacturers: Setra and Mamac.

- .4 Building Differential Air Pressure Applications (-1" to +1" w.c.)
 - .1 The differential pressure transmitter shall be of industrial quality and transmit a linear, 4 to 20 mA output in response to variation of differential pressure or air pressure sensing points.
 - .2 The differential pressure transmitter shall have non-interactive zero and span adjustments that are adjustable from the outside cover and meet the following performance specifications:
 - .1 -1.00 to +1.00 w.c. input differential pressure ranges. (Select range appropriate for system application)
 - .2 4-20 mA output.
 - .3 Maintain accuracy up to 20 to 1 ratio turndown.
 - .4 Reference Accuracy: +0.2% of full span.
 - .3 Acceptable Manufacturers: Johnson Controls and Setra.
- .5 Low Differential Air Pressure Applications (0" to 5" w.c.)
 - .1 The differential pressure transmitter shall be of industrial quality and transmit a linear, 4 to 20 mA output in response to variation of differential pressure or air pressure sensing points.
 - .2 The differential pressure transmitter shall have non-interactive zero and span adjustments that are adjustable from the outside cover and meet the following performance specifications:
 - .1 (0.00 1.00" to 5.00") w.c. input differential pressure ranges. (Select range appropriate for system application.)
 - .2 4-20 mA output.
 - .3 Maintain accuracy up to 20 to 1 ratio turndown.
 - .4 Reference Accuracy: +0.2% of full span.
 - .3 Acceptable Manufacturers: Johnson Controls and Setra.
- .6 Medium Differential Air Pressure Applications (5" to 21" w.c.)
 - .1 The pressure transmitter shall be similar to the Low Air Pressure Transmitter, except that the performance specifications are not as severe. Differential pressure transmitters shall be provided that meet the following performance requirements:
 - .1 Zero & span: (c/o F.S./Deg. F): .04% including linearity, hysteresis and repeatability.

- .2 Accuracy: 1% F.S. (best straight line) Static Pressure Effect: 0.5% F.S. (to 100 PSIG.
- .3 Thermal Effects: <+.033 F.S./°F. over 40°F. to 100°F. (calibrated at 70°F).
- .2 Standalone pressure transmitters shall be mounted in a bypass valve assembly panel. The panel shall be constructed to NEMA 1 standards. The transmitter shall be installed in the panel with high and low connections piped and valved. Air bleed units, bypass valves, and compression fittings shall be provided.
- .3 Acceptable manufacturers: Johnson Controls and Setra.
- .5 Status and Safety Switches
 - .1 General Requirements
 - .1 Switches shall be provided to monitor equipment status, safety conditions, and generate alarms at the BMS when a failure or abnormal condition occurs. Safety switches shall be provided with two sets of contacts and shall be interlock wired to shut down respective equipment.
 - .2 Current Sensing Switches
 - .1 The current sensing switch shall be self-powered with solid-state circuitry and a dry contact output. It shall consist of a current transformer, a solid state current sensing circuit, adjustable trip point, solid state switch, SPDT relay, and an LED indicating the on or off status. A conductor of the load shall be passed through the window of the device. It shall accept over-current up to twice its trip point range.
 - .2 Current sensing switches shall be used for run status for fans, pumps, and other miscellaneous motor loads.
 - .3 Current sensing switches shall be calibrated to show a positive run status only when the motor is operating under load. A motor running with a broken belt or coupling shall indicate a negative run status.
 - .4 Acceptable manufacturers: Veris Industries
 - .3 Air Filter Status Switches
 - .1 Differential pressure switches used to monitor air filter status shall be of the automatic reset type with SPDT contacts rated for 2 amps at 120VAC.
 - .2 A complete installation kit shall be provided, including: static pressure tops, tubing, fittings, and air filters.
 - .3 Provide appropriate scale range and differential adjustment for intended service.
 - .4 Acceptable manufacturers: Johnson Controls, Cleveland Controls

- .4 Air Flow Switches
 - .1 Differential pressure flow switches shall be bellows actuated mercury switches or snap acting micro-switches with appropriate scale range and differential adjustment for intended service.
 - .2 Acceptable manufacturers: Johnson Controls, Cleveland Controls
- .5 Air Pressure Safety Switches
 - .1 Air pressure safety switches shall be of the manual reset type with SPDT contacts rated for 2 amps at 120VAC.
 - .2 Pressure range shall be adjustable with appropriate scale range and differential adjustment for intended service.
 - .3 Acceptable manufacturers: Johnson Controls, Cleveland Controls
- .6 Water Flow Switches
 - .1 Water flow switches shall be equal to the Johnson Controls P74.
- .7 Low Temperature Limit Switches
 - .1 The low temperature limit switch shall be of the manual reset type with Double Pole/Single Throw snap acting contacts rated for 16 amps at 120VAC.
 - .2 The sensing element shall be a minimum of 15 feet in length and shall react to the coldest 18-inch section. Element shall be mounted horizontally across duct in accordance with manufacturers recommended installation procedures.
 - .3 For large duct areas where the sensing element does not provide full coverage of the air stream, additional switches shall be provided as required to provide full protection of the air stream.
 - .4 The low temperature limit switch shall be equal to Johnson Controls A70.

2.6 Output Devices

- .1 Actuators
 - .1 General Requirements
 - .1 Damper and valve actuators shall be electronic and/or pneumatic, as specified in the System Description section.
 - .2 Electronic Damper Actuators
 - .1 Electronic damper actuators shall be direct shaft mount.

- .2 Modulating and two-position actuators shall be provided as required by the sequence of operations. Damper sections shall be sized Based on actuator manufacturer's recommendations for face velocity, differential pressure and damper type. The actuator mounting arrangement and spring return feature shall permit normally open or normally closed positions of the dampers, as required. All actuators (except terminal units) shall be furnished with mechanical spring return unless otherwise specified in the sequences of operations. All actuators shall have external adjustable stops to limit the travel in either direction, and a gear release to allow manual positioning.
- .3 Modulating actuators shall accept 24 VAC or VDC power supply, consume no more than 15 VA, and be UL listed. The control signal shall be 2-10 VDC or 4-20 mA, and the actuator shall provide a clamp position feedback signal of 2-10 VDC. The feedback signal shall be independent of the input signal and may be used to parallel other actuators and provide true position indication. The feedback signal of one damper actuator for each separately controlled damper shall be wired back to a terminal strip in the control panel for trouble-shooting purposes.
- .4 Two-position or open/closed actuators shall accept 24 or 120 VAC power supply and be UL listed. Isolation, smoke, exhaust fan, and other dampers, as specified in the sequence of operations, shall be furnished with adjustable end switches to indicate open/closed position or be hard wired to start/stop associated fan. Two-position actuators, as specified in sequences of operations as "quick acting," shall move full stroke within 20 seconds. All smoke damper actuators shall be quick acting.
- .5 Acceptable manufacturers: Johnson Controls, Mamac.
- .3 Electronic Valve Actuators
 - .1 Electronic valve actuators shall be manufactured by the valve manufacturer.
 - .2 Each actuator shall have current limiting circuitry incorporated in its design to prevent damage to the actuator.
 - .3 Modulating and two-position actuators shall be provided as required by the sequence of operations. Actuators shall provide the minimum torque required for proper valve close-off against the system pressure for the required application. The valve actuator shall be sized Based on valve manufacturer's recommendations for flow and pressure differential. All actuators shall fail in the last position unless specified with mechanical spring return in the sequence of operations. The spring return feature shall permit normally open or normally closed positions of the valves, as required. All direct shaft mount rotational actuators shall have external adjustable stops to limit the travel in either direction.
 - .4 Modulating Actuators shall accept 24 VAC or VDC and 120 VAC power supply and be UL listed. The control signal shall be 2-10 VDC or 4-20 mA and the actuator shall provide a clamp position feedback signal of 2-10 VDC. The feedback signal shall be independent of the input signal, and may be used to parallel other actuators and provide true position indication. The feedback signal of each valve

actuator (except terminal valves) shall be wired back to a terminal strip in the control panel for trouble-shooting purposes.

- .5 Two-position or open/closed actuators shall accept 24 or 120 VAC power supply and be UL listed. Butterfly isolation and other valves, as specified in the sequence of operations, shall be furnished with adjustable end switches to indicate open/closed position or be hard wired to start/stop the associated pump or chiller.
- .6 Acceptable manufacturers: Johnson Controls
- .2 Control Dampers
 - .1 Furnish all automatic dampers. All automatic dampers shall be sized for the application by the Controls Contractor or as specifically indicated on the Drawings.
 - .2 All dampers used for throttling airflow shall be of the opposed blade type arranged for normally open or normally closed operation, as required. The damper is to be sized so that, when wide open, the pressure drop is a sufficient amount of its close-off pressure drop to shift the characteristic curve to near linear.
 - .3 All dampers used for two-position, open/close control shall be parallel blade type arranged for normally open or closed operation, as required.
 - .4 Damper frames and blades shall be constructed of either galvanized steel or aluminum. Maximum blade length in any section shall be 60". Damper blades shall be 16-gauge minimum and shall not exceed eight (8) inches in width. Damper frames shall be 16gauge minimum hat channel type with corner bracing. All damper bearings shall be made of reinforced nylon, stainless steel or oil-impregnated bronze. Dampers shall be tight closing, low leakage type, with synthetic elastomer seals on the blade edges and flexible stainless steel side seals. Dampers of 48"x48" size shall not leak in excess of 8.0 cfm per square foot when closed against 4" w.g. static pressure when tested in accordance with AMCA Std. 500.
 - .5 Airfoil blade dampers of double skin construction with linkage out of the air stream shall be used whenever the damper face velocity exceeds 1500 FPM or system pressure exceeds 2.5" w.g., but no more than 4000 FPM or 6" w.g. Acceptable manufacturers are Johnson Controls D-7250 D-1250 or D-1300, Ruskin CD50, and Vent Products 5650.
 - .6 One piece rolled blade dampers with exposed or concealed linkage may be used with face velocities of 1500 FPM or below. Acceptable manufacturers are: Johnson Controls D-1600, Ruskin CD36, and Vent Products 5800.
 - .7 Multiple section dampers may be jack-shafted to allow mounting of piston pneumatic actuators and direct connect electronic actuators. Each end of the jackshaft shall receive at least one actuator to reduce jackshaft twist.
- .3 Control Relays
 - .1 Control Pilot Relays
- .1 Control pilot relays shall be of a modular plug-in design with retaining springs or clips.
- .2 Mounting Bases shall be snap-mount.
- .3 DPDT, 3PDT, or 4PDT relays shall be provided, as appropriate for application.
- .4 Contacts shall be rated for 10 amps at 120VAC.
- .5 Relays shall have an integral indicator light and check button.
- .6 Acceptable manufacturers: Johnson Controls, Lectro
- .2 Lighting Control Relays
 - .1 Lighting control relays shall be latching with integral status contacts.
 - .2 Contacts shall be rated for 20 amps at 277 VAC.
 - .3 The coil shall be a split low-voltage coil that moves the line voltage contact armature to the ON or OFF latched position.
 - .4 Lighting control relays shall be controlled by:
 - .1 Pulsed Tri-state Output Preferred method.
 - .2 Pulsed Paired Binary Outputs.
 - .3 A Binary Input to the Facility Management System shall monitor integral status contacts on the lighting control relay. Relay status contacts shall be of the "dry-contact" type.
 - .5 The relay shall be designed so that power outages do not result in a change-ofstate, and so that multiple same state commands will simply maintain the commanded state. Example: Multiple OFF command pulses shall simply keep the contacts in the OFF position.
- .4 Control Valves
 - .1 All automatic control valves shall be fully proportioning and provide near linear heat transfer control. The valves shall be quiet in operation and fail-safe open, closed, or in their last position. All valves shall operate in sequence with another valve when required by the sequence of operations. All control valves shall be sized by the control manufacturer, and shall be guaranteed to meet the heating and cooling loads, as specified. All control valves shall be suitable for the system flow conditions and close against the differential pressures involved. Body pressure rating and connection type (sweat, screwed, or flanged) shall conform to the pipe schedule elsewhere in this Specification.

- .2 Chilled water control valves shall be modulating plug, ball, and/or butterfly, as required by the specific application. Modulating water valves shall be sized per manufacturer's recommendations for the given application. In general, valves (2 or 3-way) serving **variable** flow air handling unit coils shall be sized for a pressure drop equal to the actual coil pressure drop, but no less than 5 PSI. Valves (3-way) serving **constant** flow air handling unit coils with secondary circuit pumps shall be sized for a pressure drop equal to 25% the actual coil pressure drop, but no less than 2 PSI. Mixing valves (3-way) serving secondary water circuits shall be sized for a pressure drop of no less than 5 PSI. Valves for terminal reheat coils shall be sized for a 2 PSIG pressure drop, but no more than a 5 PSI drop.
- .3 Ball valves shall be used for hot and chilled water applications, water terminal reheat coils, radiant panels, unit heaters, package air conditioning units, and fan coil units except those described hereinafter.
- .4 Modulating plug water valves of the single-seat type with equal percentage flow characteristics shall be used for all special applications as indicated on the valve schedule. Valve discs shall be composition type. Valve stems shall be stainless steel.
- .5 Butterfly valves shall be acceptable for modulating large flow applications greater than modulating plug valves, and for all two-position, open/close applications. In-line and/or three-way butterfly valves shall be heavy-duty pattern with a body rating comparable to the pipe rating, replaceable lining suitable for temperature of system, and a stainless steel vane. Valves for modulating service shall be sized and travel limited to 50 degrees of full open. Valves for isolation service shall be the same as the pipe. Valves in the closed position shall be bubble-tight.
- .6 Acceptable manufacturers: Johnson Controls
- .5 Electronic Signal Isolation Transducers
 - .1 A signal isolation transducer shall be provided whenever an analog output signal from the BMS is to be connected to an external control system as an input (such as a chiller control panel), or is to receive as an input signal from a remote system.
 - .2 The signal isolation transducer shall provide ground plane isolation between systems.
 - .3 Signals shall provide optical isolation between systems.
 - .4 Acceptable manufacturers: Advanced Control Technologies
- .6 External Manual Override Stations
 - .1 External manual override stations shall provide the following:
 - .1 An integral HAND/OFF/AUTO switch shall override the controlled device pilot relay.
 - .2 A status input to the Facility Management System shall indicate whenever the switch is not in the automatic position.
 - .3 A Status LED shall illuminate whenever the output is ON.

- .4 An Override LED shall illuminate whenever the HOA switch is in either the HAND or OFF position.
- .5 Contacts shall be rated for a minimum of 1 amp at 24 VAC.
- .7 Electronic/Pneumatic Transducers
 - .1 Electronic to Pneumatic transducers shall provide:
 - .1 Output: 3-15 PSIG.
 - .2 Input: 4-20 mA or 0-10 VDC.
 - .3 Manual output adjustment.
 - .4 Pressure gauge.
 - .5 External replaceable supply air filter.
 - .6 Acceptable manufacturers: Johnson Controls, Mamac

2.7 Miscellaneous Devices

- .1 Variable Frequency Motor Speed Control Drives (VFD). Where shown on the drawings, adjustable frequency drives 1 through 75 HP shall have the following features:
 - .1 The VFD shall be rated for 600 Vac (optional input voltages of 208, 240 Vac through 30 HP). The VFD shall provide microprocessor based control for three-phase induction motors. The controller's full load output current rating shall be based on variable torque application at 40° C ambient and 1-16 kHz switching frequency below 50 HP and 1-10 kHz 50 HP and above to reduce motor noise and avoid increased motor losses.
 - .2 The VFD shall be of the Pulse Width Modulated (PWM) design converting the utility input voltage and frequency to a variable voltage and frequency output via a two-step operation. Adjustable Current Source VFD are not accepted. Insulated Gate Bipolar Transistors (IGBTs) shall be used in the inverter section. Bipolar Junction Transistors, GTOs or SCRs are not accepted. The VFD shall run at the above listed switching frequencies.
 - .3 The VFD shall have efficiency at full load and speed that exceeds 95% for VFD below 15 HP and 97% for drives 15 HP and above. The efficiency shall exceed 90% at 50% speed and load.
 - .4 The VFD shall maintain a minimum line side displacement power factor of 0.96, regardless of speed and load.
 - .5 The VFD shall have a one (1) minute overload current rating of 110% for variable torque applications.
 - .6 The VFD shall be capable of operating any NEMA design B squirrel cage induction motor, regardless of manufacturer, with a horsepower and current rating within the capacity of the VFD.

- The VFD shall have an integral EMI/RFI filter as standard. .7
- The VFD shall limit harmonic distortion reflected onto the utility system to voltage and .8 current levels as defined by IEEE 519-1992 for general systems applications, by utilizing the standard 3% nominal impedance integral ac three-phase line reactor. DC link chokes are not accepted.
- Any harmonic calculations shall be done based on the kVA capacity, X/R ratio and the .9 impedance of the utility transformer feeding the installation, as noted on the drawings, and the total system load. The calculations shall be made with the point of common coupling (PCC) being the point where the utility feeds multiple customers.
- .10 Total harmonic distortion shall be calculated under worst case conditions in accordance with the procedure outlined in IEEE 519-1992. Copies of these calculations are to be made available upon request. Provide any needed information to the VFD supplier three (3) weeks prior to requiring harmonic calculations.
- .11 The system containing the VFD shall comply with the 5% level of total harmonic distortion of line voltage and the line current limits as defined in IEEE 519-1992. If the system cannot meet the harmonic levels with the VFD provided with the standard input line reactor or optional input isolation transformer, the VFD manufacturer shall supply an eighteen pulse, multiple bridge rectifier ac to dc conversion section with phase shifting transformer for all drives above 75 HP. This eighteen pulse rectifier converter shall result in a multiple pulse current waveform that will more nearly approximate a true sinewave to reduce voltage harmonic content on the utility line. The phase shifting transformer shall be of a single winding type to optimize its KVA rating and harmonic cancellation capability.
 - Harmonic filters are not accepted above 75 HP. .1
- .12 The VFD shall be able to start into a spinning motor. The VFD shall be able to determine the motor speed in any direction and resume operation without tripping. If the motor is spinning in the reverse direction, the VFD shall start into the motor in the reverse direction, bring the motor to a controlled stop, and then accelerate the motor to the preset speed.
- .13 Standard operating conditions shall be:
 - Incoming Power: Three-phase, 208 / 240 / 480 (+10% to -15%) and 50/60 Hz .1 (+/- 5 Hz) power to a fixed potential DC bus level.
 - .2 Frequency stability of +/-0.05% for 24 hours with voltage regulation of +/-1% of maximum rated output voltage.
 - .3 Speed regulation of +/- 0.5% of base speed.
 - .4 Load inertia dependant carryover (ridethrough) during utility loss.
 - .5 Insensitive to input line rotation.
 - .6 Humidity: 0 to 95% (non-condensing and non-corrosive).

- .7 Altitude: 0 to 3,300 feet (1000 meters) above sea level.
- .8 Ambient Temperature: -10 to 40°C (VT).
- .9 Storage Temperature: -40 to 70°C.
- .14 Control Functions
 - .1 Frequently accessed VFD programmable parameters shall be adjustable from a digital operator keypad located on the front of the VFD. The VFD shall have a 3 line alphanumeric programmable display with status indicators. Keypads must use plain English words for parameters, status, and diagnostic messages. Keypads that are difficult to read or understand are not accepted, and particularly those that use alphanumeric code and tables. Keypads shall be adjustable for contrast with large characters easily visible in normal ambient light.
 - .2 The keypad shall include a Hand-Off-Auto membrane selection and an Inverter/Bypass membrane selection. When in "Hand" the VFD will be started and the speed will be controlled from the up/down arrows. When in "Off", the VFD will be stopped. In "Auto", the VFD will start via an external contact closure or a communication network and the VFD speed will be controlled via an external speed reference.
 - .3 The keypad shall have copy / paste capability.
 - .4 Upon initial power up of the VFD, the keypad shall display a start up guide that will sequence all the necessary parameter adjustments for general start up.
 - .5 Standard advanced programming and trouble-shooting functions shall be available by using a personal computer's RS-232 port and Windows[™] based software. In addition the software shall permit control and monitoring via the VFD's RS232 port. The manufacturer shall supply a diskette with the required software. An easily understood instruction manual and software help screens shall also be provided. The computer software shall be used for modifying the drive setup and reviewing diagnostic and trend information as outlined in this section through section 18.
 - .6 The operator shall be able to scroll through the keypad menu to choose between the following:
 - .1 Parameter Menu
 - .2 Keypad Control
 - .3 System Menu
 - .4 Expander Boards
 - .5 Monitoring Menu
 - .6 Operate Menu

- .7 The following setups and adjustments, at a minimum, are to be available:
 - .1 Start command from keypad, remote or communications port
 - .2 Speed command from keypad, remote or communications port
 - .3 Motor direction selection
 - .4 Maximum and minimum speed limits
 - .5 Acceleration and deceleration times, two settable ranges
 - .6 Critical (skip) frequency avoidance
 - .7 Torque limit
 - .8 Multiple attempt restart function
 - .9 Multiple preset speeds adjustment
 - .10 Catch a spinning motor start or normal start selection
 - .11 Programmable analog output
- .15 The VFD shall have the following system interfaces:
 - .1 Inputs A minimum of six (6) programmable digital inputs, two (2) analog inputs and serial communications interface shall be provided with the following available as a minimum:
 - .1 Remote manual/auto
 - .2 Remote start/stop
 - .3 Remote forward/reverse
 - .4 Remote preset speeds
 - .5 Remote external trip
 - .6 Remote fault reset
 - .7 Process control speed reference interface, 4-20mAdc
 - .8 Potentiometer or process control speed reference interface, 0 -10Vdc
 - .9 RS232 programming and operation interface port
 - .2 Outputs A minimum of two (2) discrete programmable digital outputs, one (1) programmable open collector output, and one (1) programmable analog output shall be provided, with the following available at minimum.

- .1 Programmable relay outputs with one (1) set of Form C contacts for each, selectable with the following available at minimum:
 - .1 Fault
 - .2 Run
 - .3 Ready
 - .4 Reversing
 - .5 Jogging
 - .6 At speed
 - .7 In torque limit
 - .8 Motor rotation direction opposite of commanded
 - .9 Overtemperature
- .2 Programmable open collector output with available 24 VDC power supply and selectable with the following available at minimum:
 - .1 Fault
 - .2 Run
 - .3 Ready
 - .4 Reversing
 - .5 Jogging
 - .6 At speed
 - .7 In torque limit
 - .8 Motor rotation direction opposite of commanded
 - .9 Overtemperature
- .3 Programmable analog output signal, selectable with the following available at minimum:
 - .1 Output frequency
 - .2 Frequency reference
 - .3 Motor speed

- .4 Output current
- .5 Motor torque
- .6 Motor power
- .7 Motor voltage
- .8 DC link voltage
- .9 PID controller reference value
- .10 PID controller actual value 1
- .11 PID controller actual value 2
- .12 PID controller error value
- .13 PID controller output
- .3 Capability of two additional expandable I/O interface cards. Upon installation, software shall automatically identify the interface card and activate the appropriate parameters.
- .16 Monitoring and Displays
 - .1 The VFD's display shall be a LCD type capable of displaying three (3) lines of text and the following thirteen (13) status indicators:
 - .1 Run
 - .2 Forward
 - .3 Reverse
 - .4 Stop
 - .5 Ready
 - .6 Alarm
 - .7 Fault
 - .8 I/O Terminal
 - .9 Keypad
 - .10 Bus/comm
 - .11 Hand
 - .12 Auto

.13 Off

- .2 The VFD's keypad shall be capable of displaying the following monitoring functions at a minimum:
 - .1 Motor Speed (RPM and %)
 - .2 Frequency reference
 - .3 Output frequency
 - .4 Motor current
 - .5 Motor torque
 - .6 Motor power
 - .7 Motor voltage
 - .8 DC-link voltage
 - .9 Heatsink temperature
 - .10 Motor run time (resetable)
 - .11 Total operating days counter
 - .12 Operating hours (resetable)
 - .13 Total megawatt hours
 - .14 Megawatt hours (resetable)
 - .15 Voltage level of analog input
 - .16 Current level of analog input
 - .17 Digital inputs status
 - .18 Digital and relay outputs status
 - .19 Motor temperature rise
 - .20 PID references
- .17 Protective Functions
 - .1 The VFD shall include the following protective features at minimum:
 - .1 Overcurrent
 - .2 Overvoltage

ELECTRIC AND ELECTRONIC CONTROL SYSTEMS FOR HVAC

- .3 System fault
- .4 Undervoltage
- .5 Input line supervision
- .6 Output phase supervision
- .7 Undertemperature
- .8 Overtemperature
- .9 Motor stalled
- .10 Motor overtemperature
- .11 Motor underload
- .12 Logic voltage failure
- .13 Microprocessor failure
- .14 Brake chopper supervision
- .15 DC Injection braking
- .2 The VFD shall provide ground fault protection during power-up, starting, and running. VFD's with no ground fault protection during running are not accepted.
- .18 Diagnostic Features
 - .1 Active Faults
 - .1 The last 10 faults shall be recorded and stored in sequential order
 - .2 Fault code and description of fault shall be displayed on the keypad.
 - .3 Fault or alarm LED shall blink
 - .4 Display drive data at time of fault
 - .5 In the event several faults occur simultaneously, the sequence of active faults shall be viewable.
 - .2 Fault History
 - .1 The last 30 faults shall be recorded and stored in sequential order.
 - .2 Display drive data at time of fault

- .19 Additional features included in the VFD
 - .1 A HMCP or MMP device shall provide a disconnect means with provision for lockout. Disconnect handles mounted on the door will not be accepted. The handle position shall indicate ON and OFF condition. Operator shall be interlocked with cover to prevent opening with disconnect in the ON position.
 - .2 The following indicating lights shall be provided on the keypad.
 - .1 Drive/Bypass Ready (Flashing in Bypass Mode)
 - .2 Drive/Bypass Run
 - .3 Drive Fault
 - .3 The current withstand rating of the drive shall be 100,000 AIC. The bypass shall have an interrupting capacity of 65,000 AIC or greater. The combined withstand rating of drive and bypass must be 65,000 AIC or higher.
 - .4 The VFD shall have a cooling fan that is field replaceable using non-screw accessibility.
- .20 Enclosure
 - .1 The VFD and bypass shall be designed in a NEMA Type 1 enclosure to provide enhanced protection against radiated EMI/RFI.
 - .2 The VFD shall have complete front accessibility with easily removable assemblies.
 - .3 Cable entry shall be top or bottom entry.
- .21 Acceptable Manufacturers
 - .1 Eaton/Cutler Hammer (Johnson Controls)
 - .2 ABB
 - .3 Danfoss
- .2 Local Control Panels
 - .1 All control panels shall be factory constructed, incorporating the BMS manufacturer's standard designs and layouts. All control panels shall be UL inspected and listed as an assembly and carry a UL 508 label listing compliance. Control panels shall be fully enclosed, with perforated sub-panel, hinged door, and slotted flush latch.
 - .2 In general, the control panels shall consist of the DDC controller(s), display module as specified and indicated on the plans, and I/O devices—such as relays, transducers, and so forth—that are not required to be located external to the control panel due to function. Where specified the display module shall be flush mounted in the panel face unless otherwise noted.

- .3 All I/O connections on the DDC controller shall be provide via removable or fixed screw terminals.
- .4 Low and line voltage wiring shall be segregated. All provided terminal strips and wiring shall be UL listed, 300-volt service and provide adequate clearance for field wiring.
- .5 All wiring shall be neatly installed in plastic trays or tie-wrapped.
- .6 A convenience 120 VAC duplex receptacle shall be provided in each enclosure, fused on/off power switch, and required transformers.
- .3 Power Supplies
 - .1 DC power supplies shall be sized for the connected device load. Total rated load shall not exceed 75% of the rated capacity of the power supply.
 - .2 Input: 120 VAC +10%, 60Hz.
 - .3 Output: 24 VDC.
 - .4 Line Regulation: +0.05% for 10% line change.
 - .5 Load Regulation: +0.05% for 50% load change.
 - .6 Ripple and Noise: 1 mV rms, 5 mV peak to peak.
 - .7 An appropriately sized fuse and fuse block shall be provided and located next to the power supply.
 - .8 A power disconnect switch shall be provided next to the power supply.
- .4 Thermostats
 - .1 Electric room thermostats of the heavy-duty type shall be provided for unit heaters, cabinet unit heaters, and ventilation fans, where required. All these items shall be provided with concealed adjustment. Finish of covers for all room-type instruments shall match and, unless otherwise indicated or specified, covers shall be manufacturer's standard finish.
- .5 Speed Controller
 - .1 Single Phase Fan Speed control for EF-1, shall be controlled by Johnson Controls S66 Electronic Fan Speed Controller.

3. PERFORMANCE/EXECUTION

3.1 BMS Specific Requirements

.1 Graphic Displays

- .1 Provide a color graphic system flow diagram display for each system with all points as indicated on the point list. All terminal unit graphic displays shall be from a standard design library.
- .2 User shall access the various system schematics via a graphical penetration scheme and/or menu selection.
- .2 Custom Reports:
 - .1 Provide custom reports as required for this Work:
- .3 Actuation / Control Type
 - .1 Primary Equipment
 - .1 Controls shall be provided by equipment manufacturer as specified herein.
 - .2 All damper and valve actuation shall be electric.
 - .2 Air Handling Equipment
 - .1 All air handers shall be controlled with a HVAC-DDC Controller
 - .2 All damper and valve actuation shall be electric.
 - .3 Terminal Equipment:
 - .1 Terminal Units (VAV, UV, etc.) shall have electric damper and valve actuation.
 - .2 All Terminal Units shall be controlled with HVAC-DDC Controller)

3.2 Installation Practices

- .1 BMS Wiring
 - .1 Provide all conduit, wiring, accessories and wiring connections required for the installation of the Building Management System, as herein specified unless specifically shown on the Electrical Drawings under Division 26 Electrical. All wiring shall comply with the requirements of applicable portions of Division 26 and all local and national electric codes, unless specified otherwise in this section.
 - .2 All BMS wiring materials and installation methods shall comply with BMS manufacturer recommendations.
 - .3 The sizing, type and provision of cable, conduit, cable trays, and raceways shall be the design responsibility of the Controls Contractor.
 - .4 Class 2 Wiring
 - .1 All Class 2 (24VAC or less) wiring shall be installed in conduit unless otherwise specified.

- .2 Conduit is not required for Class 2 wiring in concealed accessible locations. Class 2 wiring not installed in conduit shall be supported every 5' from the building structure utilizing metal hangers designed for this application. Wiring shall be installed parallel to the building structural lines. All wiring shall be installed in accordance with local code requirements.
- .5 Class 2 signal wiring and 24VAC power can be run in the same conduit. Power wiring 120VAC and greater cannot share the same conduit with Class 2 signal wiring.
- .6 Provide for complete grounding of all applicable signal and communications cables, panels and equipment so as to ensure system integrity of operation. Ground cabling and conduit at the panel terminations. Avoid grounding loops.
- .2 BMS Line Voltage Power Source
 - .1 120-volt AC circuits used for the Building Management System shall be taken from panel boards and circuit breakers provided by Division 26.
 - .2 Circuits used for the BMS shall be dedicated to the BMS and shall not be used for any other purposes.
 - .3 DDC terminal unit controllers may use AC power from motor power circuits.
- .3 BMS Raceway
 - .1 All wiring shall be installed in conduit or raceway except as noted elsewhere in this specification. Minimum control wiring conduit size 1/2".
 - .2 Where it is not possible to conceal raceways in finished locations, surface raceway (Wiremold) may be used as approved by the Contract Administrator.
 - .3 All conduits and raceways shall be installed level, plumb, at right angles to the building lines and shall follow the contours of the surface to which they are attached.
 - .4 Flexible Metal Conduit shall be used for vibration isolation and shall be limited to 3 feet in length when terminating to vibrating equipment. Flexible Metal Conduit may be used within partition walls. Flexible Metal Conduit shall be UL listed.
- .4 Penetrations
 - .1 Provide fire stopping for all penetrations used by dedicated BMS conduits and raceways.
 - .2 All openings in fire proofed or fire stopped components shall be closed by using approved fire resistive sealant.
 - .3 All wiring passing through penetrations, including walls shall be in conduit or enclosed raceway.
 - .4 Penetrations of floor slabs shall be by core drilling. All penetrations shall be plumb, true, and square.

- .5 BMS Identification Standards
 - .1 Node Identification. All nodes shall be identified by a permanent label fastened to the enclosure. Labels shall be suitable for the node location.
 - .2 Cable types specified in Item A shall be color coded for easy identification and troubleshooting.
- .6 BMS Panel Installation
 - .1 The BMS panels and cabinets shall be located as indicated at an elevation of not less than 2 feet from the bottom edge of the panel to the finished floor. Each cabinet shall be anchored per the manufacturer's recommendations.
 - .2 Coordinate panel locations with other trades.
- .7 Input Devices
 - .1 All Input devices shall be installed per the manufacturer recommendation
 - .2 Locate components of the BMS in accessible local control panels wherever possible.
- .8 HVAC Input Devices Genera1
 - .1 All Input devices shall be installed per the manufacturer recommendation
 - .2 Locate components of the BMS in accessible local control panels wherever possible.
 - .3 The mechanical contractor shall install all in-line devices such as temperature wells, pressure taps, airflow stations, etc.
 - .4 Input Flow Measuring Devices shall be installed in strict compliance with ASME guidelines affecting non-standard approach conditions.
 - .5 Outside Air Sensors
 - .1 Sensors shall be mounted on the North wall to minimize solar radiant heat impact or located in a continuous intake flow adequate to monitor outside air conditions accurately.
 - .2 Sensors shall be installed with a rain proof, perforated cover.
 - .6 Water Differential Pressure Sensors
 - .1 Differential pressure transmitters used for flow measurement shall be sized to the flow-sensing device.
 - .2 Differential pressure transmitters shall be supplied with tee fittings and shut-off valves in the high and low sensing pick-up lines.
 - .3 The transmitters shall be installed in an accessible location wherever possible.

- .7 Medium to High Differential Water Pressure Applications (Over 21" w.c.):
 - .1 Air bleed units, bypass valves and compression fittings shall be provided.
- .8 Building Differential Air Pressure Applications (-1" to +1" w.c.):
 - .1 Transmitters exterior sensing tip shall be installed with a shielded static air probe to reduce pressure fluctuations caused by wind.
 - .2 The interior tip shall be inconspicuous and located as shown on the drawings.
- .9 Air Flow Measuring Stations:
 - .1 Where the stations are installed in insulated ducts, the airflow passage of the station shall be the same size as the inside airflow dimension of the duct.
 - .2 Station flanges shall be two inch to three inch to facilitate matching connecting ductwork.
- .10 Duct Temperature Sensors:
 - .1 Duct mount sensors shall mount in an electrical box through a hole in the duct and be positioned so as to be easily accessible for repair or replacement.
 - .2 The sensors shall be insertion type and constructed as a complete assembly including lock nut and mounting plate.
 - .3 For ductwork greater in any dimension than 48 inches or where air temperature stratification exists such as a mixed air plenum, utilize an averaging sensor.
 - .4 The sensor shall be mounted to suitable supports using factory approved element holders.
- .11 Space Sensors:
 - .1 Shall be mounted per ADA requirements.
 - .2 Provide lockable tamper-proof covers in public areas and/or where indicated on the plans.
- .12 Low Temperature Limit Switches:
 - .1 Install on the discharge side of the first water or steam coil in the air stream.
 - .2 Mount element horizontally across duct in a serpentine pattern insuring each square foot of coil is protected by 1 foot of sensor.
 - .3 For large duct areas where the sensing element does not provide full coverage of the air stream, provide additional switches as required to provide full protection of the air stream.

- .13 Air Differential Pressure Status Switches:
 - .1 Install with static pressure tips, tubing, fittings, and air filter.
- .14 Water Differential Pressure Status Switches:
 - .1 Install with shut off valves for isolation.
- .9 HVAC Output Devices
 - .1 All output devices shall be installed per the manufacturer's recommendation. The mechanical contractor shall install all in-line devices such as control valves, dampers, airflow stations, pressure wells, etc.
 - .2 Actuators: All control actuators shall be sized capable of closing against the maximum system shut-off pressure. The actuator shall modulate in a smooth fashion through the entire stroke. When any pneumatic actuator is sequenced with another device, pilot positioners shall be installed to allow for proper sequencing.
 - .3 Control Dampers: Shall be opposed blade for modulating control of airflow. Parallel blade dampers shall be installed for two position applications.
 - .4 Control Valves: Shall be sized for proper flow control with equal percentage valve plugs. The maximum pressure drop for water applications shall be 5 PSI. The maximum pressure drop for steam applications shall be 7 PSI.
 - .5 Electronic Signal Isolation Transducers: Whenever an analog output signal from the Building Management System is to be connected to an external control system as an input (such as a chiller control panel), or is to receive as an input a signal from a remote system, provide a signal isolation transducer. Signal isolation transducer shall provide ground plane isolation between systems. Signals shall provide optical isolation between systems

3.3 Commissioning

- .1 Fully commission all aspects of the Building Management System work.
- .2 Acceptance Check Sheet
 - .1 Prepare a check sheet that includes all points for all functions of the BMS as indicated on the point list included in this specification.
 - .2 Submit the check sheet to the Contract Administrator for approval
 - .3 The Contract Administrator will use the check sheet as the basis for acceptance with the Controls Contractor.
- .3 Promptly rectify all listed deficiencies and submit to the Contract Administrator that this has been done.

HANGERS AND SUPPORTS FOR ELECTRICAL SYSTEMS

1. GENERAL

1.1 Section Includes

.1 Materials and installation for hangers and supports.

2. PRODUCTS

2.1 Support Channels

.1 U shape, size 41 x 41 mm, 2.5 mm thick, surface mounted.

3. EXECUTION

3.1 Installation

- .1 Secure equipment to solid masonry, tile and plaster surfaces with adjustable anchors bolts.
- .2 Secure equipment to poured concrete with expandable inserts.
- .3 Secure equipment to hollow masonry walls or suspended ceilings with toggle bolts.
- .4 Secure surface mounted equipment with twist clip fasteners to inverted T bar ceilings. Ensure that T bars are adequately supported to carry weight of equipment specified before installation.
- .5 Support equipment, conduit or cables using clips, spring loaded nuts, spring loaded bolts, cable clamps designed as accessories to basic channel members.
- .6 Fasten exposed conduit or cables to building construction or support system using straps.
 - .1 One-hole malleable iron or aluminum straps to secure surface conduits and cables 50 mm and smaller.
 - .2 Two-hole steel or aluminum straps for conduits and cables larger than 50 mm.
 - .3 Beam clamps to secure conduit to exposed steel work.
- .7 Suspended support systems.
 - .1 Support individual cable or conduit runs with 6 mm dia threaded rods and spring clips.
 - .2 Support 2 or more cables or conduits on channels supported by 6 mm dia threaded rod hangers where direct fastening to building construction is impractical.
- .8 For surface mounting of two or more conduits use channels at 1.5 m on centre spacing.
- .9 Provide metal brackets, frames, hangers, clamps and related types of support structures where indicated or as required to support conduit and cable runs.

- .10 Ensure adequate support for raceways and cables dropped vertically to equipment where there is no wall support.
- .11 Do not use wire lashing or perforated strap to support or secure raceways or cables.
- .12 Do not use supports or equipment installed for other trades for conduit or cable support except with permission of other trade and approval of Contract Administrator.
- .13 Install fastenings and supports as required for each type of equipment cables and conduits, and in accordance with manufacturer's installation recommendations.

JUNCTION AND PULL BOXES

1. GENERAL

1.1 REFERENCES

- .1 Canadian Standards Association (CSA International)
 - .1 CSA C22.1, Canadian Electrical Code.

1.2 SUBMITTALS

- .1 Provide submittals in accordance with Section 01 33 00 Submittal Procedures.
- .2 Product Data:
 - .1 Provide manufacturer's printed product literature, specifications and datasheet and include product characteristics, performance criteria, physical size, finish and limitations.
- .3 Provide shop drawings: in accordance with Section 01 33 00 Submittal Procedures.
 - .1 Provide drawings stamped and signed by professional engineer registered or licensed in Province of Manitoba, Canada.

2. PRODUCTS

2.1 JUNCTION AND PULL BOXES

- .1 Construction:welded steel enclosure.
- .2 Covers Flush Mounted: 25 mm minimum extension all around.
- .3 Covers Surface Mounted: screw-on turned edge-covers.

3. EXECUTION

3.1 JUNCTION AND PULL BOXES

- .1 Install junction and pull boxes in inconspicuous but accessible locations.
- .2 Only main junction and pull boxes are indicated. Install additional pull boxes as required by CSA C22.1.

3.2 IDENTIFICATION

- .1 Equipment Identification: to Section 26 05 00 Common Work Results for Electrical.
- .2 Identification Labels: size 2 indicating system name, voltage and phase or as indicated.

1. GENERAL

1.1 References

- .1 Canadian Standards Association (CSA International)
 - .1 CAN/CSA C22.2 No. 18.1, Metallic Outlet Boxes.
 - .2 CSA C22.2 No.18.2, Nonmetallic Outlet Boxes
 - .3 CSA C22.2 No. 45.1, Electrical Rigid Metal Conduit Steel.
 - .4 CSA C22.2 No. 56, Flexible Metal Conduit and Liquid-Tight Flexible Metal Conduit.
 - .5 CSA C22.2 No. 83, Electrical Metallic Tubing.
 - .6 CSA C22.2 No. 211.2, Rigid PVC (Unplasticized) Conduit.
 - .7 CSA C22.2 No. 227.3, Nonmetallic Mechanical Protection Tubing (NMPT).

1.2 Submittals

- .1 Provide submittals in accordance with Section 01 33 00 Submittal Procedures.
- .2 Product data: submit manufacturer's printed product literature, specifications and datasheets.
 - .1 Submit cable manufacturing data.
- .3 Quality assurance submittals:
 - .1 Test reports: submit certified test reports.
 - .2 Certificates: submit certificates signed by manufacturer certifying that materials comply with specified performance characteristics and physical properties.
 - .3 Instructions: submit manufacturer's installation instructions.

2. PRODUCTS

2.1 Cables and Reels

- .1 Provide cables on reels or coils.
 - .1 Mark or tag each cable and outside of each reel or coil, to indicate cable length, voltage rating, conductor size, and manufacturer's lot number and reel number.
- .2 Each coil or reel of cable to contain only one continuous cable without splices.
- .3 Identify cables for exclusively dc applications.

2.2 Conduits

- .1 Rigid metal conduit: to CSA C22.2 No. 45, hot dipped galvanized steel threaded.
- .2 Epoxy coated conduit: to CSA C22.2 No. 45, with zinc coating and corrosion resistant epoxy finish inside and outside.
- .3 Electrical metallic tubing (EMT): to CSA C22.2 No. 83, with couplings.
- .4 Rigid pvc conduit: to CSA C22.2 No. 211.2.
- .5 Flexible metal conduit: to CSA C22.2 No. 56, liquid-tight flexible metal.
- .6 Flexible pvc conduit: to CSA-C22.2 No. 227.3.

2.3 Conduit Fastenings

- .1 One hole malleable iron straps to secure surface conduits 50 mm and smaller.
 - .1 Two hole steel straps for conduits larger than 50 mm.
- .2 Beam clamps to secure conduits to exposed steel work.
- .3 Channel type supports for two or more conduits at 1.5 m on centre.
- .4 Threaded rods, 6 mm diameter, to support suspended channels.

2.4 Conduit Fittings

.1 Fittings: manufactured for use with conduit specified. Coating: same as conduit.

2.5 Fish Cord

.1 Polypropylene.

3. EXECUTION

3.1 Manufacturer's Instructions

.1 Compliance: comply with Manufacturer's written recommendations or specifications, including product technical bulletins, handling, storage and installation instructions, and datasheets.

3.2 Installation

- .1 Install conduits to conserve headroom in exposed locations and cause minimum interference in spaces through which they pass.
- .2 Conceal conduits except in mechanical and electrical service rooms.
- .3 Use rigid hot dipped galvanized steel threaded conduit except where specified otherwise.

- Use electrical metallic tubing (EMT) except in cast concrete. .4
- .5 Use flexible metal conduit for connection to motors in dry areas, connection to recessed incandescent fixtures without prewired outlet box, connection to surface or recessed fluorescent fixtures.
- Use liquid tight flexible metal conduit for connection to motors or vibrating equipment in .6 damp, wet or corrosive locations.
- Use explosion proof flexible connection for connection to explosion proof motors. .7
- .8 Minimum conduit size for lighting and power circuits: 19 mm.
- Bend conduit cold: .9
 - .1 Replace conduit if kinked or flattened more than 1/10th of its original diameter.
- .10 Mechanically bend steel conduit over 19 mm diameter.
- .11 Field threads on rigid conduit must be of sufficient length to draw conduits up tight.
- .12 Install fish cord in empty conduits.
- .13 Run 2- 25 mm spare conduits up to ceiling space and 2- 25 mm spare conduits down to ceiling space from each panel.
 - .1 Terminate these conduits in 152 x 152 x 102 mm junction boxes in ceiling space or in case of an exposed concrete slab, terminate each conduit in surface type box.
- .14 Remove and replace blocked conduit sections.
 - .1 Do not use liquids to clean out conduits.
- .15 Dry conduits out before installing wire.

3.3 **Surface Conduits**

- Surface conduits in service spaces only (new and existing areas). .1
- .2 Run parallel or perpendicular to building lines.
- Locate conduits behind infrared or gas fired heaters with 1.5 m clearance. .3
- Run conduits in flanged portion of structural steel. .4
- Group conduits wherever possible on suspended channels. .5
- Do not pass conduits through structural members except as indicated. .6
- Do not locate conduits less than 75 mm parallel to steam or hot water lines with minimum of .7 25 mm at crossovers.

3.4 Concealed Conduits

- .1 Run parallel or perpendicular to building lines.
- .2 Do not install horizontal runs in masonry walls.
- .3 Do not install conduits in terrazzo or concrete toppings.

3.5 Conduits In Cast-In-Place Concrete

- .1 Locate to suit reinforcing steel.
 - .1 Install in centre one third of slab.
- .2 Protect conduits from damage where they stub out of concrete.
- .3 Install sleeves where conduits pass through slab or wall.
- .4 Provide oversized sleeve for conduits passing through waterproof membrane, before membrane is installed.
 - .1 Use cold mastic between sleeve and conduit.
- .5 Conduits in slabs: minimum slab thickness 4 times conduit diameter.
- .6 Encase conduits completely in concrete with minimum 25 mm concrete cover.
- .7 Organize conduits in slab to minimize cross-overs.

3.6 Cleaning

.1 On completion and verification of performance of installation, remove surplus materials, excess materials, rubbish, tools and equipment.

1. GENERAL

1.1 Submittals

- .1 Provide submittals in accordance with Section 01 33 00 Submittal Procedures.
- .2 Submit product data sheets for sills, busbars and compartments. Include product characteristics, physical size and finish.
- .3 Manufacturer's Instructions: provide to indicate special handling criteria, installation sequence and cleaning procedures
- .4 Submit WHMIS MSDS Material Safety Data Sheets in accordance with Section 01 33 00 Submittal Procedures.
- .5 Submit Shop Drawings and indicate:
 - .1 Outline dimensions.
 - .2 Configuration of identified compartments.
 - .3 Floor anchoring method and dimensioned foundation template.
 - .4 Cable entry and exit locations.
 - .5 Dimensioned position and size of busbars and details of provision for future extension.
 - .6 Schematic and wiring diagrams.
 - .7 Include data for each type and style of starter.

2. PRODUCTS

2.1 Supply Characteristics

.1 208 V, 60Hz, wye connected, 3 phase, 4 wire, grounded.

2.2 General Description

- .1 Compartmentalized vertical sections with common power busbars.
- .2 Floor mounting, free standing, enclosed dead front.
- .3 Indoor NEMA 1 gasketted enclosure, front mounting.

2.3 Vertical Section Construction

.1 Independent vertical sections fabricated from rolled flat steel sheets bolted together to form rigid, completely enclosed assembly.

- .2 Each vertical section divided into compartment units, minimum 305 mm high, as indicated.
- .3 Each unit to have complete top and bottom steel plate for isolation between units.
- .4 Horizontal wireways, equipped with cable supports, across top and bottom, extending full width of motor control centre, isolated from busbars by steel barriers.
- .5 Vertical wireways complete with doors for load and control conductors extending full height of vertical sections, and equipped with cable tie supports. Installation wiring to units accessible with doors open and units in place.
- .6 Openings, with removable cover plates, in side of vertical sections for horizontal wiring between sections.
- .7 Incoming cables to enter at top as indicated.
- .8 Provision for outgoing cables to exit via top or bottom with terminals.
- .9 Removable lifting means.
- .10 Provision for future extension of both ends of motor control centre including busbars without need for further drilling, cutting or preparation in field.
- .11 Divide assembly for shipment to site, complete with hardware and instructions for re-assembly.

2.4 Sills

.1 Continuous 38 mm channel iron floor sills for mounting bases with 19 mm diameter holes for bolts.

2.5 Busbars

- .1 Main horizontal and branch vertical, three phase and neutral high conductivity copper busbars in separate compartment self-cooled, extending entire width and height of motor control centre, supported on insulators and rated:
 - .1 Branch vertical busbars: 300 A as indicated.
- .2 Branch vertical busbars for distribution of power to units in vertical sections.
- .3 No other cables, wires, equipment in main and branch busbar compartments.
- .4 Brace buswork to withstand effects of short-circuit current of 42 kA rms symmetrical.
- .5 Bus supports: with high dielectric strength, low moisture absorption, high impact material and long creepage surface designed to discourage collection of dust.

2.6 Ground Bus

.1 Copper ground bus extending entire width of motor control centre.

.2 Vertical ground bus strap, full height of section, tied to horizontal ground bus, engaged by plug-in unit ground stab.

2.7 Motor Starters and Devices

.1 Section 26 29 10 – Motor Starters to 600 V.

2.8 Starter Unit Compartments

- .1 Units EEMAC size 5 and smaller, circuit breaker units 225 A and smaller, plug-in type with self-disconnect. Guide rail supports for units to ensure that stabs make positive contact with vertical bus. Provision for units to be installed or removed, off load, while buses energized.
- .2 Unit mounting:
 - .1 Engaged position unit stabbed into vertical bus.
 - .2 Withdrawn position unit isolated from vertical bus but supported by structure. Terminal block accessible for electrical testing of starter.
 - .3 Provision for positive latching in either engaged or withdrawn position and padlocking in withdrawn position.
 - .4 Stab-on connectors free floating tin plated clips, self-aligning, backed up with steel springs.
- .3 External operating handle of circuit switch interlocked with door to prevent door opening with switch in "on" position. Provision for 3 padlocks to lock operating handle in "off" position and lock door closed.
- .4 Hinge unit doors on same side.
- .5 Overload relays manually reset from front with door closed.
- .6 Pushbuttons and selector switches mounted on door front.
- .7 Devices and components by one manufacturer to facilitate maintenance.
- .8 Pull-apart terminal blocks for power and control to allow removal of starter units without removal of field wiring.

2.9 Wiring Identification

.1 Provide wiring identification in accordance with Section 26 05 00 - Common Work Results for Electrical.

2.10 Equipment Identification

- .1 Provide equipment identification in accordance with Section 26 05 00 Common Work Results for Electrical.
 - .1 Motor control centre main nameplate: size No. 7, engraved MCC-B, 208 V, 3 PH, 4 W.

.2 Individual compartment nameplates: size No. 8, engraved as indicated.

2.11 Finishes

- .1 Apply finishes in accordance with Section 26 05 00 Common Work Results for Electrical.
- .2 Paint motor control centre exterior light gray and interiors white.

2.12 Source Quality Control

- .1 Provide manufacturer's type test certificates including short circuit fault damage certification up to short circuit values specified under bus bracing.
- .2 Contract Administrator to witness standard factory testing of complete motor control centre including operation of switches, circuit breakers, starters and controls.

2.13 Approved Manufacturer

.1 MCC shall be as manufactured by Square D, Cutler-Hammer or Siemens.

3. EXECUTION

3.1 Installation

- .1 Set and secure motor control centre in place on channel bases, rigid, plumb and square to building floor and wall.
- .2 Make field power and control connections as indicated.
- .3 Ensure correct overload heater elements are installed.

3.2 Field Quality Control

- .1 Perform tests in accordance with Section 26 05 00 Common Work Results for Electrical.
- .2 Ensure moving and working parts are lubricated where required.
- .3 Operate starters to prove satisfactory performance of motor control centre during 8 hour period.

WIRING DEVICES

1. GENERAL

1.1 Section Includes

.1 Switches, receptacles, wiring devices, cover plates and their installation.

1.2 Related Sections

- .1 Section 01 33 00 Submittal Procedures.
- .2 Section 26 05 00 Common Work Results Electrical.

1.3 References

- .1 Canadian Standards Association (CSA International)
 - .1 CSA-C22.2 No.42, General Use Receptacles, Attachment Plugs and Similar Wiring Devices.
 - .2 CSA-C22.2 No.42.1, Cover Plates for Flush-Mounted Wiring Devices
 - .3 CSA-C22.2 No.55, Special Use Switches.
 - .4 CSA-C22.2 No.111, General-Use Snap Switches.

1.4 Shop Drawings and Product Data

.1 Submit Shop Drawings and product data in accordance with Section 01 33 00 - Submittal Procedures.

2. PRODUCTS

2.1 Switches

- .1 15 A, 120 V, single pole switches 120 V lighting source.
- .2 Manually-operated general purpose ac switches with following features:
 - .1 Terminal holes approved for No. 10 AWG wire.
 - .2 Silver alloy contacts.
 - .3 Nylon molding for parts subject to carbon tracking.
 - .4 Suitable for back and side wiring.
 - .5 Ivory toggle.
- .3 Toggle operated, fully rated for tungsten filament and fluorescent lamps, and up to 80% of rated capacity of motor loads.

Section 26 27 26

Page 2 of 4

January 2009

- .5 Acceptable manufacturers:
 - .1 WattStopper
 - .2 Leviton
 - .3 Pass & Seymour
 - .4 Hubble
- .6 Standard of acceptance: Pass & Seymour 2601 347-I and 2601-I.

2.2 Occupancy Sensor

- .1 15 A, 120 V, single pole switches 120 V lighting source.
- .2 Automatically and Manually-operated general purpose ac switches with following features:

WIRING DEVICES

- .1 Terminal holes approved for No. 10 AWG wire.
- .2 Silver alloy contacts.
- .3 Nylon molding for parts subject to carbon tracking.
- .4 Suitable for back and side wiring.
- .3 Fully rated for tungsten filament and fluorescent lamps, and up to 80% of rated capacity of motor loads.
- .4 Switches of one manufacturer throughout project.
- .5 Acceptable manufacturers:
 - .1 WattStopper
 - .2 Leviton
 - .3 Pass & Seymour
 - .4 Hubble
- .6 Standard of acceptance: WattStopper UW-100.

2.3 Receptacles

- .1 Duplex receptacles, CSA type 5-15 R, 125 V, 15 A, U ground, to: CSA-C22.2 No.42 with following features:
 - .1 Ivory nylon moulded housing.

- .2 Suitable for No. 10 AWG for back and side wiring.
- .3 Break-off links for use as split receptacles.
- .4 Eight back wired entrances, four side wiring screws.
- .5 Triple wipe contacts and rivetted grounding contacts.
- .6 Standard of acceptance: Pass & Seymour 885I Series.
- .2 Single receptacles CSA type 5-15 R, 125 V, 15 A, U ground with following features:
 - .1 Ivory urea moulded housing.
 - .2 Suitable for No. 10 AWG for back and side wiring.
 - .3 Four back wired entrances, 2 side wiring screws.
- .3 Other receptacles with ampacity and voltage as indicated.
- .4 Receptacles of one manufacturer throughout project.
- .5 Mount weatherproof receptacles horizontal.

2.4 Manual Motor Disconnects

- .1 Double pole, 120 V, 30 A rated starting switch.
- .2 Standard of acceptance: Pass & Seymour PS30AC2-HP.

2.5 Cover Plates

- .1 Cover plates for wiring devices to: CSA-C22.2 No.42.1.
- .2 Cover plates from one manufacturer throughout project.
- .3 Sheet steel utility box cover for wiring devices installed in surface-mounted utility boxes.
- .4 Sheet steel cover plates, for wiring devices mounted in flush-mounted outlet box.

3. EXECUTION

3.1 Installation

- .1 Switches:
 - .1 Install single throw switches with handle in "UP" position when switch closed.
 - .2 Install switches in gang type outlet box when more than one switch is required in one location.

WIRING DEVICES

- .3 Mount toggle switches at height in accordance with Section 26 05 00 Common Work Results Electrical or as indicated.
- .2 Receptacles:
 - .1 Install receptacles in gang type outlet box when more than one receptacle is required in one location.
 - .2 Mount receptacles at height in accordance with Section 26 05 00 Common Work Results Electrical or as indicated.
 - .3 Where split receptacle has one portion switched, mount vertically and switch upper portion.
- .3 Cover plates:
 - .1 Install suitable common cover plates where wiring devices are grouped.
 - .2 Do not use cover plates meant for flush outlet boxes on surface-mounted boxes.

1. GENERAL

1.1 Section Includes

.1 Materials for moulded-case circuit breakers, circuit breakers.

1.2 Related Sections

.1 Section 01 33 00 - Submittal Procedures.

1.3 References

- .1 Canadian Standards Association (CSA International).
 - .1 CSA-C22.2 No. 5, Moulded-Case Circuit Breakers, Molded-Case Switches and Circuit-Breaker Enclosures.

1.4 Submittals

.1 Submit product data in accordance with Section 01 33 00 - Submittal Procedures.

2. PRODUCTS

2.1 Breakers General

- .1 Moulded-case circuit breakers: to CSA C22.2 No. 5
- .2 Bolt-on moulded case circuit breaker: quick- make, quick-break type, for manual and automatic operation with temperature compensation for 40°C ambient.
- .3 Common-trip breakers: with single handle for multi-pole applications.
- .4 Magnetic instantaneous trip elements in circuit breakers to operate only when value of current reaches setting.
 - .1 Trip settings on breakers with adjustable trips to range from 3 to 10 times current rating.
- .5 Circuit breakers to have minimum 42 kA symmetrical rms interrupting capacity rating.

2.2 Thermal Magnetic Breakers

.1 Moulded case circuit breaker to operate automatically by means of thermal and magnetic tripping devices to provide inverse time current tripping and instantaneous tripping for short circuit protection.

2.3 Magnetic Breakers

.1 Moulded case circuit breaker to operate automatically by means of magnetic tripping devices to provide instantaneous tripping for short circuit protection.

3. EXECUTION

3.1 Installation

.1 Install circuit breakers as indicated.

3.2 Manufacturers

.1 Acceptable manufacturer: Square D, Cutler Hammer, Siemens.

1. GENERAL

1.1 Section Includes

.1 Materials and installation for load break switches and enclosures.

1.2 Related Sections

- .1 Section 01 33 00 Submittal Procedures.
- .2 Section 26 05 00 Common Work Results Electrical.

1.3 References

- .1 Canadian Standards Association (CSA International)
 - .1 CAN/CSA-C22.2 No. 4, Enclosed and Dead-Front Switches.
 - .2 CAN/CSA-C22.2 No. 31, Switchgear Assemblies.
- .2 Underwriters' Laboratories (UL)
 - .1 UL 977, Safety Fused Power-Circuit Devices.

1.4 Product Data

.1 Submit product data in accordance with Section 01 33 00 - Submittal Procedures.

1.5 Extra Materials

.1 1 set of arc suppressing contacts for each size of switch supplied.

2. PRODUCTS

2.1 Switches

- .1 Load Break Switches: to CAN/CSA-C22.2 No. 4, CAN/CSA-C22.2 No. 31, UL 977.
- .2 Switches of continuous ampere rating as indicated, load-break bolted contact type.
- .3 Interrupting rating of 6 times continuous current on contacts on manual operation, 12 times on motorized operation. Interrupting capacity to withstand and close onto circuits having available fault currents of 10 kA rms symmetrical, with HRC-L fuses.
- .4 Switch blades and terminals silver plated copper with drilled holes and surface ground to ensure high quality surface contact.
- .5 Replaceable arc suppressing contacts of silver tungsten construction with first-in, last-out operation.

LOAD BREAK SWITCHES

- .6 Positive switching action of operating mechanism independent of speed at which handle is operated.
- .7 Quick make, quick break, stored energy operating mechanism for manual closing operation.
- .8 Operating handle mechanically interlocked with fuse access door with provision for quadruple padlocking in open position.
- .9 Operating mechanism arranged to prevent "teasing" operation of contacts.
- .10 Switches front accessible for quick and easy installation or removal.
- .11 Auxiliary isolated contacts normally open with interrupting contact rating of 10 A at 120 V.

2.2 Enclosure

- .1 Enclosure designed to withstand mechanical stresses associated with available fault current of 10 kA rms symmetrical.
- .2 CSA Enclosure NEMA 4X for exterior mount and NEMA 1 or 12 for interior mounting, wall mounting.
- .3 Enclosure access door with shatterproof wire re-inforced glass inspection window for viewing switch operating mechanism and terminations.
- .4 Finish exterior in accordance with Section 26 05 00 Common Work Results Electrical.

3. EXECUTION

3.1 Installation

.1 Install equipment in accordance with Manufacturer's instructions.

3.2 Field Quality Control

- .1 Perform tests in accordance with Section 26 05 00 Common Work Results Electrical.
- .2 Operate switch on line under normal load conditions 1 times in presence of Contract Administrator and prove out operating functions.
1. GENERAL

1.1 Section Includes

.1 Materials and installation for non-fused load break disconnect switches.

1.2 Related Sections

- .1 Section 01 33 00 Submittal Procedures.
- .2 Section 26 05 00 Common Work Results for Electrical.

1.3 References

- .1 Canadian Standards Association (CSA International).
 - .1 CSA C22.2 No.4, Enclosed and Dead-Front Switches.
 - .2 CSA C22.2 No.39, Fuseholder Assemblies Industrial Products.

1.4 Submittals

.1 Submit product data in accordance with Section 01 33 00 - Submittal Procedures.

2. PRODUCTS

2.1 Disconnect Switches

- .1 Non-fusible, horsepower rated disconnect switch in CSA Enclosure 1, 4X as shown, size as indicated.
- .2 Provision for padlocking in "off" switch position by three locks.
- .3 Mechanically interlocked door to prevent opening when handle in ON position.
- .4 Quick-make, quick-break action.
- .5 ON-OFF switch position indication on switch enclosure cover.
- .6 Solid neutral block as required.
- .7 Acceptable Manufacturer: Square D.

2.2 Boiler Disconnect Switches

.1 Cast box with cast switch fitting.

2.3 Equipment Identification

- .1 Provide equipment identification in accordance with Section 26 05 00 Common Work Results for Electrical.
- .2 Indicate name of load controlled on size 4 nameplate.

3. EXECUTION

3.1 Installation

.1 Install disconnect switches complete with fuses if applicable.

1. GENERAL

1.1 Section Includes

.1 Materials and installation for industrial control devices including pushbutton stations, control and relay panels.

1.2 Related Sections

- .1 Section 01 33 00 Submittal Procedures.
- .2 Section 26 05 00 Common Work Results Electrical.

1.3 References

- .1 Canadian Standards Association (CSA International)
 - .1 CSA C22.2 No.14, Industrial Control Equipment.
- .2 National Electrical Manufacturers Association (NEMA)
 - .1 NEMA ICS 1, Industrial Control and Systems: General Requirements.

1.4 Shop Drawings

- .1 Submit Shop Drawings in accordance with Section 01 33 00 Submittal Procedures.
- .2 Include schematic, wiring, interconnection diagrams.

1.5 Quality Assurance

.1 Submit to Contract Administrator one copy of test results.

2. PRODUCTS

2.1 Ac Control Relays

- .1 Control Relays: to CSA C22.2 No.14 and NEMA ICS 1.
- .2 Sealed contact type: electrically held with 4. Coil rating: 120 V. Contact rating: 120 V, 10A.

2.2 Operator Control Stations

.1 Enclosure: NEMA Type 12, flush mounting:

2.3 Pushbuttons

.1 Illuminated and Oil tight. Operator flush type as indicated. Rated at 10 A, AC, labels as indicated. Stop pushbuttons coloured red, provision for padlocking in depressed position labelled "Stop".

CONTROL DEVICES

2.4 Selector Switches

.1 Maintained 3 position labelled "H-O-A" as indicated oil tight, operators standard, contact arrangement as indicated, rated 120 V, 10 A, AC.

2.5 Control and Relay Panels

.1 CSA Type 1 sheet steel enclosure with hinged padlockable access door, accommodating relays timers, labels, as indicated, factory installed and wired to identified terminals.

2.6 Control Circuit Transformers

- .1 Single phase, dry type.
- .2 Primary: 208 V, 60 Hz AC.
- .3 Secondary: 120 V, AC.
- .4 Rating: 150 VA or as required.
- .5 Secondary fuse: as required.
- .6 Close voltage regulation as required by magnet coils and solenoid valves.

3. EXECUTION

3.1 Installation

.1 Install pushbutton stations, control and relay panels, control devices and interconnect.

3.2 Field Quality Control

- .1 Perform tests in accordance with Section 26 05 00 Common Work Results Electrical.
- .2 Depending upon magnitude and complexity, divide control system into convenient sections, energize one section at time and check out operation of section.
- .3 Upon completion of sectional test, undertake group testing.
- .4 Check out complete system for operational sequencing.

MOTOR STARTERS TO 600 V

1. GENERAL

1.1 Related Sections

.1 Section 26 05 00 - Common Work Results for Electrical.

1.2 References

- .1 International Electrotechnical Commission (IEC)/Dansk Standard (DS)
 - .1 DS DS/EN 60947-4-1, Part 4: Contactors and motor-starters.

1.3 Shop Drawings and Product Data

- .1 Submit Shop Drawings in accordance with Section 01 33 00 Submittal Procedures.
- .2 Indicate:
 - .1 Mounting method and dimensions.
 - .2 Starter size and type.
 - .3 Layout of identified internal and front panel components.
 - .4 Enclosure types.
 - .5 Wiring diagram for each type of starter.
 - .6 Interconnection diagrams.

1.4 Closeout Submittals

.1 Include operation and maintenance data for each type and style of starter.

1.5 Extra Materials

- .1 Provide listed spare parts for each different size and type of starter:
 - .1 4 contacts, stationary.
 - .2 4 contacts, movable.
 - .3 2 contacts, auxiliary.
 - .4 2 control transformers.
 - .5 2 operating coil.
 - .6 10% indicating lamp bulbs used.
 - .7 1 HOA kit.

MOTOR STARTERS TO 600 V

1.6 Waste Management and Disposal

- .1 Place materials defined as hazardous or toxic waste in designated containers.
- .2 Ensure emptied containers are sealed and stored safely for disposal away from children.

2. PRODUCTS

2.1 Materials

- .1 Starters: to IEC/DS DS/EN 60947-4-1.
- .2 Starters: EEMAC E14-2.

2.2 Manual Motor Starters

- .1 Single and Three phase manual motor starters of size, type, rating, and enclosure type as indicated, with components as follows:
 - .1 Switching mechanism, quick make and break.
 - .2 Overload heaters, manual reset, trip indicating handle.
- .2 Accessories:
 - .1 Toggle switch: labelled as indicated.
 - .2 Indicating light: type and colour as indicated.
 - .3 Locking tab to permit padlocking in "OFF" position.
 - .4 Flush mounted type in public areas or as indicated.

2.3 Full Voltage Magnetic Starters

- .1 Combination magnetic starters of size, type, rating and enclosure type as indicated with components as follows:
 - .1 Contactor solenoid operated, rapid action type.
 - .2 Motor overload protective device in each phase, manually reset from outside enclosure.
 - .3 Wiring and schematic diagram inside starter enclosure in visible location.
 - .4 Identify each wire and terminal for external connections, within starter, with permanent number marking identical to drawing.
- .2 Combination type starters to include circuit breaker with operating lever on outside of enclosure to control circuit breaker, and provision for:
 - .1 Locking in "OFF" position with up to 3 padlocks.

- .2 Independent locking of enclosure door.
- .3 Provision for preventing switching to "ON" position while enclosure door open.
- .3 Accessories:
 - .1 Selector switches: standard labelled as indicated.
 - .2 Indicating lights: standard type and color as indicated.
 - .3 1-N/O and 1-N/C spare auxiliary contacts unless otherwise indicated.

2.4 Control Transformer

- .1 Single phase, dry type, control transformer with primary voltage as indicated and 120 V secondary, complete with secondary fuse, installed in with starter as indicated.
- .2 Size control transformer for control circuit load plus 20% spare capacity.

2.5 Finishes

.1 Apply finishes to enclosure in accordance with Section 26 05 00 - Common Work Results for Electrical.

2.6 Equipment Identification

- .1 Provide equipment identification in accordance with Section 26 05 00 Common Work Results for Electrical.
- .2 Manual starter designation label, white plate, black letters, size 1, engraved as indicated.
- .3 Magnetic starter designation label, white plate, black letters, size 4 as indicated on drawing. Engraved as indicated.

3. EXECUTION

3.1 Installation

- .1 Install starters, connect power and control as indicated.
- .2 Ensure correct fuses and overload devices elements installed.

3.2 Field Quality Control

- .1 Perform tests in accordance with Section 26 05 00 Common Work Results for Electrical and Manufacturer's instructions.
- .2 Operate switches, contactors to verify correct functioning.
- .3 Perform starting and stopping sequences of contactors and relays.

MOTOR STARTERS TO 600 V

- .4 Check that sequence controls, interlocking with other separate related starters, equipment, control devices, operate as indicated.
- .5 Ensure motor rotation corresponds with the direction required by the driven equipment.

LIGHTING

1. GENERAL

1.1 References

- .1 ANSI/NEMA
 - .1 ANSI/NEMA C82.1, Lamp Ballasts Line Frequency Flourescent Lamp Ballast.
 - .2 ANSI/NEMA C82.4, Ballasts for High-Intensity-Discharge and Low-Pressure Sodium Lamps.

.2 ANSI/IEEE

- .1 ANSI/IEEE C62.41, Recommended Practice on Surge Voltages in Low-Voltage AC Power Circuits.
- .3 ASTM
 - .1 ASTM F1137, Specification for Phosphate/Oil and Phosphate/Organic Corrosion Protective Coatings for Fasteners.
- .4 FCC
 - .1 FCC 47 CFR EM and RF Interference Suppression.

1.2 Related Sections

.1 Section 01 33 00 - Submittal Procedures.

1.3 Shop Drawings and Product Data

- .1 Submit Shop Drawings in accordance with Section 01 33 00 Submittal Procedures.
- .2 Submit complete photometric data for luminaires where specified, for review by Contract Administrator.

2. PRODUCTS

2.1 Ballasts

.1 Fluorescent ballast as indicated: CBM and CSA certified, energy efficient type.

3. EXECUTION

3.1 Installation

.1 Locate and install luminaires as indicated.

3.2 Wiring

- .1 Connect luminaires to lighting circuits:
 - .1 Directly for luminaire.
 - .2 Through rigid conduit for luminaire designs.

3.3 Luminaire Alignment

- .1 Align luminaires mounted in continuous rows to form straight uninterrupted line.
- .2 Align luminaires mounted individually parallel or perpendicular to building grid lines.

1. GENERAL

1.1 Section Includes

.1 Materials and installation for emergency lighting systems.

1.2 Related Sections

- .1 Section 01 33 00 Submittal Procedures.
- .2 Section 26 05 21 Wire and Cables (0-1000 V).
- .3 Section 26 05 34 Conduits, Conduit Fastenings and Conduit Fittings.

1.3 References

- .1 Canadian Standards Association (CSA International)
 - .1 CSA C22.2 No.141, Unit Equipment for Emergency Lighting.

1.4 Submittals

- .1 Submit product data in accordance with Section 01 33 00 Submittal Procedures.
- .2 Data to indicate system components, mounting method, source of power and special attachments.

2. PRODUCTS

2.1 Equipment

- .1 Emergency lighting equipment: to CSA C22.2 No.141.
- .2 Supply voltage: 120 VAC.
- .3 Operating time: 30 minutes min.
- .4 Battery: sealed, maintenance free.
- .5 Cabinet: suitable for direct or shelf mounting to wall and c/w knockouts for conduit. Removable or hinged front panel for easy access to batteries.

3. EXECUTION

3.1 Installation

- .1 Install unit equipment and remote mounted fixtures.
- .2 Direct heads.

.3 Connect exit lights to unit equipment.

EXIT LIGHTS

1. GENERAL

1.1 References

- .1 Canadian Standards Association (CSA International)
 - .1 CSA C22.2 No.141, Unit Equipment for Emergency Lighting.
 - .2 CSA C860, Performance of Internally-Lighted Exit Signs.
- .2 National Fire Protection Association (NFPA)
 - .1 NFPA 101, Life Safety Code.

1.2 Submittals

- .1 Provide submittals in accordance with Section 01 33 00 Submittal Procedures.
- .2 Product Data:
 - .1 Submit manufacturer's printed product literature, specifications and datasheet and include product characteristics, performance criteria, physical size, finish and limitations.
- .3 Submit WHMIS MSDS Material Safety Data Sheets in accordance with Section.
- .4 Quality Assurance Submittals:
 - .1 Instructions: submit Manufacturer's installation instructions and special handling criteria, installation sequence, cleaning procedures.

2. PRODUCTS

2.1 Standard Units

- .1 Exit lights: to CSA C22.2 No.141 and CSA C860.
 - .1 As per luminaire schedule.
- .2 Housing: cold rolled steel minimum.
- .3 Face and back plates: die formed cold rolled steel.
- .4 Lamps: LED light.
- .5 Letters: Red reading EXIT.

EXIT LIGHTS

3. EXECUTION

3.1 Manufacturer's Instructions

.1 Compliance: comply with Manufacturer's written recommendations or specifications, including product technical bulletins, handling, storage and installation instructions, and datasheets.

3.2 Installation

- .1 Install exit lights to Manufacturer's recommendations, listing requirements, NFPA standard and local regulatory requirements.
- .2 Connect fixtures to exit light circuits.
- .3 Connect emergency lamp sockets to emergency circuits.
- .4 Ensure that exit light circuit breaker is locked in on position.

3.3 Cleaning

.1 On completion and verification of performance of installation, remove surplus materials, excess materials, rubbish, tools and equipment.