

## U/G SERVICE NOTES:

1. LOCATIONS OF UNDERGROUND STRUCTURES AS SHOWN ARE BASED ON THE BEST INFORMATION AVAILABLE BUT NO GUARANTEE IS GIVEN THAT ALL EXISTING ARE SHOWN OR THAT THE GIVEN LOCATIONS ARE EXACT. CONFIRMATION OF EXISTENCE AND EXACT LOCATION OF ALL SERVICES MUST BE OBTAINED FROM THE INDIVIDUAL UTILITIES BEFORE PROCEEDING WITH CONSTRUCTION. ANY ENCUMBRANCES SHALL BE REPORTED TO THE CONTRACT ADMINISTRATOR IMMEDIATELY.

2. DUCTS CONTAIN FIBRE OPTIC CABLES AND MUST BE EXCAVATED IN ACCORDANCE WITH UTILITY'S EXPRESS REQUIREMENTS. THE CONTRACTOR SHALL CONTACT THE UTILITY AT LEAST SEVEN DAYS PRIOR TO EXCAVATION.

3. THE LOCATION OF WATER SERVICE SHUT-OFF VALVES CAN VARY SIGNIFICANTLY. A MINIMUM OF 1.0 METER CLEARANCE FROM ALL SHUT-OFF VALVES IS REQUIRED.

4. A MINIMUM CLEARANCE OF 1.0 METER MUST BE PROVIDED BETWEEN THE UNDERSIDE OF ANY EXISTING WATERMAIN OR SEWERMAIN AND THE TOP OF PROPOSED WORKS.

5. A MINIMUM CLEARANCE OF 0.5 METER MUST BE PROVIDED BETWEEN THE UNDERSIDE OF THE PROPOSED WORKS AND THE TOP OF ANY EXISTING WATERMAIN OR SEWERMAIN.

6. A MINIMUM CLEARANCE OF 2.0 METERS MUST BE PROVIDED BETWEEN ANY EXISTING WATERMAIN OR SEWERMAIN PIPE AND THE PROPOSED WORKS.

7. CONTACT THE CUSTOMER TECHNICAL SERVICES BRANCH AT 986-3322 48 HOURS PRIOR TO CONSTRUCTION FOR CLEARANCE OF EXISTING WATER AND WASTEWATER UTILITIES. <u>LEGEND</u>

## ---- PROPERTY LINE LIMIT OF CONSTRUCTION —— — MTS ————— GAS ------ WATER MAIN WWS \_\_\_\_\_ STREET LIGHT PEDESTRIAN CROSSING SIGNAL ←• STREET SIGNS $\bigcirc$ MANHOLES CATCH BASINS -----FIRE HYDRANT CURB INLET VALVES Q Ø $\triangleright$ SURVEY BARS SIDEWALK PAVEMENT / PAVING STONE תתתתח **ROADWAY PAVEMENT / PAVING STONE** Addendum 1 June 15, 2010 Issued for Tender June 3, 2010 Released for Review March 10, 2010 No. Revision Date

THIS DRAWING MUST NOT BE SCALED.


THE GENERAL CONTRACTOR SHALL VERIFY ALL DIMENSIONS, DATUMS AND LEVELS PRIOR TO COMMENCEMENT OF WORK. ALL ERRORS AND OMISSIONS TO BE REPORTED IMMEDIATELY TO THE LANDSCAPE ARCHITECT. VARIATIONS & MODIFICATIONS TO WORK SHOWN ON THESE DRAWINGS SHALL NOT BE CARRIED OUT WITHOUT WRITTEN PERMISSION FROM THE LANDSCAPE ARCHITECT. THIS DRAWING IS THE EXCLUSIVE PROPERTY OF THE LANDSCAPE ARCHITECTS AND CAN BE REPRODUCED ONLY WITH THE PERMISSION OF THE LANDSCAPE ARCHITECTS, IN WHICH CASE THE REPRODUCTION MUST BEAR THEIR NAME AS LANDSCAPE ARCHITECTS.

## **EDMONTON STREET** WEST SIDEWALK **PORTAGE TO GRAHAM**

Streetscape Redevelopment Project Title

## **EXISTING CONDITIONS & DEMOLITION PLAN - SOUTH**

Drawing Title



Landscape Architecture • Planning 500-115 Bannatyne Avenue East, Telephone 204 • 944 • 9907 Winnipeg, Manitoba R3B 0R3 Facsimile 204 • 957 • 1467

Drawn	JH	GM Approved
Scale	1:100	JUNE 3, 2010
Job	09 048	Drawing L-1.1