Corporate Finance Department
Materials Management Division

BID OPPORTUNITY NO. 240-2010 ADDENDUM 3

RE-ROOFING OF THE WATER SERVICES GARAGE BUILDING AND THE FLOOD EQUIPMENT STORAGE BUILDING

ISSUED: March 30, 2010
BY: Doug Berg
TELEPHONE NO. (204) 986-4452

URGENT

PLEASE FORWARD THIS DOCUMENT TO WHOEVER IS IN POSSESSION OF THE BID OPPORTUNITY

THIS ADDENDUM SHALL BE INCORPORATED INTO THE BID OPPORTUNITY AND SHALL FORM A PART OF THE CONTRACT DOCUMENTS

Template Version: A20070419

Please note the following and attached changes, corrections, additions, deletions, information and/or instructions in connection with the Bid Opportunity, and be governed accordingly. Failure to acknowledge receipt of this Addendum in Paragraph 8 of Form A: Bid may render your Bid non-responsive.

Note: There was no Addendum No. 1. The first addendum was issued as No. 2 in error

PART A – BID SUBMISSION

Replace: BID OPPORTUNITY NO. 240-2010 Bid Submission with BID OPPORTUNITY NO. 240-2010 Addendum 3- Bid Submission. The following is a summary of changes incorporated in the replacement Bid Submission:

Form B(R1): Add Provisional Item No. 3: Asbestos Removal

Page numbering on some forms may be changed as a result.

PART E – SPECIFICATIONS

Revise: E2.1 to read: If hazardous materials, with the exception of Asbestos Containing Materials (ACM's), are encountered during the Work of the Contract, the Contractor shall stop all work and notify the Contract Administrator immediately. Removal of the hazardous materials shall be dealt with by the City and the Contractor shall await further instruction by the Contract Administrator

Add: E2.2 The Contractor shall be responsible for the removal and disposal of any ACM's directly impeding the work to complete the re-roofing at the buildings herein described in this specification.

Add: E2.2.1 Removal and handling of ACM's is to be performed by persons trained in the methods, procedures and practices for asbestos abatement.

Add: E2.2.2 Removal and disposal of any ACM's shall be in compliance with the latest Federal, Provincial and local requirements for such work.