A 120/208V, 225 A, 3PH, 4W 30 CCTS.

225A, 3P SH. TRIP

LOAD	DESCRIPTION			DESCRIPTION	LOAD
	OUTLET 8	1 15A	15A 2	OUTLET 12	
	OUTLET 9	3 15A	15A 4	OUTLET 13	
	OUTLET 10	5 15A	15A 6	OUTLET 14	
	OUTLET 11	7 15A	50A 8	PANEL B	
	PANEL C	9 50A	50A 10		
		11 50A	50A 12		
		13 50A	14	SPARE	
	SPARE	15	16	SPARE	
	SPARE	17	18	SPARE	
	SPARE	19	20	SPARE	
	SPARE	21	22	SPARE	
	SPARE	23	24	SPARE	
	SPARE	25	26	SPARE	
	SPARE	27	28	SPARE	
	SPARE	29	30	SPARE	

B 120/208V, 100 A, 3PH, 4W 30 CCTS.

100A, 3P SH. TRIP

LOAD	DESCRIPTION			DESCRIPTION	LOAD
	OUTLET 1	1 15A	15A 2	OUTLET 5	
	OUTLET 2	3 15A	15A 4	OUTLET 6	
	OUTLET 3	5 15A	15A 6	OUTLET 7	
	OUTLET 4	7 15A	8	SPARE	
	SPARE	9	10	SPARE	
	SPARE	11	12	SPARE	
	SPARE	13	14	SPARE	
	SPARE	15	16	SPARE	
	SPARE	17	18	SPARE	
	SPARE	19	20	SPARE	
	SPARE	21	22	SPARE	
	SPARE	23	24	SPARE	
	SPARE	25	26	SPARE	
	SPARE	27	28	SPARE	
	SPARE	29	30	SPARE	

C 120/208V, 100 A, 3PH, 4W 30 CCTS.

100A, 3P SH. TRIP

LOAD	DESCRIPTION			DESCRIPTION	LOAD
	OUTLET 15	1 15A	15A 2	OUTLET 18	
	OUTLET 16	3 15A	15A 4	OUTLET 19	
	OUTLET 17	5 15A	15A 6	OUTLET 20	
	SPARE	7	15A 8	OUTLET 21	
	SPARE	9	10	SPARE	
	SPARE	11	12	SPARE	
	SPARE	13	14	SPARE	
	SPARE	15	16	SPARE	
	SPARE	17	18	SPARE	
	SPARE	19	20	SPARE	
	SPARE	21	22	SPARE	
	SPARE	23	24	SPARE	
	SPARE	25	26	SPARE	
	SPARE	27	28	SPARE	
	SPARE	29	30	SPARE	

APEGM
Certificate of Authorization
Dillon Consulting Limited (MB)
No. 1789 Date: 04/23/10

LOCATION UNDERGROUND APPROVED STRUCTURES

SUPV. U/G STRUCTURES COMMITTEE DATE

NOTE:
LOCATION OF UNDERGROUND STRUCTURES AS SHOWN ARE BASED ON THE BEST INFORMATION AVAILABLE, BUT NO GUARANTEE IS GIVEN THAT ALL EXISTING UTILITIES ARE SHOWN OR THAT THE GIVEN LOCATIONS ARE EXACT. CONFIRMATION OF EXISTENCE AND EXACT LOCATION OF ALL SERVICES MUST BE OBTAINED FROM THE INDIVIDUAL UTILITIES BEFORE PROCEEDING WITH CONSTRUCTION.

B.M.
ELEV.

NO.	REVISIONS	DATE	BY
1	ADDENDUM #2	04/23/10	MCL

DESIGNED BY ML
DRAWN BY JV
CHECKED BY ORIGINAL SIGNED BY AA
APPROVED BY ORIGINAL SIGNED BY WCDD
HOR. SCALE
VERTICAL
DATE

DILLON CONSULTING

RELEASED FOR CONSTRUCTION
ORIGINAL SIGNED BY RANDY FINGAS
DATE 04/23/10

ENGINEER'S SEAL
PROVINCE OF MANITOBA
ORIGINAL STAMPED BY
W.C.D. DEGAGNE
04/23/10
REGISTERED PROFESSIONAL ENGINEER

CONSULTANT PROJECT NO.
088813

Winnipeg

THE CITY OF WINNIPEG
TRANSIT DEPARTMENT

SOUTHWEST RAPID TRANSIT CORRIDOR - STAGE 1
TRANSITWAY CONSTRUCTION, LANDSCAPING & ASSOCIATED WORKS

ELECTRICAL - VIA PARKING LOT PANEL SCHEDULES

CITY DRAWING NUMBER P-3317-76
SHEET 76 OF 84
CONSULTANT DRAWING NUMBER C6-C3055-T

G:\CAD\088813\Contract\Contract 6-Busway\Current\Electrical\VIA PARKING LOT\E4-PANEL SCHEDULES.dwg