



362-2010 ADDENDUM 3

Removal of Fuel Tanks and Associated Infrastructure at Two City of Winnipeg Fuel Sites (St. Anne's & Waverley)

ISSUED: May 28, 2010
BY: Ajaleigh Williams
TELEPHONE NO. (204) 986-7879

URGENT

PLEASE FORWARD THIS DOCUMENT TO WHOEVER IS IN POSSESSION OF THE BID OPPORTUNITY

THIS ADDENDUM SHALL BE INCORPORATED INTO THE BID OPPORTUNITY AND SHALL FORM A PART OF THE CONTRACT DOCUMENTS

Template Version: A20070419

Please note the following and attached changes, corrections, additions, deletions, information and/or instructions in connection with the Bid Opportunity, and be governed accordingly. Failure to acknowledge receipt of this Addendum in Paragraph 8 of Form A: Bid may render your Bid non-responsive.

PART A – BID SUBMISSION

Replace: 362-2010 Bid Submission with 362-2010 Addendum 3 - Bid Submission. The following is a summary of changes incorporated in the replacement Bid Submission:

Form B(R1): Added Items No. 1m to 1p inclusive and items No. 2m to 2p inclusive. Page numbering on some forms may be changed as a result.

PART D – SUPPLEMENTAL CONDITIONS

- Revise: D11.3 to read: The City intends to award this Contract by June 23, 2010
- Revise: D12.1(a) to read: All Work at 590 St. Anne's Road, with the exception of the soil report which may be submitted up to 2 weeks following, shall be completed by July 21, 2010.
- Revise: D13.1 to read: With exception to the soil reports, which may be submitted up to 2 weeks following, the Contractor shall achieve Total Performance by August 4, 2010.

PART E – SPECIFICATIONS

Add: E1.2.4 to read: The following drawings are applicable to the work. The drawings are to be used for informational purposes only and should not negate the need for a site investigation. Drawings were printed between 1978-1985.

| <u>Drawing No.</u> | <u>Drawing Name/Title</u> |
|--------------------|--|
| 84.603 F1 | 1539 Waverley Street District 6 Operations & Parks Departments Fueling Station Site Plan |
| 84.603 F2 | 1539 Waverley Street District 6 Operations & Parks Departments Fueling Station Enlarged Drawing. |
| L-427 | 590 St. Anne's Road Site Plan |

- Revise: E2.1 (a) (iv) to read: Removal and disposal of concrete fuel island and associated infrastructure including the complete removal of the curbing surrounding the elevated pad located above fuel tanks, and level to grade.
- Add: E2.1 (a) (xi) to read: Removal and restoration of metal fencing as required. Fencing is located adjacent to the fuel site on the North side. For the purposes of bidding, assume that fifty (50) feet of fencing will be removed and replaced. Replace with existing fence if possible, or match

new fence material to existing. For the purpose of bidding, assume that fifty (50) feet of new fence material will be required to replace the fencing removed during Work. If at the time of Work this amount is deemed not to be required, it will be eliminated from the cost billed to the City.

Add: E2.1 (a) (xii) to read Removal of ABS piping as required. ABS piping is located on the boulevard facing Forrester Avenue on the opposing side of the existing metal fence. For the purposes of bidding, assume that all related ABS piping infrastructure will be removed. If at the time of Work this amount is deemed not to be required, it will be eliminated from the cost billed to the City.

Add: E3.1 (a) (xi) to read Removal and restoration of chain-link fencing as required. Fencing runs approximately South-East to North-West and is currently above existing fuel tanks. For the purposes of bidding, assume that fifty (50) feet of fencing will be removed and replaced. Replace with existing fence if possible, or match new fence material to existing. For the purpose of bidding, assume that fifty (50) feet of new fence material will be required to replace the chain-link fencing removed during Work. If at the time of Work this amount is deemed not to be required, it will be eliminated from the cost billed to the City.

Add: E3.1 (a) (xii) to read Removal of large wood loading dock as required. Wood loading dock is located approximately South-West of the fence on the opposing side of the existing chain-link fence. If at the time of Work this amount is deemed not to be required, it will be eliminated from the cost billed to the City.

DRAWINGS

Add: 362-2010 _Drawing_84.603 F1

362-2010 _Drawing 84.603 F2

362-2010 _Drawing L-427