



229-2011 ADDENDUM 1

NOTRE DAME AVENUE WATERMAIN RENEWAL – CONTRACT NO.16

URGENT

**PLEASE FORWARD THIS DOCUMENT TO
WHOEVER IS IN POSSESSION OF THE BID
OPPORTUNITY**

ISSUED: March 25, 2011
BY: Hartley Katz, C.E.T., P.Eng.
TELEPHONE NO. (204) 489-5900

**THIS ADDENDUM SHALL BE INCORPORATED
INTO THE BID OPPORTUNITY AND SHALL
FORM A PART OF THE CONTRACT
DOCUMENTS**

Template Version: A20070419

Please note the following and attached changes, corrections, additions, deletions, information and/or instructions in connection with the Bid Opportunity, and be governed accordingly. Failure to acknowledge receipt of this Addendum in Paragraph 9 of Form A: Bid may render your Bid non-responsive.

PART A – BID SUBMISSION

Replace: 229-2011 Bid Submission with 229-2011 Addendum 1 - Bid Submission. The following is a summary of changes incorporated in the replacement Bid Submission:

Form B(R1): Add Item A. 5 'Rail Crossing Warning Signs'

Renumbered A. 6 through A. 18

Page numbering on forms did not change as a result.

PART E – SPECIFICATIONS

Revise: E5.5 a i) to read: 508 mm outside diameter steel pipe conforming to CW 2110

Revise: E5.5 a ii) to read: Minimum wall thickness: 7.1 mm

Add: E5.6 c Warning signs installed within the C.P. Rail right of way will be measured on a unit basis and paid for at the Contract Unit Price for "Rail Crossing Warning Signs". Number of units to be paid for will be the total number of warning signs supplied and installed in accordance with this specification, accepted and measured by Contract Administrator.

Add: E5.9 The Contractor shall be responsible for coordinating his work with Manitoba Hydro. The Contractor is to have a Manitoba Hydro watch present during construction within the C.P. Rail Right of Way due to the close proximity of overhead hydro lines. The Contractor shall be responsible for any charges associated having a hydro watch on site.

Add: E7.3 No additional payment shall be made for pipe and soil samples that are to be obtained by the Contractor. The unit price bid for the installation of "Watermain Renewals" shall include all work required to obtain the soil/pipe samples and provide them to the Contract Administrator in accordance with this specification.

DRAWINGS

Replace: 229-2011 _Drawing_D-12319-R0 with 229-2011 _Addendum_1 Drawing D-12319-R1