



5-2011 ADDENDUM 1

SUPPLY AND INSTALLATION OF QUARRY TILE FLOORING AND COVE BASE AT KITCHEN AND FOOD PREPARATION AREAS FOR THE HARBOUR VIEW RECREATION COMPLEX – 1867 SPRINGFIELD RD., WINNIPEG, MANITOBA

ISSUED: January 31, 2011
BY: Coleen Groening
TELEPHONE NO. (204) 986-2491

URGENT

**PLEASE FORWARD THIS DOCUMENT TO
WHOEVER IS IN POSSESSION OF THE BID
OPPORTUNITY**

**THIS ADDENDUM SHALL BE INCORPORATED
INTO THE BID OPPORTUNITY AND SHALL
FORM A PART OF THE CONTRACT
DOCUMENTS**

Template Version: A20070419

Please note the following and attached changes, corrections, additions, deletions, information and/or instructions in connection with the Bid Opportunity, and be governed accordingly. Failure to acknowledge receipt of this Addendum in Paragraph 8 of Form A: Bid may render your Bid non-responsive.

PART D – SUPPLEMENTAL CONDITIONS

- Revise:** D2.2 (b) to read: Demolition to include all components connected to and affecting a proper removal and new installation (wall tile base, water closets, floor drains). Cutting down of the existing metal door bottoms to accommodate new floor tile installation shall be the responsibility of the City of Winnipeg.
- Add:** D2.2 (d) the removal, modifications and reinstallation of the existing cooler and freezer stainless steel doors shall be the responsibility of the City of Winnipeg.
- Add:** D2.2 (e) Contractor shall remove and replace all floor drains with new and to be installed flush and level with new quarry tile. Contractor shall make all adjustments necessary.
- Add:** D2.2 (f) Contractor to provide new Schluter RENO-U transition strips or edges to suit all floor material changes.
- Add:** D2.2 (g) Contractor to provide epoxy coving beneath cooler and freezer doors only.