



306-2012 ADDENDUM #1

ULTRAVIOLET DISINFECTION SYSTEMS, 25 POSEIDON

URGENT

**PLEASE FORWARD THIS DOCUMENT TO
WHOEVER IS IN POSSESSION OF THE BID
OPPORTUNITY**

ISSUED: April 18, 2012
BY: Kathy Roberts
TELEPHONE NO. (204) 470-7380

**THIS ADDENDUM SHALL BE INCORPORATED
INTO THE BID OPPORTUNITY AND SHALL
FORM A PART OF THE CONTRACT
DOCUMENTS**

Template Version: A20070419

Please note the following and attached changes, corrections, additions, deletions, information and/or instructions in connection with the Bid Opportunity, and be governed accordingly. Failure to acknowledge receipt of this Addendum in Paragraph 8 of Form A: Bid may render your Bid non-responsive.

PART E – SPECIFICATIONS

Add:

E12. GENERAL REQUIREMENTS

- E12.1 Reference drawing M101, provide a 1" FNPT connection in the pool water piping between the outlet of the UV light and the existing 12" butterfly valve. Provide a type 316 stainless steel thermowell for the connection. Install the existing temperature sensor, used for pool temperature control, in the thermowell c/w heat transfer compound. Coordinate exact location on site. Provide reducers as required to suit thermowell/temperature probe and connection.
- E12.2 Reference Drawing M102. The contractor is to remove the existing 1-1/2" diameter PVC piping and associated pump that is currently tied into the redundant chlorine gas injection system. The pump associated with this system is to be turned over to the Owner.
- E12.3 Contractor is to complete all electrical work at the beginning of the pool shutdown. This is to maintain power availability to the other trades that will be on site completing other projects. Contractor to assume that shutdown will occur afterhours.