



573-2012 ADDENDUM 4

NORTH END WATER POLLUTION CONTROL CENTRE REHABILITATION OF DIGESTER NO. 11 AND SLUDGE HOLDING TANKS NO. 5 AND 7

URGENT

**PLEASE FORWARD THIS DOCUMENT TO
WHOEVER IS IN POSSESSION OF THE BID
OPPORTUNITY**

ISSUED: November 23, 2012
BY: Jamie Brewster
TELEPHONE NO. (204) 489-5900

**THIS ADDENDUM SHALL BE INCORPORATED
INTO THE BID OPPORTUNITY AND SHALL
FORM A PART OF THE CONTRACT
DOCUMENTS**

Template Version: A20070419

Please note the following and attached changes, corrections, additions, deletions, information and/or instructions in connection with the Bid Opportunity, and be governed accordingly. Failure to acknowledge receipt of this Addendum in Paragraph 10 of Form A: Bid may render your Bid non-responsive.

PART E – SPECIFICATIONS

- | | |
|--------------------------------------|---|
| Add: Section 03 70 00 Clause 3.1.6 | Removal of concrete. Contractor shall remove depths of damaged / softened concrete to minimum depths as shown on the drawings. Hydro demolition shall be the preferred method to demolish damaged concrete to sound concrete. All damaged concrete shall be removed. Means to demolish concrete shall not damage sound concrete. Damage of sound concrete shall be repaired at the expense of the Contractor. |
| Add: Section 03 70 00 Clause 3.1.7 | Hydro demolition. All damaged concrete shall be removed by water pressure to a maximum of 10,000 psi. Contractor shall create a trial blasting area. The size of the trial blasting area to be determined by the Contract Administrator. Water flow rates shall be the responsibility of the Contractor. All debris and water from hydro demolition shall be removed by the Contractor. |
| Add: Section 46 73 21 Clause 2.6.1.7 | In Gallery 5, replace two (2) existing 2.5 inches (63.5 mm) diameter flanged Fisher Pressure Regulating Valves with two (2) new Fisher PRVs. |