

830-2012 ADDENDUM 3

REHABILITATION OF BRIDGE AND REPLACEMENT OF MIDTOWN FEEDERMAIN AT THE ASSINIBOINE RIVER

URGENT

**PLEASE FORWARD THIS DOCUMENT TO
WHOEVER IS IN POSSESSION OF THE BID
OPPORTUNITY**

ISSUED: December 3, 2012
BY: M.McDonald
TELEPHONE NO. (204) 477-5381

**THIS ADDENDUM SHALL BE INCORPORATED
INTO THE BID OPPORTUNITY AND SHALL
FORM A PART OF THE CONTRACT
DOCUMENTS**

Template Version: A20120228

Please note the following and attached changes, corrections, additions, deletions, information and/or instructions in connection with the Bid Opportunity, and be governed accordingly. Failure to acknowledge receipt of this Addendum in Paragraph 10 of Form A: Bid may render your Bid non-responsive.

PART E – SPECIFICATIONS

Revise: E3.2 (e) (Addendum 2) to read:

The Contractor will be permitted to obtain temporary power from the Aubrey Flood Pumping Station. The Contractor will be required to provide all temporary panels, wiring, cables, breakers and other items required to complete the connections. 600 volt and single phase power is available. The Contractor shall meter power usage. The Contractor will not be permitted to connect to power supply if flood pumping station is in service.

Add: E19.2 (a) (viii)

(viii) Quality Control

- (i) Provide record of pressure test for all pipe in accordance to AWWA C200-12 Section 5.2.1. Submit test records to Contract Administrator.
- (ii) Provide evidence of Quality Assurance program, and test reports of pipe manufacture upon request of Contract Administrator. Manufacture records shall be traceable to pipe runs. Pipes shall be marked in accordance to AWWA C200 Section 6.1.

Add: E19.2 (l) (iv)

(iv) Quality Control

- (i) Provide access to Contract Administrator for inspection of coating processes. Provide a minimum of 5 Business Days notice in advance of coating operations.
- (ii) Provide test records of coating systems and preparation process.
- (iii) Contract Administrator reserves the right to conduct Quality Assurance testing on coatings. Contractor shall repair any defects resulting from Contract Administrator testing.