

242-2015 ADDENDUM #2

KILDONAN PARK GOLF COURSE – PATIO RENOVATION

URGENT

PLEASE FORWARD THIS DOCUMENT TO WHOEVER IS IN POSSESSION OF THE BID OPPORTUNITY

ISSUED: MAY 7, 2015 BY: KATHY ROBERTS TELEPHONE NO. (204) 470-7380

THIS ADDENDUM SHALL BE INCORPORATED INTO THE BID OPPORTUNITY AND SHALL FORM A PART OF THE CONTRACT DOCUMENTS

Please note the following and attached changes, corrections, additions, deletions, information and/or instructions in connection with the Bid Opportunity, and be governed accordingly. Failure to acknowledge receipt of this Addendum in Paragraph 8 of Form A: Bid may render your Bid non-responsive.

PART A - BID SUBMISSION

Replace: 242-2015 Bid_Submission with 242-2015 Addendum_2_Bid_Submission. The following is a summary of changes incorporated in the replacement Bid Submission:

Form B(R1): Add Item No. 13, REMOVE AND DISPOSE OF IRRIGATION PIPING

PART D – SUPPLEMENTAL CONDITIONS

Revise:	D2.2(d) to read:	Restore all areas damaged during construction, including curbing, sidewalk, and grassed areas. No extra will be allowed for restoration Work.
Delete:	D2.2(d)(i)	
Add:	D2.2(e)	Create Construction Access Path following Specification E6, and protect all trees adjacent to the Work Area. The City will mark the boundaries of the Work Area, where construction fencing shall be installed.
Add:	D2.2(f)	Contractor shall arrange and pay for all necessary permits and inspections, and obtain all necessary approvals of the Authority Having Jurisdiction.

PART E – SPECIFICATIONS

Add:	E5.4(a)	Contractor shall be permitted to stockpile materials at the southwest side of the Work Area.
Revise:	E5.6 to read:	Golf Course parking lot shall not be used by the Contractor for personal parking or any construction-related purpose.
Revise:	E5.7 to read:	Contractor must provide washroom facilities for their workers. Contractor may not use the washroom facilities in the Clubhouse. Contractor's washroom facilities to be located on the south side of the Work Area.
Add:	E5.8	Contractor to provide own generator for any required power. Generator to be located on the southwest side of the Work Area, to be least disruptive to golfers on the 18 th green.

Bid Opportunity No. 242-2015 Addendum #2 Page 2 of 2

Revise:	E6.1 to read:	Construction deliveries shall use the designated Construction Access Path only. No deliveries or access of any kind will be permitted at the North (parking lot) side of the Site.
Add:	E6.3(c)	The City will spray-paint lines to indicate Work Area extents, where Contractor shall install boundary fencing.
Delete:	E6.4(a)(ii)	
Delete:	E6.4(b)	
Revise:	E6.4(c) to read:	Contractor shall lay 5/8" plywood over the entire Construction Access Path.
Revise:	E7.3 to read:	Contractor shall be responsible for obtaining permit(s) to block a lane on Main Street for deliveries. No construction deliveries will be allowed after 3:00 pm daily.
Revise:	E7.5 to read:	Contractor shall ensure that Work Area is secured at the end of each day.
Revise:	E7.6 to read:	Only the following vehicles/equipment will be allowed on the Construction Access Path:
Delete:	E7.6(a)	
Revise:	E7.6(b) to read:	Bobcat or Skid Steer with tracks
Delete:	E7.6(c)	
Add:	EDD	REMOVE AND DISPOSE OF IRRIGATION PIPING
	E22	REMOVE AND DISPOSE OF IRRIGATION FIFING
	E22.1	Description
	E22.1	Description Work shall include the removal and disposal of underground irrigation piping,
	E22.1 E22.1.1	Description Work shall include the removal and disposal of underground irrigation piping, including capping the piping.
	E22.1 E22.1.1 E22.1.2	Description Work shall include the removal and disposal of underground irrigation piping, including capping the piping. Confirm extent of removal with Contract Administrator. In removal areas where new construction work is not specified elsewhere in the
	E22.1 E22.1.1 E22.1.2 E22.1.3	Description Work shall include the removal and disposal of underground irrigation piping, including capping the piping. Confirm extent of removal with Contract Administrator. In removal areas where new construction work is not specified elsewhere in the drawings and specifications, Contractor shall remediate the area with topsoil and sod.
	E22.1 E22.1.1 E22.1.2 E22.1.3 E22.1.4	DescriptionWork shall include the removal and disposal of underground irrigation piping, including capping the piping.Confirm extent of removal with Contract Administrator.In removal areas where new construction work is not specified elsewhere in the drawings and specifications, Contractor shall remediate the area with topsoil and sod.Specification E21.1.5 will apply to this section.

DRAWINGS

Replace: 242-2015_Addendum_1_Drawing_K.3-1-R1 with 242-2015_Addendum_2_Drawing_K.3-1-R2