



821-2015 ADDENDUM 1

2015 SEWER RENEWALS BY CIPP LINING, CONTRACT 3

URGENT

PLEASE FORWARD THIS DOCUMENT TO WHOEVER IS IN POSSESSION OF THE BID OPPORTUNITY

ISSUED: January 15, 2016
BY: Christopher Mitchell
TELEPHONE NO. 204 928-9259

THIS ADDENDUM SHALL BE INCORPORATED INTO THE BID OPPORTUNITY AND SHALL FORM A PART OF THE CONTRACT DOCUMENTS

Template Version: A20150806

Please note the following and attached changes, corrections, additions, deletions, information and/or instructions in connection with the Bid Opportunity, and be governed accordingly. Failure to acknowledge receipt of this Addendum in Paragraph 10 of Form A: Bid may render your Bid non-responsive.

PART B – SITE INVESTIGATION

- Add: B3.3: Further to C3.1 and E5.3.2, the Contract Administrator or an authorised representative will be available at the Ash Pumping Station Site at the intersection of Ash Street and Wellington Crescent, Winnipeg R3M 0A7 from 9:00am to 11:00am, on January 21, 2016 to provide Bidders access to the Site.
- Add: B3.4: Proponents attending the investigation are requested to notify the Contract Administrator listed in D4, a minimum of 24 hours in advance of the site meeting.
- Add: B3.5: The Bidder shall not be entitled to rely on any information or interpretation received at the Site investigation unless that information or interpretation is the Bidder’s direct observation, or is provided by the Contract Administrator in writing.
- Add: B3.6: Although attendance at the Site investigations is not mandatory, the City strongly suggests that Proponents attend.
- Add: B3.7: The Bidder is advised that valve chambers and other structures will be deemed Confined Entry locations. Persons wishing to enter these structures will be required to supply all necessary personal protective safety equipment, including body harness, hard hats and safety boots, gas detector as well as intrinsically safe lighting required to view the site. The City of Winnipeg will provide a retrieval hoist and surface lighting. Personnel attending the Site and intending to enter Confined Spaces shall be properly trained in Confined Space entry in accordance with Manitoba legislation and their individual company policy.

PART E – SPECIFICATIONS

- Revise: E5.3.2(g) to read: Pump station shutdowns shall only commence at or near 12:00 AM (midnight) and only once the Contractor is fully prepared to proceed with the proposed work with City approval. Pump station shutdowns shall only occur during weekdays (Monday to Friday). Estimated shutdown durations provided in E5.3.2(h) are based on shutdowns commencing at 12:00 AM. Long duration shutdowns (longer than 6.5 hrs) may commence at alternative times of the day, however, the Contractor shall be aware that storage volumes within the SRS system may increase or decrease accordingly from those provided in Appendix C.

- Revise: E5.3.2(i) to read: Dewatering of the SRS, if applicable, may only commence after the system has been dewatered below 225.48 m with the Ash Pumping Station. Depending on the level of sewage storage, drawing down the system with the Ash Pumping Station to this level may take upwards of 13.5 hours.
- Add: E7.5.6 b): Manhole Installations shown on the drawings to be constructed "By Others" or identified prior to sewer lining will be completed by the City of Winnipeg. However, during the Contract, if the City of Winnipeg is unable to undertake this work, the Contract Administrator shall instruct the Bidder to install said Manholes using the Provisional Pricing M.1 to M.3.