

APPENDIX C (R2) – PROJECT LOCATIONS AND TECHNICAL SCOPING

See Tables below.

Note:

The “Additional Information” provided within the following tables relative to specific Project Packages and/or Project Locations contain specific information or issues, known to exist on Site at the time of issuance of this Request for Proposal. This information is not meant to be exhaustive and not meant to take the place of investigations and due diligence required of the Proponent.

The specific utility and agency coordination identified below notwithstanding, the successful Consultant(s) will be required to investigate and coordinate any utility requirements of the Project.

LOCAL STREETS PACKAGE - 16-R-01			Notes	Street	From	To	Const. Est.	Project Est.
16-R-01	842-2015.1	Concrete Reconstruction	1,3,4	De Baets St	Paquin Rd	Camiel Sys St	\$2,414,740	\$3,714,984
16-R-01	842-2015.1	Concrete Reconstruction	1,2,3	Saulteaux Cr W Leg	Moray St	Murray Park Rd	\$1,443,125	\$2,220,192
LOCAL STREETS PACKAGE - 16-R-01							Total Project Package Budget	\$5,935,176
							Fees Proposal Evaluation Criteria (see B20.2)	B - STANDARD
<p><i>Additional Information:</i></p> <p>General Assume 85 working days to Substantial Performance for this package</p> <ol style="list-style-type: none"> 1 Consultant to provide a pavement design brief 2 The concrete/asphalt reconstruction streets in this package will have street lighting work (including the installation of bases and wiring and the replacement of lamp standards) completed under the roadworks construction contract. Co-ordination with Manitoba Hydro will be required. Lighting design will be completed by Manitoba Hydro and inspection will be provided by Manitoba Hydro after each phase of work. Layout will be performed by the successful proponent. Quantities to be included in the Bid Opp and typical Manitoba Hydro specifications for all works to be included in the construction Bid Opportunity will be supplied to the successful proponent. Work will be required to insert documents into the construction Bid Opportunity. 3 Project to include the construction of new sidewalk on one side of the roadway. Consultant is to consider/study pedestrian activities and provide most appropriate options. The new sidewalk on Saulteaux includes new railway crossing. Railway road crossing was recently replaced and is not anticipated to be replaced in this contract. Co-ordination with CPR required. 4 Backlogged sewer external point repairs. Co-ordination with Water and Waste required. 								

LOCAL STREETS PACKAGE - 16-R-02			Notes	Street	From	To	Const. Est.	Project Est.
16-R-02	842-2015.2	Concrete Reconstruction	4,5,6	Trottier Bay	Chevrier Blvd	Chevrier Blvd	\$668,023	\$1,027,728.00
16-R-02	842-2015.2	Concrete Reconstruction	2,4	Sony Pl	Irene St	Hamelin St	\$627,869	\$965,952.00
16-R-02	842-2015.2	Concrete Reconstruction	2,3	Yale Ave	Rockwood St	Cambridge St	\$272,938	\$419,904.00
16-R-02	842-2015.2	Concrete Reconstruction	2,3	Hector Ave	Wilton St	Hector Bay E (W Leg)	\$411,091	\$632,448.00
16-R-02	842-2015.2	Concrete Reconstruction	3	Mathers Ave	Ash St	Campbell St	\$1,284,941	\$1,976,832.00
16-R-02	842-2015.2	Rehabilitation	3	Lorette Ave	Arbuthnot St	Stafford St	\$412,916	\$635,256
16-R-02	842-2015.2	Concrete Reconstruction	1,3	Scotland Ave	Wentworth St	50m West	\$84,240	\$129,600
16-R-02	842-2015.2	Concrete Reconstruction	2,3	Jessie Ave	Nassau St N	Daly St N	\$405,194	\$623,376
16-R-02	842-2015.2	Asphalt Reconstruction	3	Cockburn St S	Kylemore Ave	Rathgar Ave	\$196,344	\$302,068
16-R-02	842-2015.2	Concrete Reconstruction		South Dr	Dowker Ave	Crane Ave	\$566,233	\$871,128
LOCAL STREETS PACKAGE - 16-R-02							Total Project Package Budget	\$7,584,292
							<i>Fees Proposal Evaluation Criteria (see B20.2)</i>	B - STANDARD
Additional Information:								
<p>General Assume 2 construction Bid Opportunities with 75 working days each to Substantial Performance for this package</p> <ol style="list-style-type: none"> 1 School in the immediate vicinity - Construction must take place during July/August 2 The concrete/asphalt reconstruction streets in this package will have street lighting work (including the installation of bases and wiring and the replacement of lamp standards) completed under the roadworks construction contract. Co-ordination with Manitoba Hydro will be required. Lighting design will be completed by Manitoba Hydro and inspection will be provided by Manitoba Hydro after each phase of work. Layout will be performed by the successful proponent. Quantities to be included in the Bid Opp and typical Manitoba Hydro specifications for all works to be included in the construction Bid Opportunity will be supplied to the successful proponent. Work will be required to insert documents into the construction Bid Opportunity. 3 Backlogged sewer external point repairs. Co-ordination with Water and Waste required. 4 Consultant to provide a pavement design brief 5 Project to include the construction of new sidewalk on one side of the roadway. Consultant is to consider/study pedestrian activities and provide most appropriate options. 6 Consultant to review and recommend geometric changes including pavement width. Consultant to review adjacent properties access and transportation requirements/operations. 								

LOCAL STREETS PACKAGE - 16-R-03			Notes	Street	From	To	Const. Est.	Project Est.
16-R-03	842-2015.3	Rehabilitation	1	Rougeau Ave N/B and S/B	Regent Ave W	#453 Rougeau	\$415,188	\$638,750.00
16-R-03	842-2015.3	Rehabilitation	5	Bond St	McMeans Ave W	Victoria Ave W	\$843,336	\$1,297,440.00
16-R-03	842-2015.3	Rehabilitation	5	Ravelston Ave W	Day St	Madeline St	\$534,643	\$822,528.00
16-R-03	842-2015.3	Rehabilitation	2,4,5	Rothesay St	Edison Ave	McLeod Ave	\$593,775	\$913,500
16-R-03	842-2015.3	Rehabilitation	5	Mildred St	Knowles Ave	Headmaster Row	\$105,300	\$162,000
16-R-03	842-2015.3	Rehabilitation	2,5	McLeod Ave	Durness Bay	Rothesay St	\$254,641	\$391,755
16-R-03	842-2015.3	Rehabilitation	5	Pennefather St	Headmaster Row	Bonner Ave	\$133,380	\$205,200
16-R-03	842-2015.3	Rehabilitation		Rockspur St	Tu-pelo Ave	Antrim Rd	\$326,196	\$501,840
16-R-03	842-2015.3	Rehabilitation	7	Grey St	Kimberly Ave	Concordia Ave	\$183,938	\$282,982
16-R-03	842-2015.3	Rehabilitation		London St	Nottingham Ave	Union Ave E	\$178,270	\$274,261
16-R-03	842-2015.3	Rehabilitation	2,5,8	Poplar Ave	Brazier St	Henderson Hwy	\$207,309	\$318,937
16-R-03	842-2015.3	Asphalt Reconstruction	3,5,6	Manhattan Ave	CPR RRX	Grey St	\$386,148	\$594,074
LOCAL STREETS PACKAGE - 16-R-03							Total Project Package Budget	\$6,403,267
							Fees Proposal Evaluation Criteria (see B20.2)	B - STANDARD
<p><i>Additional Information:</i></p> <p><i>General Assume 2 construction Bid Opportunities with 75 working days each to Substantial Performance for this package</i></p> <p>1 Includes construction of new sidewalk and railway crossing on eastside. Co-ordination with CEMR required.</p> <p>2 School in the immediate vicinity - Construction must take place during July/August</p> <p>3 The concrete/asphalt reconstruction streets in this package will have street lighting work (including the installation of bases and wiring and the replacement of lamp standards) completed under the roadworks construction contract. Co-ordination with Manitoba Hydro will be required. Lighting design will be completed by Manitoba Hydro and inspection will be provided by Manitoba Hydro after each phase of work. Layout will be performed by the successful proponent. Quantities to be included in the Bid Opp and typical Manitoba Hydro specifications for all works to be included in the construction Bid Opportunity will be supplied to the successful proponent. Work will be required to</p> <p>4 Watermain renewal by Water and Waste planned in 2016. Co-ordination with Water & Waste will be required.</p> <p>5 Backlogged sewer external point repairs. Co-ordination with Water and Waste required.</p> <p>6 Co-ordination with CPR will be required. Railway crossing renewal not included.</p> <p>7 Sewer EPR by Water and Waste scheduled in 2016 at Bronx Intersection. Co-ordination required.</p> <p>8 Adjacent sewer liner by Water and Waste scheduled in 2016. Co-ordination required.</p>								

LOCAL STREETS PACKAGE - 16-R-04			Notes	Street	From	To	Const. Est.	Project Est.
16-R-04	842-2015.4	Rehabilitation	4	Eagle Dr	Oak Point Hwy	Brookside Blvd	\$892,915	\$1,373,715
16-R-04	842-2015.4	Rehabilitation/Asphalt Reconstruction	2,6	Flint St	William Ave W	Notre Dame Ave	\$331,765	\$510,408
16-R-04	842-2015.4	Rehabilitation		Ritchie St	Foxwarren Dr	Chochinov Ave	\$210,038	\$323,136
16-R-04	842-2015.4	Rehabilitation	4	Leahcrest Cr W Leg	Argate Dr	Scarfe St	\$496,454	\$763,776
16-R-04	842-2015.4	Rehabilitation	4	Maevista Pl	Blechner Dr	Jefferson Ave	\$220,381	\$339,048
16-R-04	842-2015.4	Rehabilitation	5	Valewood Cr	Marianne Rd	Inkster Garden Dr	\$418,486	\$643,824
16-R-04	842-2015.4	Rehabilitation	4	Mallard Way	Inkster Garden Dr	Inkster Garden Dr	\$260,161	\$400,248
16-R-04	842-2015.4	Rehabilitation	4	Petriw Bay	Rosehill Way	Rosehill Way	\$301,532	\$463,896
16-R-04	842-2015.4	Asphalt Reconstruction	3,4	Artillery St	Burrows Ave	Pritchard Ave	\$302,983	\$466,128
16-R-04	842-2015.4	Rehabilitation		Acores St	N. Limit	Higgins Ave	\$47,736	\$73,440
16-R-04	842-2015.4	Rehabilitation	1,4	Machray Ave	Robertson St	McPhillips St	\$368,363	\$566,712
LOCAL STREETS PACKAGE - 16-R-04							Total Project Package Budget	\$5,924,331
							Fees Proposal Evaluation Criteria (see B20.2)	B - STANDARD
<p><i>Additional Information:</i></p> <p>General Assume 2 construction Bid Opportunities with 75 working days each to Substantial Performance for this package</p> <ol style="list-style-type: none"> 1 School in the immediate vicinity - Construction must take place during July/August 2 Sewer EPR by Water and Waste scheduled in 2016. Co-ordination required. 3 MH renewal by Water and Waste scheduled in 2016. Co-ordination required. 4 Backlogged sewer external point repairs. Co-ordination with Water and Waste required. 5 Includes cul-de-sac for #68 to #104 Valewood 6 Asphalt Reconstruction Notre Dame to Winnipeg 								

LOCAL STREETS PACKAGE - 16-R-05			Notes	Street	From	To	Const. Est.	Project Est.
16-R-05	842-2015.5	Rehabilitation		Dussault Ave	Bibeau Bay S Leg	Cottonwood Rd	\$225,950	\$347,616
16-R-05	842-2015.5	Rehabilitation	4,5,7	Traverse Ave	Enfield Cr	St. Mary's Rd	\$259,896	\$399,840
16-R-05	842-2015.5	Rehabilitation	2,4	Lakewood Blvd	Edgewater Dr	Beaverhill Blvd	\$784,992	\$1,207,680
16-R-05	842-2015.5	Rehabilitation	4	Abbotsford Cr	Dakota St	Wyoming St	\$163,098	\$250,920
16-R-05	842-2015.5	Asphalt Reconstruction	1,4	Portland Ave	St. George Rd	Neepawa St	\$495,238	\$761,904
16-R-05	842-2015.5	Asphalt Reconstruction	1,3,4	Vivian Ave	Rue Des Meurons	St. Mary's Rd	\$295,682	\$454,896
16-R-05	842-2015.5	Rehabilitation	4,5	Crofton Bay	Pulberry St	Pulberry St	\$511,571	\$787,032
16-R-05	842-2015.5	Rehabilitation	6	Cloutier Dr	#878 Cloutier Dr	Pembina Hwy	\$264,139	\$406,368
16-R-05	842-2015.5	Rehabilitation	2,4	Markham Rd	Forest Lake Dr	Chancellor Dr S Leg	\$343,699	\$528,768
16-R-05	842-2015.5	Rehabilitation	4	Killkenny Dr	Kings Dr	Patricia Ave	\$452,813	\$696,636
LOCAL STREETS PACKAGE - 16-R-05							Total Project Package Budget	\$5,841,660
							Fees Proposal Evaluation Criteria (see B20.2)	B - STANDARD
Additional Information:								
<i>General Assume 2 construction Bid Opportunities with 75 working days each to Substantial Performance for this package</i>								
<ol style="list-style-type: none"> 1 The concrete/asphalt reconstruction streets in this package will have street lighting work (including the installation of bases and wiring and the replacement of lamp standards) completed under the roadworks construction contract. Co-ordination with Manitoba Hydro will be required. Lighting design will be completed by Manitoba Hydro and inspection will be provided by Manitoba Hydro after each phase of work. Layout will be performed by the successful proponent. Quantities to be included in the Bid Opp and typical Manitoba Hydro specifications for all works to be included in the construction Bid Opportunity will be supplied to the successful proponent. Work will be required to insert documents into the construction Bid Opportunity. 2 School in the immediate vicinity - Construction must take place during July/August 3 Consultant to provide a pavement design brief 4 Backlogged sewer external point repairs. Co-ordination with Water and Waste required. 5 Watermain renewal by Water and Waste planned in 2016. Co-ordination with Water & Waste will be required. 6 Watermain renewal planned on Pembina Hwy in 2016. Co-ordination with Water & Waste will be required. 7 Includes entire intersection at Enfield 								

LOCAL STREETS PACKAGE - 16-R-06			Notes	Street	From	To	Const. Est.	Project Est.
16-R-06	842-2015.6	Rehabilitation/Asphalt Reconstruction	2,3,4,6	Acheson Dr	West Limit	Arthur Creak Dr S Leg	\$644,904	\$992,160
16-R-06	842-2015.6	Rehabilitation		Goodridge Cr	Acheson Dr	Arthur Creak Dr	\$154,346	\$237,456
16-R-06	842-2015.6	Rehabilitation		Sonnichsen Pl	Hamilton Ave	Acheson Dr	\$70,013	\$107,712
16-R-06	842-2015.6	Rehabilitation	1,4	Bedson St	Allard Ave	Sansome Ave	\$356,429	\$548,352
16-R-06	842-2015.6	Asphalt Reconstruction	2	Olive St	Portage Ave	Assiniboine Cr	\$205,806	\$316,624
16-R-06	842-2015.6	Rehabilitation		Tylehurst St	Portage Ave	Wolseley Ave W	\$148,777	\$228,888
16-R-06	842-2015.6	Asphalt Reconstruction	4	Rowand Ave	Mount Royal Rd	Mount Royal Rd	\$637,603	\$980,928
16-R-06	842-2015.6	Concrete Reconstruction	1,3,5	Burnell St	St. Matthews Ave	St. Paul Ave	\$780,000	\$1,200,000
16-R-06	842-2015.6	Asphalt Reconstruction	2,3,4	Toronto St	St. Matthews Ave	Portage Ave	\$400,953	\$616,850
16-R-06	842-2015.6	Asphalt Reconstruction	1,2,4	Stack St	Barker Blvd S Leg	Roblin Ave	\$232,003	\$356,928
16-R-06	842-2015.6	Asphalt Reconstruction	2,4	Boreham Blvd	Corydon Ave	Cuthbertson Ave	\$328,536	\$505,440
16-R-06	842-2015.6	Rehabilitation	4	Barker Blvd SB	Barker Blvd S Leg	Roblin Ave	\$191,740	\$294,984
16-R-06	842-2015.6	Rehabilitation		Barker Blvd NB	Roblin Ave	Barker Blvd S Leg	\$191,740	\$294,984
Total Project Package Budget							\$6,681,306	
<i>Fees Proposal Evaluation Criteria (see B20.2)</i>								B - STANDARD
<p>Additional Information:</p> <p>General Assume 2 construction Bid Opportunities with 75 working days each to Substantial Performance for this package</p> <ol style="list-style-type: none"> 1 School in the immediate vicinity - Construction must take place during July/August 2 The concrete/asphalt reconstruction streets in this package will have street lighting work (including the installation of bases and wiring and the replacement of lamp standards) completed under the roadworks construction contract. Co-ordination with Manitoba Hydro will be required. Lighting design will be completed by Manitoba Hydro and inspection will be provided by Manitoba Hydro after each phase of work. Layout will be performed by the successful proponent. Quantities to be included in the Bid Opp and typical Manitoba Hydro specifications for all works to be included in the construction Bid Opportunity will be supplied to the successful proponent. Work will be required to insert documents into the construction Bid Opportunity. 3 Watermain renewal by Water and Waste planned in 2016. Co-ordination with Water & Waste will be required. 4 Backlogged sewer external point repairs. Co-ordination with Water and Waste required. 5 See Appendix E- Drawings for conceptual/preliminary drawing of Burnell. Consultant to review drawing and incorporate drawing and recommendations as required into final design. 6 Asphalt reconstruction aproximately 180m at Dohaney intersection 								

ALLEY PACKAGE - 16-RL-01			Notes	Lane Bounded By	Const. Est.	Project Est.
16-RL-01	842-2015.7	Concrete Reconstruction		Waterloo St/Ash St/Wellington Cr/Academy Rd	\$539,904	\$830,622
16-RL-01	842-2015.7	Concrete Reconstruction		Waverley St/Oxford St/Grosvenor Ave/Kingsway Ave	\$450,115	\$692,484
16-RL-01	842-2015.7	Concrete Reconstruction		Cambridge St/Oxford St/Grosvenor Ave/Corydon Ave	\$447,782	\$688,896
16-RL-01	842-2015.7	Concrete Reconstruction		Lilac St/Wentworth St/Grosvenor Ave/Dorchester Ave	\$200,569	\$308,568
16-RL-01	842-2015.7	Concrete Reconstruction		Wardlaw Ave/Stradbroke Ave/Donald St/Scott St	\$316,013	\$486,174
16-RL-01	842-2015.7	Concrete Reconstruction	2	McPhillips St/Fife St/Troy Ave/Chamberlain Ave	\$233,220	\$358,800
16-RL-01	842-2015.7	Concrete Reconstruction		St. Anthony ave/Jefferson Ave/McGregor St/McKenzie St	\$233,220	\$358,800
16-RL-01	842-2015.7	Concrete Reconstruction	1	Jefferson Ave/Perth Ave/Powers St/Andrews St	\$152,759	\$235,014
16-RL-01	842-2015.7	Concrete Reconstruction		Main St(eastside)/North-South Lane/Kingsbury Ave/Royal Ave	\$94,454	\$145,314
16-RL-01	842-2015.7	Concrete Reconstruction		Main St(eastside)/North-South Lane/Semple Ave/Burrin Ave	\$116,610	\$179,400
16-RL-01	842-2015.7	Concrete Reconstruction		Chestnut St/Walnut St/Preston Ave/Westminster Ave	\$257,708	\$396,474
16-RL-01	842-2015.7	Concrete Reconstruction	1	Garfield St N/Sherburn St/Notre Dame Ave/Grundy Ave	\$202,901	\$312,156
16-RL-01	842-2015.7	Concrete Reconstruction		Agnes St/Victor St/Ellice Ave/Sargent Ave	\$464,108	\$714,012
16-RL-01	842-2015.7	Concrete Reconstruction		Portage Ave/Wolseley St/Basswood Pl/Newman St	\$466,440	\$717,600
16-RL-01	842-2015.7	Concrete Reconstruction		Young St/Spence St/Cumberland Ave/Sargent Ave	\$299,688	\$461,058
16-RL-01	842-2015.7	Concrete Reconstruction	1,3	Crossgate Rd/Whitehall Blvd/St.Martin Blvd/Krambele Pl	\$209,898	\$322,920
Total Project Package Budget					\$7,208,292	
<i>Fees Proposal Evaluation Criteria (see B20.2)</i>					B - STANDARD	
<p><i>Additional Information:</i></p> <p>General Assume 2 construction Bid Opportunities with 75 working days each to Substantial Performance for this package</p> <p>1 School in the immediate vicinity - Construction must take place during July/August</p> <p>2 North-South lane adjacent to 1030 McPhillips</p> <p>3 Backlogged sewer external point repairs. Co-ordination with Water and Waste required.</p>						

REGIONAL STREETS PACKAGE - 16-C-01			Notes	Street	From	To	Const. Est.	Project Est.
16-C-01	842-2015.8	Rehabilitation	1,2,3	Sargent Avenue	Victor Street	Arlington Street	\$1,170,000	\$1,800,000
16-C-01	842-2015.8	Mill and Fill	4	Isabel Street	Notre Dame Avenue	William Avenue	\$325,000	\$500,000
16-C-01	842-2015.8	Mill and Fill	4	Notre Dame Avenue (Eastbound)	Wall Street	Arlington Street	\$487,500	\$750,000
Total Project Package Budget								\$3,050,000
<i>Fees Proposal Evaluation Criteria (see B20.2)</i>								B - STANDARD
<p><i>Additional Information:</i></p> <p><i>General Assume 45 working days to Substantial Performance for this package</i></p> <ol style="list-style-type: none"> 1 Watermain renewal by Water and Waste planned in 2016. Co-ordination with Water & Waste will be required. 2 Backlogged sewer external point repairs. Co-ordination with Water and Waste required. 3 Includes construction of new pedestrian corridors at Toronto and Agnes. Co-ordination required. 4 Construction on Isabel Street and Notre Dame projects not to occur concurrently 								

REGIONAL STREETS PACKAGE - 16-C-02			Notes	Street	From	To	Const. Est.	Project Est.
16-C-02	842-2015.9	Rehabilitation	1,2,3,5,6	Academy Road	Harrow Street	Stafford Street	\$455,000	\$700,000
16-C-02	842-2015.9	Mill and Fill	3,4	Academy Road	Stafford Street	Maryland Bridge	\$520,000	\$800,000
16-C-02	842-2015.9	Mill and Fill	6,7	Academy Road	Campbell Street	Renfrew Street	\$455,000	\$700,000
Total Project Package Budget								\$2,200,000
Fees Proposal Evaluation Criteria (see B20.2)								B - STANDARD
<p>Additional Information:</p> <p>General Assume 35 working days to Substantial Performance for this package</p> <ol style="list-style-type: none"> 1 Includes new full width sidewalk on northside 2 The concrete/asphalt reconstruction streets in this package will have street lighting work (including the installation of bases and wiring and the replacement of lamp standards) completed under the roadworks construction contract. Co-ordination with Manitoba Hydro will be required. Lighting design will be completed by Manitoba Hydro and inspection will be provided by Manitoba Hydro after each phase of work. Layout will be performed by the successful proponent. Quantities to be included in the Bid Opp and typical Manitoba Hydro specifications for all works to be included in the construction Bid Opportunity will be supplied to the successful proponent. Work will be required to insert documents into the construction Bid Opportunity. 3 School in the immediate vicinity - Construction must take place during July/August 4 Sewermain renewal by Water and Waste planned in 2016. Co-ordination with Water & Waste will be required. 5 Backlogged sewer external point repairs. Co-ordination with Water and Waste required. 6 Construction not to begin until after Manitoba Marathon 7 Includes railway crossing resurfacing. Co-ordinate with CPR 								

REGIONAL STREETS PACKAGE - 16-C-03			Notes	Street	From	To	Const. Est.	Project Est.
16-C-03	842-2015.10	Mill and Fill	3,4,5	Maryland Street	Ellice Avenue	Portage Avenue	\$455,000	\$700,000
16-C-03	842-2015.10	Rehabilitation	1,2	Maryland Street	Portage Avenue	Broadway Avenue	\$520,000	\$800,000
Total Project Package Budget								\$1,500,000
Fees Proposal Evaluation Criteria (see B20.2)								B - STANDARD
<p><i>Additional Information:</i></p> <p><i>General Assume 35 working days to Substantial Performance for this package</i></p> <ol style="list-style-type: none"> <i>1 Backlogged sewer external point repairs. Co-ordination with Water and Waste required.</i> <i>2 School in the immediate vicinity - Construction must take place during July/August</i> <i>3 Watermain renewal by Water and Waste planned in 2016. Co-ordination with Water & Waste will be required.</i> <i>4 Sewermain renewal by Water and Waste planned in 2016. Co-ordination with Water & Waste will be required.</i> <i>5 Includes construction of pedestrian corridors at St. Matthews. Co-ordination required.</i> 								

REGIONAL STREETS PACKAGE - 16-C-04			Notes	Street	From	To	Const. Est.	Project Est.
16-C-04	842-2015.11	Mill and Fill	2,4	Lagimodiere Southbound	Dugald Road	Marion Street	\$162,500	\$250,000
16-C-04	842-2015.11	Mill and Fill	1,3,5	St Mary's Road(NB and SB)	St Anne's Road	Lyndale Drive	\$1,040,000	\$1,600,000
Total Project Package Budget								\$1,850,000
Fees Proposal Evaluation Criteria (see B20.2)								B - STANDARD
<p><i>Additional Information:</i></p> <p><i>General Assume 40 working days to Substantial Performance for this package</i></p> <p><i>1 Backlogged sewer external point repairs. Co-ordination with Water and Waste required.</i></p> <p><i>2 Construction not to start until September 1, 2016</i></p> <p><i>3 Construction not to begin until after Manitoba Marathon</i></p> <p><i>4 Does not include railway crossing resurfacing. Co-ordinate with GWWD Railway</i></p> <p><i>5 Must maintain 2 lanes of traffic in the peak traffic direction</i></p>								

GRANULAR ROAD RENEWAL - 16-R-07			Notes	Street	From	To	Const. Est.	Project Est.
16-R-07	842-2015.12	Granular Road Reconstruction	1,2,3	Loudoun Road	Wyper Road	Wilkes Avenue	\$2,100,000	\$3,000,000
Total Project Package Budget								\$3,000,000
Fees Proposal Evaluation Criteria (see B20.2)								B - STANDARD
<p><i>Additional Information:</i></p> <p><i>General Assume 120 working days to Substantial Performance for this package</i></p> <p>¹ <i>The project budget for the Loudon Rd renewal is part of the 2016 and 2017 Capital Budgets. There is \$1,500,00 budgeted in 2016 and \$1,500,000 budgeted in 2017. The work is to be completed in stages, with Total Completion of all works by the end of the 2017 construction season. It is expected that there will be a separate construction Bid Opportunity for each year of construction and be based on the allocated project budget for each year.</i></p> <p>² <i>Includes Chip Seal Surface Treatment and ditch regrading</i></p> <p>³ <i>Preliminary design to include recommendation for property acquisition if required.</i></p>								