



1002-2016 ADDENDUM 3

DESIGN AND INSTALLATION OF NEW LED VIDEO DISPLAY BOARD – PAN AM INDOOR POOL – 25 POSEIDON BAY

URGENT

**PLEASE FORWARD THIS DOCUMENT TO
WHOEVER IS IN POSSESSION OF THE BID
OPPORTUNITY**

ISSUED: December 8, 2016
BY: Lou Chubenko
TELEPHONE NO. 204 986-2727

**THIS ADDENDUM SHALL BE INCORPORATED
INTO THE BID OPPORTUNITY AND SHALL
FORM A PART OF THE CONTRACT
DOCUMENTS**

Template Version: A20160708

Please note the following and attached changes, corrections, additions, deletions, information and/or instructions in connection with the Bid Opportunity, and be governed accordingly. Failure to acknowledge receipt of this Addendum in Paragraph 8 of Form A: Bid may render your Bid non-responsive.

PART D – SUPPLEMENTAL CONDITIONS

Revise: D2.2 (e) to read: Dismantle, remove and dispose of existing LED video display board off site. Do not salvage existing display board.

Add: D12.6 The following dates are not available for Contractor to Work on site due to scheduled pool swimming events and programs:

- January 14, 15, 21-30
- February 10-12, 17-19, 25-26
- March 2-5, 11-12, 18-19, 28-30
- April 2, 7-9, 15, 23, 28-30
- May 11-14
- June 3-4, 6-11, 16-18, 23-25

PART E – SPECIFICATIONS

Section 10 14 00 Video Display System

Add: 1.1.7 No alterations are required to existing A/C or video display access area at the back of the board. The existing air handling unit is expected to be reused for this installation. If there is the requirement to modify the A/C or access area, there shall be a Change in Work as specified in the General Conditions for Construction C7 Changes in Work.

Revise: 1.2.1 to read: Existing Display Board – This section details the specifications of the removal and disposal of the existing LED scoreboard located in the competition pool at Pan Am Pool. This includes everything required to complete this removal.

Add: 1.10.1.1: The Contractor shall be responsible for structural modifications related to mounting and anchoring of the new video display board. If extraneous structural issues are encountered or discovered during the structural engineering review there shall be a Change in Work as specified in the General Conditions for Construction C7, Changes in Work, and costs shall be covered by the City of Winnipeg.

Add: 1.10.1.2: The existing power phase and amperage is shown on Construction Drawings AQ100 and AQ102 as 208V 3PH 50Amp.

- Add: 1.10.1.3: Construction Drawing AQ100 shows the requirement of a 4 strand fibre cable and how the cable is terminated and connected to the Timing Office rack and the video display.
- Add: 1.11.2(a) Refer to 1002-2016_Addendum_3-Preventative_Maintenance_Checklist.
- Revise: 2.1 to read: REMOVAL OF EXISTING SCOREBOARD – The Pan Am Pool currently houses – 1 LED Scoreboard located on the East Wall at the shallow end of the Competition Pool which must be dismantled, removed and dispose of from the site prior to the installation of a new Video Display.
- Add: 2.1.11 Limited interruption in the existing Weight Room during construction can occur but Contractor must provide specific dates and times to the Contract Administrator when Work would be undertaken.
- Revise: 2.2.1 to read: Base specified product for this project is a Video Display Board – Media Resources – Vision IQ Video Display – Model #P10-RGB-**672-416**.
- Revise: 3.0.7 to read: 2017 Canada Games – Provide technical support to City pool staff for four (4) days duration on site during the Canada Games from July 27 to July 30, 2017. Contractor shall provide a daily flat rate for this service. It would be expected the technical support be on site for the preliminaries in the morning and the finals in the evening.