

Part 1 General

1.1 REFERENCES

- .1 ASTM International Inc.
 - .1 ASTM C564-03a, Standard Specification for Rubber Gaskets for Cast Iron Soil Pipe and Fittings.
- .2 Canadian Standards Association (CSA International).
 - .1 CSA B67-1972(R1996), Lead Service Pipe, Waste Pipe, Traps, Bends and Accessories.
 - .2 CAN/CSA-B70-06, Cast Iron Soil Pipe, Fittings and Means of Joining.
 - .3 CAN/CSA-B125.3-05, Plumbing Fittings.
- .3 Green Seal Environmental Standards (GSES)
 - .1 Standard GS-36-00, Commercial Adhesives.
- .4 South Coast Air Quality Management District (SCAQMD), California State
 - .1 SCAQMD Rule 1168-A2005, Adhesive and Sealant Applications.

1.2 ACTION AND INFORMATIONAL SUBMITTALS

- .1 Provide submittals in accordance with Section 01 33 00 - Submittal Procedures.
- .2 Product Data:
 - .1 Provide manufacturer's printed product literature and datasheets for adhesives, and include product characteristics, performance criteria, physical size, finish and limitations.

1.3 DELIVERY, STORAGE AND HANDLING

- .1 Deliver materials to site in original factory packaging, labelled with manufacturer's name, address.

Part 2 Products

2.1 CAST IRON PIPING AND FITTINGS

- .1 Above ground sanitary and vent: to CAN/CSA-B70.
 - .1 Joints:
 - .1 Mechanical joints:
 - .1 Neoprene or butyl rubber compression gaskets with stainless steel clamps.

Part 3 Execution

3.1 APPLICATION

- .1 Manufacturer's Instructions: comply with manufacturer's written recommendations, including product technical bulletins, handling, storage and installation instructions, and datasheets.

3.2 INSTALLATION

- .1 Install in accordance with National Plumbing Code, Provincial Plumbing Code, and local authority having jurisdiction.

3.3 TESTING

- .1 Pressure test buried systems before backfilling.
- .2 Hydraulically test to verify grades and freedom from obstructions.

3.4 PERFORMANCE VERIFICATION

- .1 Cleanouts:
 - .1 Ensure accessible and that access doors are correctly located.
 - .2 Open, cover with linseed oil and re-seal.
 - .3 Verify that cleanout rods can probe as far as the next cleanout, at least.
- .2 Test to ensure traps are fully and permanently primed.
- .3 Storm water drainage:
 - .1 Verify domes are secure.
 - .2 Ensure weirs are correctly sized and installed correctly.
 - .3 Verify provisions for movement of roof system.
- .4 Ensure that fixtures are properly anchored, connected to system and effectively vented.
- .5 Affix applicable label (storm, sanitary, vent, pump discharge etc.) c/w directional arrows every floor or 4.5 m (whichever is less).

3.5 CLEANING

- .1 Clean in accordance with Section 01 74 11 - Cleaning.

END OF SECTION