



# 561-2016 ADDENDUM 1

## ARCHIBALD STREET AND WATT STREET RENEWALS INCLUDING ARCHIBALD UNDERPASS STRUCTURAL WORK

### **URGENT**

**PLEASE FORWARD THIS DOCUMENT TO WHOEVER IS IN POSSESSION OF THE BID OPPORTUNITY**

ISSUED: July 15, 2016  
BY: Dylan Mourant, C.E.T.  
TELEPHONE NO. 204 -478-8969

**THIS ADDENDUM SHALL BE INCORPORATED INTO THE BID OPPORTUNITY AND SHALL FORM A PART OF THE CONTRACT DOCUMENTS**

Template Version: A20150806

**Please note the following and attached changes, corrections, additions, deletions, information and/or instructions in connection with the Bid Opportunity, and be governed accordingly. Failure to acknowledge receipt of this Addendum in Paragraph 10 of Form A: Bid may render your Bid non-responsive.**

### **TABLE OF CONTENTS**

Add:	Part E - Specifications	Appendix 'A' – Manitoba Hydro
Add:	Part E - Specifications	Appendix 'B' – Safe Excavation
Add:	Part E - Specifications	Appendix 'C' – Elmwood Mission Gas Distribution
Add:	Part E - Specifications	Appendix 'D' – William Elmwood Gas Distribution
Add:	Part E - Specifications	Appendix 'E' – Geotechnical Report
Add:	Part E - Specifications	Appendix 'F' – Canadian Pacific Railway(CPR) Documents

### **PART A – BID SUBMISSION**

Replace: 561-2016\_Bid\_Submission with \_Addendum\_1-Bid\_Submission. The following is a summary of changes incorporated in the replacement Bid Submission:

Form B(R1): Numerous changes.

Page numbering on some forms may be changed as a result.

Replace: 561-2016\_Form\_B-Excel with 561-2016\_Addendum\_1-Form\_B-Excel.

### **PART B – BIDDING PROCEDURES**

Revise: B16.2 to read: Further to B16.1(a), the Award Authority may reject a Bid as being non-responsive if the Bid is incomplete, obscure or conditional, or contains additions, deletions, alterations or other irregularities. The Award Authority may reject all or any part of any Bid, or waive technical requirements or minor informalities or irregularities, if the interests of the City so require.

## **PART D – SUPPLEMENTAL CONDITIONS**

- Add: D14.4 The City intends to award this Contract by August 10, 2016.
- Add: D14.4.1 If the actual date of award is later than the intended date, the dates specified for Substantial Performance and Total Performance will be adjusted by the difference between the aforementioned intended and actual dates.
- Revise: D29.1 to read: Notwithstanding C13.2, the warranty period shall begin on the date of Total Performance and shall expire one (1) year thereafter for Mill and Fill, and Rehabilitation works, and two (2) years thereafter for all remaining works, including but not limited to retaining walls, parapet walls, active transportation connection path structural sidewalk, structural paths and structural road repairs in the underpass, unless extended pursuant to C13.2.1 or C13.2.2, in which case it shall expire when provided for thereunder.

## **PART E – SPECIFICATIONS**

- Revise: E10.2(a) The Work under this Specification shall include the removal and disposal of existing sidewalk, retaining walls, slope paving, traffic barriers complete with median slab footing, underpass retaining walls, road slabs and the MTS duct bank to the limits as shown on the Drawings or as otherwise directed by the Contract Administrator.
- Add: E10.8.2(a)(vii) Concrete Pavement
- Add: E11.6.2(a)(xiii) Drilled dowels and tie bars shall be installed in accordance with CW3230 using materials as indicated on the Drawings.
- Add: E11.10(a)(iv) Drilled 16X and 29X Bars
- Add: E13.5(a)(viii) Unreinforced sidewalks with retaining walls or curbs
- Add: E13.5(a)(ix) Unreinforced sidewalks
- Add: E13.12(a)(viii) 100 Thick Unreinforced Structural Sidewalks with Retaining Walls or Curbs
- Add: E13.12(a)(ix) 100 Thick Unreinforced Structural Sidewalks
- Add: E15.1(b) The Work to be done by the Contractor under this Specification shall include the furnishing of all superintendence, overhead, labour, materials, equipment, tools, supplies, and all other things necessary and or incidental to the satisfactory performance and completion of all the Work as herein after specified.
- Revise: E15.4(a) to read Hydro Excavation shall be measured on an hourly basis that the Hydro Excavation unit is onsite and paid for at the Contract Unit Price per hour for "Hydro Excavation", which price shall be payment in full for performing all operations herein described and all other items incidental to the Work included in this Specification and accepted by the Contract Administrator. The hours to be paid for will be the total number of hours of Hydro Excavation in accordance with this Specification, accepted and measured by the Contract Administrator.
- Add: E33 **CPR**
- Add: E33.1 Description
- Add: E33.1.1 The Work to be done by the Contractor under this Specification shall include the furnishing of all superintendence, overhead, labour, materials, equipment, tools, supplies, and all other things necessary or and incidental to the satisfactory performance and completion of all the Work as herein after specified.
- Add: E33.2 Scope of Work

Add: E33.2.1 The Contractor is responsible to contract CPR and obtain all required permissions, clearances and/or safety watches to complete the Work. Jennifer Benedict, [Jennifer.Benedict@cpr.ca](mailto:Jennifer.Benedict@cpr.ca), may be the contact for CPR.

Add: E33.3 No measurement or payment will be made for this item of Work.

## **DRAWINGS**

Replace: 561-2016 \_Drawing\_U205-16-10(P-3478-10)-R0 with 561-2016 \_Addendum\_1-Drawing\_U205-16-10(P3478-10)-R1

Replace: 561-2016 \_Drawing\_U205-16-11(P-3478-11)-R0 with 561-2016 \_Addendum\_1-Drawing\_U205-16-11(P3478-11)-R1

Replace: 561-2016 \_Drawing\_U205-16-16(P-3478-16)-R0 with 561-2016 \_Addendum\_1-Drawing\_U205-16-16(P3478-16)-R1

Replace: 561-2016 \_Drawing\_U205-16-17-R0 with 561-2016 \_Addendum\_1-Drawing\_U205-16-17-R1

Replace: 561-2016 \_Drawing\_U205-16-20-R0 with 561-2016 \_Addendum\_1-Drawing\_U205-16-20-R1

Replace: 561-2016 \_Drawing\_U205-16-21-R0 with 561-2016 \_Addendum\_1-Drawing\_U205-16-21-R1

Replace: 561-2016 \_Drawing\_U205-16-23-R0 with 561-2016 \_Addendum\_1-Drawing\_U205-16-23-R1

Replace: 561-2016 \_Drawing\_U205-16-24-R0 with 561-2016 \_Addendum\_1-Drawing\_U205-16-24-R1

Replace: 561-2016 \_Drawing\_U205-16-26-R0 with 561-2016 \_Addendum\_1-Drawing\_U205-16-26-R1

Replace: 561-2016 \_Drawing\_U205-16-27-R0 with 561-2016 \_Addendum\_1-Drawing\_U205-16-27-R1

Replace: 561-2016 \_Drawing\_U205-16-30-R0 with 561-2016 \_Addendum\_1-Drawing\_U205-16-30-R1

Replace: 561-2016 \_Drawing\_U205-16-31-R0 with 561-2016 \_Addendum\_1-Drawing\_U205-16-31-R1

Replace: 561-2016 \_Drawing\_U205-16-38-R0 with 561-2016 \_Addendum\_1-Drawing\_U205-16-38-R1

Replace: 561-2016 \_Drawing\_U205-16-39-R0 with 561-2016 \_Addendum\_1-Drawing\_U205-16-39-R1

Replace: 561-2016 \_Drawing\_U205-16-40-R0 with 561-2016 \_Addendum\_1-Drawing\_U205-16-40-R1

Replace: 561-2016 \_Drawing\_U205-16-41-R0 with 561-2016 \_Addendum\_1-Drawing\_U205-16-41-R1

Replace: 561-2016 \_Drawing\_U205-16-42-R0 with 561-2016 \_Addendum\_1-Drawing\_U205-16-42-R1

Replace: 561-2016 \_Drawing\_U205-16-43-R0 with 561-2016 \_Addendum\_1-Drawing\_U205-16-43-R1

Replace: 561-2016 \_Drawing\_U205-16-45-R0 with 561-2016 \_Addendum\_1-Drawing\_U205-16-45-R1

Replace: 561-2016 \_Drawing\_U205-16-46-R0 with 561-2016 \_Addendum\_1-Drawing\_U205-16-46-R1

Replace: 561-2016 \_Drawing\_U205-16-47-R0 with 561-2016 \_Addendum\_1-Drawing\_U205-16-47-R1

Replace: 561-2016 \_Drawing\_U205-16-48-R0 with 561-2016 \_Addendum\_1-Drawing\_U205-16-48-R1

Replace: 561-2016 \_Drawing\_U205-16-49-R0 with 561-2016 \_Addendum\_1-Drawing\_U205-16-49-R1

Replace: 561-2016 \_Drawing\_U205-16-50-R0 with 561-2016 \_Addendum\_1-Drawing\_U205-16-50-R1

Replace: 561-2016 \_Drawing\_U205-16-53-R0 with 561-2016 \_Addendum\_1-Drawing\_U205-16-53-R1

Replace: 561-2016 \_Drawing\_U205-16-54-R0 with 561-2016 \_Addendum\_1-Drawing\_U205-16-54-R1

Replace: 561-2016 \_Drawing\_U205-16-55-R0 with 561-2016 \_Addendum\_1-Drawing\_U205-16-55-R1

Replace: 561-2016 \_Drawing\_U205-16-56-R0 with 561-2016 \_Addendum\_1-Drawing\_U205-16-56-R1

Replace: 561-2016 \_Drawing\_U205-16-57-R0 with 561-2016 \_Addendum\_1-Drawing\_U205-16-57-R1

Replace: 561-2016 \_Drawing\_U205-16-58-R0 with 561-2016 \_Addendum\_1-Drawing\_U205-16-58-R1

## **APPENDICES**

Add: Appendix F                      561-2016\_Appendix-F\_Canadian\_Pacific\_Railway(CPR)\_Documents