## NOTES:

WIRE AND RECONNECT TO EXISTING INITIATING CIRCUIT. PROVIDE FIRE ALARM VERIFICATION FOR AFFECTED

- 1. EXISTING WIRING TO BE CONCEALED BEHIND WALL/CEILING.
- 2. REPLACE ALL EXISTING RECEPTACLES TO TEMPER RESSISTANCE DECORA TYPE.
- 3. RELOCATE RECEPTACLES. EXTEND RE-ROUTE, RE WIRE AND RECONNECT TO EXISTING ON SITE. FINAL LOCATION TO BE COORDINATED ON SITE. REFER TO ARCHITECTURAL DRAWINGS FOR DETAILS.
- 4. REFER TO ARCHITECTURAL DRAWINGS FOR DOOR ACTUATOR LOCATION.
- 5. PROVIDE AND INSTALL SEPARATE EMERGENCY CALL ALARM AND SIGNAL DEVICES FOR BASEMENT AND MAIN FLOOR UNIVERSAL TOILET ROOM. MANUFACTURED BY FEDERAL SIGNAL, MODEL #USIS C/W BUILT-IN SOUNDER.
- FLOOR MOUNT RECEPTACLE TO BE RECESSED POKE THRU TYPE C/W TRIM AND COVER. FLOORBOXES TO ACCOMODATE 4 DUPLEX RECEPATCLES AND 4 DATA PORTS C/W ALL FACEPLATES. ACCEPTABLE MANUFACTURER: LEGRAND, FSR.
- 7. FLOOR MOUNT RECEPTACLE TO BE RECESSED POKE THRU TYPE C/W TRIM AND COVER. FLOORBOXES TO ACCOMODATE 2 DUPLEX RECEPATCLES AND 4 DATA PORTS C/W ALL FACEPLATES. ACCEPTABLE MANUFACTURER: LEGRAND, FSR.
- 8. WIRE AND CONNECT DOOR ACTUATOR AND ASSOCIATED PUSH BUTTONS. PROVIDE ALL REQUIRED CONDUIT, JUNCTION BOXES, WIRING, ETC. COORDINATE ALL WORK WITH DOOR HARDWARE SUPPLIER. CONFIRM FINAL LOCATION OF BUTTONS WITH ARCHITECTURAL



**APEGIN** Certificate of Authorization HDK Consulting Incorporated

No. 5539 Date: 04/30/2017



THE CITY OF WINNIPEG PLANNING, PROPERTY AND DEVELOPMENT DEPARTMENT MUNICIPAL ACCOMMODATIONS DIVISION 4TH FLOOR - 185 KING STREET R3B 1J1

Project: St. Vital Library

6 Fermor Ave. Winnipeg Manitoba Project Number: 16054
Bid Opportunity Number: 768-2016 Drawing Title:

NEW MAIN FLOOR POWER PLAN

# Issue/Revision Date ISSUED FOR CONSTRUCTION

ADDENDUM #1 OCT 31, 2016

Sheet No: E-11

This drawing is property of the Architect and cannot be reproduced or used without the consent of the Architect. The contractor is responsible for checking and verifying all levels and dimensions and shall report all discrepancies to the Architect and obtain clarification prior to commencing work.