



1017-2018 ADDENDUM 1

Empress Street Project, Pavement Reconstruction, Portage Avenue to St. Matthews Avenue, Empress Overpass Rehabilitation, Accessibility Ramps and Associated Works

ISSUED: February 22, 2018
BY: James Kennedy
TELEPHONE NO. 204-977-8370

URGENT

PLEASE FORWARD THIS DOCUMENT TO WHOEVER IS IN POSSESSION OF THE BID OPPORTUNITY

THIS ADDENDUM SHALL BE INCORPORATED INTO THE BID OPPORTUNITY AND SHALL FORM A PART OF THE CONTRACT DOCUMENTS

Template Version: A20160708

Please note the following and attached changes, corrections, additions, deletions, information and/or instructions in connection with the Bid Opportunity, and be governed accordingly. Failure to acknowledge receipt of this Addendum in Paragraph 10 of Form A: Bid may render your Bid non-responsive.

PART A – BID SUBMISSION

Replace: 1017-2018 Bid Submission with 1017-2018 Addendum 1 - Bid Submission. The following is a summary of changes incorporated in the replacement Bid Submission:

- Form B(R1): Added B.2 “Watermain Valve Chamber Inspections”
- Revised Quantities in Section C- Street Light Installation

PART D – SUPPLEMENTAL CONDITIONS

Revise: D2.5(a)(viii) to read: Construction of Portland Cement Concrete (PCC) and Portland Limestone Cement Concrete (PLCC) **230 mm** plain dowelled concrete pavement (utilizing slip form paving equipment wherever possible);

PART E – SPECIFICATIONS

Revise: E13.5.2 to read: Construction of Portland limestone cement concrete pavement will be paid for at the Contract Unit Price per square metre for the “Items of Work” listed below, measured as specified herein, which price shall be payment in full for supplying all materials and performing all operation herein described and all other items incidental to the work included in this Specification.

Items of Work

- (a) Construction of **230 mm** Portland Limestone Cement Concrete (Plain-Dowelled)
- (b) Construction of **230 mm** Portland Limestone Cement Concrete (Plain-Dowelled, Slip-formed)
- (c) Construction of 200 mm Portland Limestone Cement Concrete (Reinforced)

Revise: E13.6.2 to read: Construction of Portland limestone cement concrete pavement for early opening will be paid for at the Contract Unit Price per square metre for the “Items of Work” listed below, measured as specified herein, which price shall be payment in full for supplying all materials and performing all operation herein described and all other items incidental to the work included in this Specification.

Items of Work

- (a) Construction of **230 mm** Portland Limestone Cement Concrete for Early Opening 72 Hour (Plain-Dowelled)

- (b) Construction of 200 mm Portland Limestone Cement Concrete for Early Opening 72 Hour (Reinforced)

Revise: E16.4.1 to read: No measurement or payment will be made for the works listed in **E16.1.1, E16.1.2, E16.2.1, E16.2.2, and E16.3.**

Revise: E16.5 to read: Measurement for "Excavation and Backfill for Sewer Service Pipe Connections Near Feedermain" will be made on a unit basis and paid for at the Contract Unit Price for the items of Work listed in **E16.2.3.** Number of units to be paid for will be the total number of excavations, connections to the combined sewer compacted bedding and backfill completed in accordance with Specification **E16.2.3** accepted and measured by the Contract Administrator. Installation of the catch basin lead, catch basin lead vertical riser, and fittings will be measured and paid as per CW 2130.

Add **E18. Watermain Valve Chamber Inspection**

DESCRIPTION

E18.1 This Specification shall cover the inspection of watermain valve chambers prior to the start of construction to determine whether or not additional work is required to repair them.

E18.2 This Specification shall supplement CW 2145-R4.

CONSTRUCTION METHODS

E18.3 Watermain Valve Chamber Inspection

E18.3.1 Watermain valve chamber inspections shall be completed in accordance with "Manhole Inspections" as described in Section 3 of CW 2145-R4.

E18.3.2 Watermain valve chamber inspections shall be completed as soon as possible after Award such that the Contract Administrator can determine if additional Work is required.

MEASUREMENT AND PAYMENT

E18.4 Watermain Valve Chamber Inspection

E18.4.1 Watermain valve chamber inspections will be measured on a unit basis and paid for at the Contract Unit Price for "Watermain Valve Chamber Inspections". The number of units to be paid for will be the total number of chambers inspected in accordance with this Specification, accepted and measured by the Contract Administrator.

E18.4.2 De-watering of the chamber, if required, will not be measured and payment shall be included in the price paid for "Watermain Valve Chamber Inspections".

E18.4.3 Payment will not be made until the required report submissions are accepted by the Contract Administrator.

E18.4.4 Payments will not be made for inspections re-performed where the Contract Administrator has determined the requirements of the specification have not been satisfied.

DRAWINGS

Add: 1017-2018_Addendum_1-Drawing_1-04707-DE-50000-0449-R1