

731-2018 ADDENDUM 1

SEVEN OAKS ARBORETEM WATER SERVICE INSTALLATION

ISSUED: September 10, 2018 BY: Steven Repa TELEPHONE NO. 204 451-2723

URGENT

PLEASE FORWARD THIS DOCUMENT TO WHOEVER IS IN POSSESSION OF THE BID OPPORTUNITY

THIS ADDENDUM SHALL BE INCORPORATED INTO THE BID OPPORTUNITY AND SHALL FORM A PART OF THE CONTRACT DOCUMENTS

Please note the following and attached changes, corrections, additions, deletions, information and/or instructions in connection with the Bid Opportunity, and be governed accordingly. Failure to acknowledge receipt of this Addendum in Paragraph 8 of Form A: Bid may render your Bid non-responsive.

PART D - SUPPLEMENTAL CONDITIONS

Revise: D2.1 to read: The Work to be done under the Contract shall consist of installing a new 19 mm water

service with a hose bibb and connection box including a C.S.P. enclosure for the water meter and backflow preventer (City of Winnipeg to Supply and Install Water Meter).

Revise: D2.2 (a) to read: Install dual check backflow preventer and C.S.P. enclosure as per SD-241B (City of

Winnipeg to Supply and Install Water Meter)

Revise: D2.2 (c) to read: Install a new 19 mm water service and tie into existing 250 mm water main.

Replace: D14.1 with: The Contractor shall achieve Substantial Performance by May 25, 2019.

Replace: D15.1 with: The Contractor shall achieve Total Performance by June 1, 2019.

PART E - SPECIFICATIONS

Revise: E1.3 to read: The following are applicable to the Work:

<u>Drawing No.</u> <u>Drawing Name/Title</u>

C-101-R1 Site Servicing Plan and Detail

SD-241B-R1 Typical Double Check Valve Assembly and Meter in C.S.P. Enclosure

Revise: E11.5.7 (a) to read: "Supply and Install 19mm Water Service" will be measured on a linear meter basis. The

work to be paid for shall be the total number of linear meters installed in accordance with

this Specification and as measured in the field, and accepted by the Contract

Administrator.