5.0 GROUND PENETRATING RADAR SURVEY

KGS Group performed a Geophysical Survey using Ground Penetrating Radar (GPR) at 61 Princess Street on February 3rd, 2016 in order to help identify any buried objects or anomalies, such as potential underground storage tanks (USTs). Possible UST locations as identified in the Phase I ESA interviews included the northwest and southwest corners of the parking lot which were likely associated with a former service station on site.

5.1 SITE CONDITIONS AND FIELD OBSERVATIONS

Jonathan McInnis of KGS Group completed the GPR survey on February 3rd, 2016. The weather condition for the survey consisted of a temperature of -19°C cloudy and snowing. The City of Winnipeg parking lot surveyed was approximately 65 metres long by 22 metres wide. The surface of the parking lot was snow packed with no vehicles present at the time. The snow cover on the parking surface had no interference with the GPR Survey results.

5.2 RESULTS AND INTERPRETATION

The GPR survey data collected identified a number of areas on the subject property with buried object and anomalies including two potential UST locations, old building foundations, an underground pipe and scattered unknown anomalies throughout the site. The areas are described below with the locations identified on Figure 3. Figures 3A to 3E display the GPR log data (hyperbolas) of the specific transect lines which correspond to the identified areas of buried objects and anomalies in the areas of interest (A, B, C and D).

Areas A and B - Potential USTs

Two possible UST locations were identified on site. The two potential UST locations are labeled Area A and Area B in Figure 3 (yellow). The areas are situated in the northwest corner of the site near Princess Street. The potential UST (Area A) closest to Princess Street is approximately 0.8 to 1.0 metres below grade and approximately 2 metres wide as displayed in Figure 3A. The second potential UST (Area B) is located northeast of the first UST (Area A) and is approximately 0.4 to 0.5 metres below grade and 1.5 metres wide as displayed in Figure 3B.



Due to the dimensions of these targets, there is strong indication that these buried objects may be USTs.

Areas C and D - Possible Building Foundations

The completion of the GPR survey identified at least two old building footprints labeled Area C in Figure 3 (yellow). The foundations of the two old buildings were identified at approximately 0.5 metres below grade. The GPR logs of transect lines in this area display a distinct edge of the foundations with rubble inside it and the footprint of the foundations are continuous (Figures 3D and 3E). The locations of these two foundations roughly correspond to the historical buildings identified in the 1950 aerial photograph (Appendix B). A third potential building foundation was identified east of these two foundations displayed in Figure 3 and labeled as Area D. No distinct foundation footprint was identified, but a hard surface at 0.5 metres below grade was visible in the GPR log for the transect line in this area with rubble below it (Figure 3C). The close proximity of this area to the foundation footprints (Area C) indicates that it may a possible third foundation, or remnants from the adjacent foundations or former buildings on site.

Area E - Underground Pipe

At a depth of approximately 0.5 metres, a Manitoba Hydro underground pipe labeled Area E in Figure 3 (yellow) was identified in the middle of the site entering into the southern building. This pipe is identifiable from its distinct target shape and hyperbolas displayed in the GPR log data.

Area F - Anomalies

A number of unknown anomalies were identified across the site and are labeled as Area F in Figure 3 (brown color). These anomalies shown in the figure do not resemble buried tanks, but are most likely buried concrete, rubble or boulders.







Monitoring Well (KGS Group)


Historic 1950 Building Foundation

1950 Building Footprint (Image)

Property Lines (Approximate)

GPR Anomalies "F"

- specified. Transverse Mercator Projection, NAD 1983, Zone 14. Elevations are in metres above sea level (MSL).



REVISIONS / ISSUE




COMBINED PHASE I/II ENVIRONMENT SITE ASSESSMENT (ESA) 61 PRINCESS STREET, WINNIPEG, MB

NOT TO BE USED FOR CONSTRUCTION

JULY 2016

FIGURE 03 0




MSW BMH
ISSUED CHECK
BY BY 0 16/07/04 ISSUED FOR FINAL REPORT NO. YY/MM/DD Winnipeg GROUP CONSULTING ENGINEERS COMBINED PHASE I/II ENVIRONMENT SITE ASSESSMENT (ESA) 61 PRINCESS STREET, WINNIPEG, MB

GPR TRANSECT 38

JULY 2016

FIGURE 03A 0

PRELIMINARY NOT TO BE USED FOR CONSTRUCTION




0 16/07/04 ISSUED FOR FINAL REPORT NO. YY/MM/DD Winnipèg CONSULTING ENGINEERS COMBINED PHASE I/II ENVIRONMENT SITE ASSESSMENT (ESA) 61 PRINCESS STREET, WINNIPEG, MB

GPR TRANSECT 57

JULY 2016

FIGURE 03B 0


PRELIMINARY NOT TO BE USED FOR CONSTRUCTION



PRELIMINARY NOT TO BE USED FOR CONSTRUCTION

JULY 2016

FIGURE 03C 0




PRELIMINARY NOT TO BE USED FOR CONSTRUCTION

GPR TRANSECT 67

JULY 2016

FIGURE 03D 0

MSW BMH



MSW BMH
ISSUED CHECK
BY BY 0 16/07/04 ISSUED FOR FINAL REPORT NO. YY/MM/DD Winnipèg GROUP CONSULTING ENGINEERS COMBINED PHASE I/II ENVIRONMENT SITE ASSESSMENT (ESA) 61 PRINCESS STREET, WINNIPEG, MB

GPR TRANSECT 50

JULY 2016

FIGURE 03E 0

PRELIMINARY NOT TO BE USED FOR CONSTRUCTION









