



252-2019 ADDENDUM 2

ST. BONIFACE INDUSTRIAL PARK PHASE 2 – STAGE 5

URGENT

PLEASE FORWARD THIS DOCUMENT TO WHOEVER IS IN POSSESSION OF THE BID OPPORTUNITY

ISSUED: March 18, 2019
BY: Paul Sunderland, P.Eng.
TELEPHONE NO. 204 489-5900

THIS ADDENDUM SHALL BE INCORPORATED INTO THE TENDER AND SHALL FORM A PART OF THE CONTRACT DOCUMENTS

Template Version: A20160708

Please note the following and attached changes, corrections, additions, deletions, information and/or instructions in connection with the Tender, and be governed accordingly. Failure to acknowledge receipt of this Addendum in Paragraph 10 of Form A: Bid may render your Bid non-responsive.

PART A – BID SUBMISSION

Replace: 252-2019 Bid Submission with 252-2019 Addendum 2 – Bid Submission. The following is a summary of changes incorporated in the replacement Bid Submission:

Form B(R1): **Add F.25 “Removal Off-Site of Top Layer of Organic Clay Material from within Parcel A”**

PART E – SPECIFICATIONS

This addendum is being issued for the following purposes:

1. Clarification of vegetation removal off-site as per E15
2. Addition of E17 addressing the removal off-site of topsoil/organic clay material from within Parcel A.

Revise: **E15** to read: **CLEARING AND GRUBBING**

Revise: E15.2 (a) to read: Clearing and grubbing to be done in accordance with CW 3010. The Contractor is to clear off-site all trees, brush, shrubbery, vegetation, grasses, bulrushes, reeds, roots and other surface litter from within the boundaries marked on the Tree Clearing Plan to the satisfaction of the Contract Administrator. No fill material can be placed in an area until the area has been cleared as per E15 and E17 to the satisfaction of the Contract Administrator.

Revise: E15.3 (a) to read: Measurement of this item shall be the lump sum amount for all trees, brush, shrubbery, vegetation, grasses, bulrushes, reeds, roots and other surface litter removed off-site as per this specification.

Add: **E17 REMOVAL OFFSITE OF ORGANIC CLAY MATERIAL FROM WITHIN PARCEL A**

E17.1 Description

- (a) This specification shall cover the removal off-site of the top layer of organic clay material from within the area of land referred to as Parcel A.
- (b) Parcel A is 15.393 hectares in area and is bounded:

- i. On the West by the St. Boniface Industrial Park Phase 2 development boundary,
- ii. On the South by the Black Diamond Boulevard right-of-way
- iii. On the East by the west limit of Parcel B, and
- iv. On the North by the south limit of the GWWD Aqueduct and Railway right-of-way

E17.2 Construction Methods

- (a) Following the completion of clearing and grubbing as per E15 of this specification, the Contractor must remove off-site all quantity of the top layer of organic clay material from within Parcel A to the satisfaction of the Contract Administrator. The entirety of Parcel A has previously been stripped of topsoil, however through consulting the Geotechnical Report in Appendix A and because of the presence of vegetation and long grasses over the majority of Parcel A, there is expected to be a consistent amount of topsoil and organic material (ranging from 0 mm to 75 mm) throughout Parcel A.

E17.3 Method of Measurement

- (a) Measurement of this item shall be the area in square metres of Parcel A.

E17.4 Basis of Payment

- (a) This item shall be paid for at the Contract Unit Price per square metre for "Removal Off-Site of Top Layer of Organic Clay Material from within Parcel A".