

4-2019 ADDENDUM 2

2019 REGIONAL STREET RENEWAL – ROBLIN BOULEVARD FROM SHAFTESBURY BOULEVARD TO ASSINIBOINE PARK DRIVE AND ASSINIBOINE PARK DRIVE FROM COMMISSARY ROAD TO ZOO DRIVE – RECONSTRUCTION AND ASSOCIATED WORKS

ISSUED: April 3, 2019
BY: Richard Weibel
TELEPHONE NO. 204 986-4112

URGENT

**PLEASE FORWARD THIS DOCUMENT TO
WHOEVER IS IN POSSESSION OF THE BID
OPPORTUNITY**

**THIS ADDENDUM SHALL BE INCORPORATED
INTO THE BID OPPORTUNITY AND SHALL
FORM A PART OF THE CONTRACT
DOCUMENTS**

Template Version: A20160708

Please note the following and attached changes, corrections, additions, deletions, information and/or instructions in connection with the Bid Opportunity, and be governed accordingly. Failure to acknowledge receipt of this Addendum in Paragraph 10 of Form A: Bid may render your Bid non-responsive.

PART B – BIDDING PROCEDURES

- Revise: B2.1 to read: The Submission Deadline is 12:00 noon Winnipeg time, **April 11, 2019**.
- Add: B9.5 Form B: Prices is organized into Parts: Part A of the Work and Part B of the Work. Bidders shall provide a total price for each Part and, on the summary sheet, a Total Bid Price consisting of the sum of prices for Part A and Part B.
- Add: B17.2.1 Any bid with an apparent imbalance between the unit prices in Part A and Part B may be determined to be non-responsive and rejected by the Award Authority in its sole discretion, acting reasonably.
- Add: B18.5 As noted in D2 and identified in Form B: Prices, the Work of Part B will be contingent upon Council approval of Assiniboine Park Drive, as a Local Street Renewal Project. If Assiniboine Park Drive, as a Local Street Renewal Project does not get approved by Council, the City will have no obligation to award all or any portion of Part B of the Contract.
- Add: B18.6 The City may, at its discretion, award the Contract in parts.

PART D – SUPPLEMENTAL CONDITIONS

- Revise: **D2** to read: **SCOPE OF WORK**
- D2.1 The Work to be done under the Contract shall consist of two parts:
- (a) Part A – City Funded Work – Roblin Boulevard Westbound from Shaftesbury Boulevard to Assiniboine Park Drive
 - (b) Part B – City Funded Work - Assiniboine Park Drive from Commissary Road to Zoo Drive

Part A – City Funded Work – Roblin Boulevard Westbound

- D2.2 Part A – City Funded Work Roblin Boulevard Westbound shall consist of:
- (a) Concrete Reconstruction and Associated Works
 - (i) Planing of existing asphalt and at intersections as required;
 - (ii) Removal of existing pavement;

- (iii) Removal of existing temporary asphalt cross-overs in median boulevard;
- (iv) Removal of existing curb, splash strip, bullnose and sidewalk;
- (v) Abandon existing catch basins;
- (vi) Abandon existing drainage inlets;
- (vii) Abandon existing spillways;
- (viii) Installation of catch basins and sewer service pipe;
- (ix) Installation of subdrains;
- (x) Relocation of electrical works for Outfront Media Bus Stop Shelter;
- (xi) Excavation;
- (xii) Stockpile suitable in-situ material as required;
- (xiii) Placement of suitable in-situ material as required;
- (xiv) Compaction of existing sub-grade;
- (xv) Adjustment of existing pavement and boulevard structures;
- (xvi) Placement of geotextile fabric;
- (xvii) Placement of sub-base material;
- (xviii) Placement of base course material;
- (xix) Construction of 230mm concrete pavement(plain-dowelled) and integral 180mm barrier curb utilizing slip form paving equipment;
- (xx) Construction of 230mm concrete pavement(plain-dowelled);
- (xxi) Construction of 200mm concrete pavement(reinforced);
- (xxii) Installation of curb inlet frames;
- (xxiii) Construction of reinforced concrete spillways with riprap;
- (xxiv) Construction of separate concrete splash strip with thickened edge;
- (xxv) Construction of monolithic concrete splash strip utilizing slip form paving equipment;
- (xxvi) Construction of barrier curb utilizing slip form paving equipment;
- (xxvii) Construction of safety curb and safety median;
- (xxviii) Construction of monolithic concrete bullnose;
- (xxix) Construction of concrete median slab and monolithic concrete median slab;
- (xxx) Construction of concrete sidewalk;
- (xxxi) Construction of OutFront Media Bus Shelter pad;
- (xxxii) Renewal of existing curbs as required;
- (xxxiii) Renewal of existing curb and gutter as required;
- (xxxiv) Renewal of existing sidewalks as required;
- (xxxv) Installation of detectable warning surface tiles;
- (xxxvi) Renewal of existing asphalt pathway as required;
- (xxxvii) Construction of asphalt overlay(average thickness 80mm);
- (xxxviii) Construction of asphalt pavement at approach tie-ins as required;
- (xxxix) Removal of existing culverts;
 - (xl) Installation of corrugated steel pipe culvert;
 - (xli) Installation of culvert end markers;
 - (xlii) Installation of ditch inlet grate;
 - (xliii) Construction of grouted stone riprap and random stone riprap;
 - (xliv) Ditching;
 - (xlv) Placement of limestone surface material;
 - (xlvi) Boulevard restoration, salt tolerant seed and sod.

Part B – City Funded Work – Assiniboine Park Drive

D2.3 Part B – City Funded Work Assiniboine Park Drive shall consist of:

- (a) Mill & Fill and Associated Works
 - (i) Planing of 25mm of existing asphalt pavement;
 - (ii) Construction of mountable curb and gutter;
 - (iii) Renewal of existing asphalt pathway as required;
 - (iv) Placement of asphalt overlay(100mm - Type 1A asphalt);
 - (v) Ditching as required;
 - (vi) Installation of corrugated steel pipe culvert;
 - (vii) Installation of culvert end markers;
 - (viii) Relocation of TeraSpan conduit as required;
 - (ix) Placement of limestone surface material;
 - (x) Boulevard restoration and sod.
- (b) Asphalt Reconstruction and Associated Works
 - (i) Removal of existing asphalt pavement;
 - (ii) Relocation of TeraSpan conduit as required;
 - (iii) Excavation;
 - (iv) Compaction of existing sub-grade;
 - (v) Adjustment of existing pavement and boulevard structures;
 - (vi) Placement of geotextile fabric;
 - (vii) Placement of sub-base material;
 - (viii) Placement of base course material;
 - (ix) Construction of mountable curb and gutter;
 - (x) Renewal of barrier curb and curb ramp;
 - (xi) Installation of curb inlet frame;
 - (xii) Regrading of existing interlocking paving stones;
 - (xiii) Renewal of existing asphalt pathway as required;
 - (xiv) Placement of asphalt pavement(100mm - Type 1A asphalt);
 - (xv) Placement of asphalt pavement at tie-ins as required;
 - (xvi) Ditching as required;
 - (xvii) Installation of corrugated steel pipe culverts;
 - (xviii) Installation of culvert end markers;
 - (xix) Placement of limestone surface material;
 - (xx) Boulevard restoration and sod.

D2.4 Further to B18.5, Council has not approved Assiniboine Park Drive (Part B) as a local street renewal. It is anticipated that the approval will be received by May 2, 2019.

D2.4.1 If Council approval of Part B is not received, the City reserves the right to not award Part B in its entirety or any portion of Part B.

Revise: D10.1 (b) to read: Automobile liability insurance covering all motor vehicles, owned and operated and used or to be used by the Contractor directly or indirectly in the performance of the Work. The limit of liability shall not be less than **\$5,000,000** inclusive for loss or damage including personal injuries and death resulting from any one accident or occurrence;

Add: D13.5 If, prior to submitting the Detailed Work Schedule, the Contractor does not receive notification pursuant to D14.5 that all or some portion of Part B of the Work may be

commenced, he/she shall complete the Detailed Work Schedule for only Part A of the Work. The time periods stipulated in D20 for Substantial Performance of the Work and in D21 for Total Performance of the Work will be reduced proportionally by zero (0) Working Days by the Contract Administrator acting reasonably.

Add: D13.6

If, after submitting the Detailed Work Schedule, the Contractor receives notification that all or any portion of Part B of the Work may be commenced, the Contractor shall submit a revised Detailed Work Schedule no later than two (2) Business Days from receipt of the notification.

Revise: D14.4 to read:

The City intends to award this Contract by **May 3, 2019**.

Add: D14.5

The Contractor shall not commence Part B of the Work as described in D2 and identified in Form B: Prices, unless Council approves Assiniboine Park Drive for the Work of Part B, until the Contractor is in receipt of a letter of intent from the Award Authority authorizing the commencement of the Work of Part B.