



61-2019 ADDENDUM 1

ASBETOS ABATEMENT, NEW SPRINKLER SYSTEM AND MECHANICAL UPGRADES AT 510 MAIN STREET

URGENT

PLEASE FORWARD THIS DOCUMENT TO WHOEVER IS IN POSSESSION OF THE TENDER

ISSUED: February 12, 2019
BY: Dennis Flores
TELEPHONE NO. 204 986-7046

THIS ADDENDUM SHALL BE INCORPORATED INTO THE TENDER AND SHALL FORM A PART OF THE CONTRACT DOCUMENTS

Template Version: A20190115

Please note the following and attached changes, corrections, additions, deletions, information and/or instructions in connection with the Tender, and be governed accordingly. Failure to acknowledge receipt of this Addendum in Paragraph 8 of Form A: Bid may render your Bid non-responsive.

PART D – SUPPLEMENTAL CONDITIONS

- | | | |
|------|----------|---|
| Add: | D2.2 (f) | There must be no relocation of any of the print shop equipment. |
| Add: | D2.2 (g) | The print shop equipment is to remain operational during construction. The Contractor shall maintain humidity levels and ensure equipment operability within a dust free environment under a platform certified by a structural engineer. |
| Add: | D2.2 (h) | The equipment shall be assessed by the City of Winnipeg and Contractor before commencement and after construction to ensure functionality. |
| Add: | D2.2 (i) | The Contractor shall ensure interior cementitious spray fire proofing is applied, where existing was removed due to asbestos abatement. Inject blue pigment into fire proofing as per City of Winnipeg Standards. |