



685-2019 ADDENDUM 4

2019 BRIDGE MAINTENANCE NORWOOD AND MAIN STREET BRIDGES

URGENT

PLEASE FORWARD THIS DOCUMENT TO WHOEVER IS IN POSSESSION OF THE TENDER

ISSUED: September 17, 2019
BY: Bill Ebenspanger
TELEPHONE NO. 204 9778370

THIS ADDENDUM SHALL BE INCORPORATED INTO THE TENDER AND SHALL FORM A PART OF THE CONTRACT DOCUMENTS

Template Version: A20190115

Please note the following and attached changes, corrections, additions, deletions, information and/or instructions in connection with the Tender, and be governed accordingly. Failure to acknowledge receipt of this Addendum in Paragraph 10 of Form A: Bid may render your Bid non-responsive.

PART E – SPECIFICATIONS

- Add: E5.3(b) The Contractor shall submit drawings sealed by a Professional Engineer registered in the Province of Manitoba detailing the Contractor's proposed scaffolding, platforms, and swingstages to be employed. All scaffolding, platforms, and swingstages shall be designed, constructed, erected and operated in accordance with Workplace Safety and Health Division requirements. No Works shall commence without prior written approval of the Contract Administrator.
- Add: E6.3.3(c) The Contractor shall submit drawings sealed by a Professional Engineer registered in the Province of Manitoba detailing the Contractor's proposed scaffolding, platforms, and swingstages to be employed. All scaffolding, platforms, and swingstages shall be designed, constructed, erected and operated in accordance with Workplace Safety and Health Division requirements. No Works shall commence without prior written approval of the Contract Administrator.
- Revise: E7.5.9(a)(iii) to read: Remove all existing copper metallizing coating by grinding, chipping prying, abrasive blasting, or other means as approved by the Contract Administrator. Where the existing copper metallizing is fully intact, it is a minimum thickness of 120 mils.
- Revise: E7.5.17(e) to read: The personnel managing the QC Program shall provide evidence of successful inspection of three (3) projects of similar or greater complexity and scope completed in the last two (2) years. References shall include the name, address, and telephone number of a contact person employed by the facility owner.
- Revise: E10.6.3(a) to read: Supply and fabricate new HSS section, new connection plates and new keys. Welding shall conform to the requirements of CSA W59 Welded Steel Construction.
- Revise: E10.6.4(b) to read: Connect all steel to wooden slats using new galvanized lag bolts.
- Revise: E10.6.4(d) to read: Connect refurbished bench to limestone and HSS section with galvanized threaded anchor rods, washers, nuts and Drop-In threads anchors.

DRAWINGS

Replace: 685-2019_Drawing_B103-19-02_B104-19-02-Sht02-R0 with

685-2019_Addendum_4_Drawing_B103-19-02_B104-19-02-Sht02-R1

Replace: 685-2019_Drawing_B103-19-09-Sht09-R0 with 685-2019_Addendum_4_Drawing_B103-19-09-Sht09-R1