



771-2019 ADDENDUM 1

CITY OF WINNIPEG, 2018 PARKING AND STREET ENHANCEMENTS PROGRAM

URGENT

PLEASE FORWARD THIS DOCUMENT TO WHOEVER IS IN POSSESSION OF THE TENDER

ISSUED: August 14, 2019
BY: Thomas Findlay, P. Eng.
TELEPHONE NO. 204 928-8438

THIS ADDENDUM SHALL BE INCORPORATED INTO THE TENDER AND SHALL FORM A PART OF THE CONTRACT DOCUMENTS

Template Version: A20160708

Please note the following and attached changes, corrections, additions, deletions, information and/or instructions in connection with the Tender, and be governed accordingly. Failure to acknowledge receipt of this Addendum in Paragraph 10 of Form A: Bid may render your Bid non-responsive.

PART A – BID SUBMISSION

Replace: 771-2019 Bid Submission with 771-2019 Addendum 1 - Bid Submission. The following is a summary of changes incorporated in the replacement Bid Submission:

Form B(R1): Revised Items: A.7(i), A.11, A.17, A.18(i), A.19(i), A.20, A.21, A.22, A.23(ii), B.12(i) and B17(i) and (ii).

PART B – BIDDING PROCEDURES

Revise: B2.1 to read: The Submission Deadline is 12:00 noon Winnipeg time, August 20, 2019.

PART E – SPECIFICATIONS

Add:	MATERIALS
E27.9	Poly Posts
E27.9.1	The poly posts shall be picked up from the City of Winnipeg Yard and brought to site for installation.
Add:	E27.7.1 (h) Installation of poly posts to be in accordance with manufacturer’s instructions and placed on each precast curb or less as per the direction of the Contract Administrator.
Add:	E29 TRAFFIC SIGNALS INSTALLATIONS TEMPORARY SIDEWALK
	DESCRIPTION
E29.1	General
E29.1.1	This specification covers the placement and maintenance of temporary asphalt sidewalk around locations requiring Traffic Signals Installation’s in accordance with CW 3410.
E29.1.2	Once Traffic Signals has completed their work the Contractor is to remove the temporary sidewalk and place permanent 100mm concrete sidewalk and paving stone bands. Permanent Concrete sidewalk to be placed in accordance with CW 3325.
E29.1.3	The estimated area of Temporary Sidewalk required is less than 20 m ² .

CONSTRUCTION METHODS

- E29.2 Temporary Asphalt Sidewalk
- E29.2.1 The Contractor shall place and maintain the temporary asphalt sidewalk around the locations requiring Traffic Signals Installation's.
- E29.2.2 It is the Contractor's responsibility to maintain the sidewalk for the duration of the time required for Signals to complete their work, estimated 2-9 months.
- E29.3 Permanent Concrete Sidewalk
- E29.3.1 Once Traffic Signals has completed their work the Contractor shall remove the temporary sidewalk, place compacted base course and construct 100 mm concrete sidewalk in accordance with CW 3325.

MEASUREMENT AND PAYMENT

- E29.4 Temporary Asphalt Sidewalk
- E29.4.1 Temporary Asphalt Sidewalk will be measured on a unit basis and paid for at the Contract Unit Price for per tonne placed to construct and maintain the sidewalk at the "Contract Unit Price for Construction of Asphaltic Concrete Overlay i) Tie-ins and Approaches ", listed here below, which price shall be payment in full for supplying all materials and for completing all operations herein described and all other items incidental to the work included in this Specification, CW 3410, and accepted and measured by the Contract Administrator.
- E29.5 Permanent Concrete Sidewalk
- E29.5.1 Permanent Concrete Sidewalk will be measured on a unit basis and paid for at the Contract Unit Price for per square meter placed to construct the sidewalk at the "Contract Unit Price for Miscellaneous Concrete Slab Installation i) 100 mm Sidewalk", listed here below, which price shall be payment in full for supplying all materials and for completing all operations herein described and all other items incidental to the work included in this Specification, CW 3410, and accepted and measured by the Contract Administrator.

DRAWINGS

Replace: 771-2019 _Drawing_CT-03-R0 with 771-2019 _Addendum_1 Drawing_CT-03-RA