



88-2019 ADDENDUM 1

SUPPLY AND INSTALLATION OF FURNITURE AT 500 SALTER STREET

URGENT

PLEASE FORWARD THIS DOCUMENT TO WHOEVER IS IN POSSESSION OF THE BID OPPORTUNITY

ISSUED: March 20, 2019
BY: Jennifer Wlwchar-Fast
TELEPHONE NO. 204 986-8642

THIS ADDENDUM SHALL BE INCORPORATED INTO THE BID OPPORTUNITY AND SHALL FORM A PART OF THE CONTRACT DOCUMENTS

Template Version: A20160708

Please note the following and attached changes, corrections, additions, deletions, information and/or instructions in connection with the Bid Opportunity, and be governed accordingly. Failure to acknowledge receipt of this Addendum in Paragraph 8 of Form A: Bid may render your Bid non-responsive.

PART A – BID SUBMISSION

Replace: 88-2019 Bid Submission with 88-2019 Addendum 1- Bid Submission. The following is a summary of changes incorporated in the replacement Bid Submission:

- Form B(R1): Add Items No. 16 L-Book End, E2.4.1.
- Form B(R1): Delete in Section A, Item No.2 (LC-2) Lounge Modular Cellular Seating by OI
Add Section C- Item No.17 (LC-2) Lounge Modular Cellular Seating by OI
- Form B(R1): Revise in Section A, Item No. 13 (TC-1) Task Chair Teknion Projek E2.1.13, QTY: 1 , Revise to QTY: 3
- Form B(R1): Delete in Section A, Item No.8 (TB-3) Sit/Stand Workstation Steelcase Migration
Add Section D- Item No.18 (TB-3) Sit/Stand Workstation Steelcase Migration
- Form B(R1): Delete in Section A, Item No.13 (TC-1)Task Chair Teknion Projek
Add Section E- Item No.19 (TB-3) Task Chair Teknion Projek

Page numbering on some forms may be changed as a result.

PART E – SPECIFICATIONS

- Revise: E2.1.1(e)(i) to read: Fully upholstered seat and back, Grade/price group 2 vinyl, combination of two colours per each chair to be selected from manufacturer's full range, colours to be selected with Contract Administrator.
- Revise: E2.1.2 to read: Item No. 17 – Lounge Chair (LC-2)
- Revise: E2.1.8 to read: Item No. 18 – Sit Stand Table Electric Height Adjustable (TB-3) (LC-2)
- Revise: E2.1.13 to read: Item No. 19 – Office Chair Task (TC-1)

Revise: E2.4.(g)(v) to read: End panels to receive custom selected acrylic resin finish with sanded edge finish. Acrylic resin panels to be flush mounted c/w stand-off caps, 25mm (1" cap) w/17mm threaded rod, #3-15-0026-K and M8 Threaded Rod 20mm #3-15-1753 onto plastic laminate end panel. Acrylic selection to be 3-Form Varia Eco Resin ¼". Finish Sandstone F-001 both sides, Style Speckle Jest with sanded edges. To be located on each end panel for LS-1 and LS-2, 1" offset from edges, top and base. Mounted to end panel with caps and threaded rods to be quantity of 6 per LS-1 and 4 per LS-2 end panel.

DRAWINGS

Replace: 88-2019 _Drawing_A-1-R0 with 88-2019 _Addendum_1 Drawing_A-1-R1