



# 10-2020 ADDENDUM 2

## 2020 REGIONAL STREET RENEWAL PROGRAM- SARGENT AVENUE RECONSTRUCTION AND WATERMAIN RENEWAL, ERIN STREET TO ARLINGTON STREET

### **URGENT**

**PLEASE FORWARD THIS DOCUMENT TO  
WHOEVER IS IN POSSESSION OF THE  
TENDER**

ISSUED: March 11, 2020  
BY: James Kennedy  
TELEPHONE NO. 204 977-8370

**THIS ADDENDUM SHALL BE INCORPORATED  
INTO THE TENDER AND SHALL FORM A PART  
OF THE CONTRACT DOCUMENTS**

Template Version: A20190115

**Please note the following and attached changes, corrections, additions, deletions, information and/or instructions in connection with the Tender, and be governed accordingly. Failure to acknowledge receipt of this Addendum in Paragraph 10 of Form A: Bid may render your Bid non-responsive.**

### **PART A – BID SUBMISSION**

Replace: 10-2020-Addendum\_1-Form\_B-Excel with 10-2020-Addendum\_2-Form\_B-Excel. The following is a summary of changes incorporated in the replacement Form B:

Form B(R2): Added A.50 “Coordination of Construction with CP Rail”

Added E.15 “Supply and Install Warning Signs”. Item number E.15 thru E.20 adjusted to suit.

Page numbering may be changed as a result.

### **PART E – SPECIFICATIONS**

- Revise: E13.2(a): Trek Geotechnical has prepared a rail monitoring plan. This plan can be found within the geotechnical report included in Appendix ‘A’.
- Add: E13.2(b): Rail monitoring will be completed by Trek Geotechnical personnel. The Contractor will have no involvement in rail monitoring.
- Add: E13.4(c): The pipe exterior shall be protected with a bonded high density polyethylene jacket such as “Yellow Jacket” manufactured by Shaw Pipe Protection Ltd., or approved equal.
- Add: E13.6: Warning Signs
- Add: E13.6.1: Steel posts shall be 38 mm nominal diameter steel pipe and:
  - (i) Schedule 40 steel pipe conforming to the latest revision of CAN3-Z245.1.
  - (ii) O.D. = 48.3 mm
  - (iii) Wall thickness = 3.7 mm
  - (iv) Galvanized
- Add: E13.6.2: Warning Sign shall be:
  - (i) A fully reflectorized white sign with black letters as shown on the Drawings.
  - (ii) Retroreflective sheeting shall be Type VIII (ASTM D4956)

- (iii) Rounded corners but conforming to the nominal dimensions for height and width noted on the Drawings.
- (iv) Consistent with City of Winnipeg requirements for "Warning and Information Signs" outlined in Section 5.00 of the "Manual of Temporary Traffic Control in Work Areas on City Streets" 2019.

Add: E13.6.3: Supply and installation of warning signs, including steel posts, shall be measured on a unit basis and paid for at the Contract Unit Price for "Supply and Install Warning Signs". The number of units to be paid for will be the total number of signs and posts supplied and installed in accordance with this Specification, accepted and measured by the Contract Administrator.