

166-2020 ADDENDUM 2

CONSTRUCTION OF LDS SEWER SEPARATION – COCKBURN SEWER RELIEF (CONTRACT 10A)

URGENT

**PLEASE FORWARD THIS DOCUMENT TO
WHOEVER IS IN POSSESSION OF THE
TENDER**

ISSUED: April 14, 2020
BY: John Minkevich
TELEPHONE NO. 204 896-1209

**THIS ADDENDUM SHALL BE INCORPORATED
INTO THE TENDER AND SHALL FORM A PART
OF THE CONTRACT DOCUMENTS**

Template Version: A20190115

Please note the following and attached changes, corrections, additions, deletions, information and/or instructions in connection with the Tender, and be governed accordingly. Failure to acknowledge receipt of this Addendum in Paragraph 10 of Form A: Bid may render your Bid non-responsive.

PART A – BID SUBMISSION

Replace: 166-2020 eForm_B-Prices.xlsx with 166-2020 Addendum 2 eForm_B-Prices.xlsx. The following is a summary of changes incorporated in the replacement eForm_B-Prices:

Item numbering has been updated.

Revise: D2.5 (a) (i) to read: During construction of Contract 5B, temporary plugs were installed in the stub out connections on Stafford Street at the south limit of the 1350 mm laterals and on Wentworth Street at the north limit of the 2100 mm trunk. A manhole was installed at the north limit of the 1350 mm lateral on Stafford Street. The elevation of the water downstream of the connections will be maintained at 227.75 m and thus seepage from the 2100 mm trunk can be expected during construction that will need to be controlled by the Contract 10A Contractor.

Revise: D3.2 (c) to read: Regrading of existing sewer and water services (as required) to permit the installation of the new LDS sewers, manholes and associated construction shafts.

Revise: D14.10 to read: Dewatering and drainage during construction will be considered incidental to Site Development and Restoration unless otherwise indicated.

PART E – SPECIFICATIONS

Revise: E3.1 to read: The Contractor shall supply a separate Site trailer for exclusive use by the Contract Administrator as their field office facility.

Revise: E13.1 (c) to read: A temporary plug was installed in the south stub out pipe on Stafford Street as part of Contract 5B to facilitate the operation of the sewer following construction. The temporary plug will have to be removed to facilitate connections to the LDS Trunk.

Revise: E13.1 (d) to read: The Work required to facilitate the installation of the LDS on Stafford Street, as well as the ultimate connection of the existing Taylor LDS Trunk may result in the lowering of the water level within the Taylor LDS Trunk and SRB, **which is not permitted**.

Revise: E13.3.1 (a) to read: Temporary plugs or bulkheads will need to be installed in the stubouts at Stafford Street.

- Revise: E13.3.1 (a)(ii) to read: The location of the temporary plugs or bulkheads must not interfere with flow in the existing LDS system and should be located upstream of the Taylor Trunk at the intersection of Stafford Street and Taylor Avenue.
- Revise: E13.3.2 (b) to read: City water may be used to refill the system during construction. Sewer Dechlorination may be required prior to filling in accordance with the City of Winnipeg Sewer By-law No. 106/2018.
- Revise: E13.3.3 to read: Removal of temporary plugs or bulkheads and connection of LDS laterals to Taylor Avenue LDS Trunk
- (a) When construction of the LDS laterals on Stafford Street is complete and the connections are made, the temporary plugs or bulkheads will need to be removed.
 - (b) The temporary plugs or bulkheads shall not be removed until final inspection of the new piping has been complete and the Contractor has received authorization from the Contract Administrator.
 - (c) Prior to removing the temporary plugs or bulkheads, the LDS laterals shall be filled with water to avoid sudden drops of water in the SRB, and to facilitate the safe removal of the plug or bulkhead.
 - (i) The method of filling the Taylor Trunk with water shall be submitted to the Contract Administrator for review and approval.
 - (ii) Ground water will not be permitted for filling the system.
- Add: E13.3.3.4 Removal of Temporary Sewer Plugs
- (a) This refers to the removal of temporary sewer plugs that were installed as part of a previous Contract to facilitate the operation on the LDS. The Work required to complete will include the following:
 - (i) Excavate and remove temporary marker for reuse.
 - (ii) Excavate and support temporary plug.
 - (iii) Prior to removing the temporary plug, the LDS laterals shall be emptied to facilitate the safe removal of the plug.
 - (iv) Remove temporary plug to facilitate connection to existing LDS.
- Revise: E13.4 (a) to read: Maintaining Water Level in the LDS Trunk and SRB will be measured and paid at the Contract Lump Sum Price for "Install and Remove Temporary Plugs or Bulkheads", which price shall be payment in full for performing all operations herein described and all other items incidental to the Work included in this Specification.
- Revise: E13.4 (b) to read: This will be paid in accordance with the following:
- Revise: E13.4 (b) (i) to read: The cost will be paid out upon first installation of the temporary plugs or bulkheads required.
- Revise: E13.4 (b) (ii) to read: The payment may be prorated if the plug s or bulkheads are installed multiple times.
- Add: E13.4 (c): Removal of Temporary Sewer Plugs and markers shall be paid on a lump sum basis for each plug diameter listed on Form B Prices. The price shall include all Works and materials necessary to complete the installation as identified herein and as indicated on the Drawings.

DRAWINGS

Replace: 166-2020 _Drawing_LD-9650 with 166-2020 _Addendum_2 Drawing LD-9650_R1

Replace: 166-2020 _Drawing_LD-9651 with 166-2020 _Addendum_2 Drawing LD-9651_R1

Replace: 166-2020 _Drawing_LD-9652 with 166-2020 _Addendum_2 Drawing LD-9652_R1