



834-2020 ADDENDUM 1

2021 REGIONAL STREET RENEWAL PROGRAM – ARCHIBALD STREET PAVEMENT RECONSTRUCTION

URGENT

**PLEASE FORWARD THIS DOCUMENT TO
WHOEVER IS IN POSSESSION OF THE
BID/PROPOSAL**

ISSUED: February 5, 2021
BY: Ryan Cunningham, P.Eng.
TELEPHONE NO. 204 928-8377

**THIS ADDENDUM SHALL BE INCORPORATED
INTO THE BID/PROPOSAL AND SHALL FORM
A PART OF THE CONTRACT DOCUMENTS**

Template Version: A20190115

Please note the following and attached changes, corrections, additions, deletions, information and/or instructions in connection with the Bid/Proposal, and be governed accordingly. Failure to acknowledge receipt of this Addendum in Paragraph 10 of Form A: Bid/Proposal may render your Bid/Proposal non-responsive.

PART E – SPECIFICATIONS

- Revise: E13.4 to read: Excavate existing material to allow for the placement of 350 mm of 50 mm Granular C sub-base and 75 mm of Type IA asphalt pavement.
- Revise: E13.7 to read: Place and compact 350 mm of 50 mm Granular C sub-base and 75 mm of Type IA asphalt pavement. Provide 2% crossfall to the west gutter line along the west side temporary pavement widening and positive drainage as required for temporary asphalt pavement in medians.
- Revise: E14.2.2 to read: Where 100 mm sidewalk with block outs is constructed adjacent to the curb, install epoxy coated 10M deformed bars, 300 mm long and 600mm on centre in the curb during pouring. Epoxy coated 10M bars are to penetrate the curb 75 mm.

DRAWINGS

Replace: 834-2020_Drawing_CT-17_R0 with 834-2020_Addendum_1-Drawing_CT-17_R1.