



156-2021 ADDENDUM 2

ROOF REPLACEMENT CHARLESWOOD SENIOR CENTER 5006 ROBLIN BLVD

URGENT

PLEASE FORWARD THIS DOCUMENT TO WHOEVER IS IN POSSESSION OF THE BID/PROPOSAL

ISSUED: March 24, 2021
BY: David Firth
TELEPHONE NO. 204 451-4098

THIS ADDENDUM SHALL BE INCORPORATED INTO THE BID/PROPOSAL AND SHALL FORM A PART OF THE CONTRACT DOCUMENTS

Template Version: Add 2021-03-05

Please note the following and attached changes, corrections, additions, deletions, information and/or instructions in connection with the Bid/Proposal, and be governed accordingly. Failure to acknowledge receipt of this Addendum in Paragraph 10 of Form A: Bid/Proposal may render your Bid/Proposal non-responsive.

PART E – SPECIFICATIONS

Revise: E1.27.8 to read: Remove and discard all old non-used roof top equipment. Remove ducting to a level below the existing decking. Secure ducting below roof level with 18g strapping adhered to the existing decking and screwed to interior of abandoned ducting. Cap off all electrical. Install metal decking patch over old openings. Confirm any removals with the Contract Administrator

Delete: E1.27.4

Delete: E1.27.38

QUESTIONS AND ANSWERS

Q1: Will rooftop shut off panels be added to the RTU units on roofs A1 and A2 during this replacement?

A1: The addition of shut off panels is not being considered at this time.