



301-2021 ADDENDUM 3

MAYFAIR PARK EAST PLAYGROUND REDEVELOPMENT

URGENT

PLEASE FORWARD THIS DOCUMENT TO WHOEVER IS IN POSSESSION OF THE REQUEST FOR PROPOSAL

ISSUED: May 6, 2021
BY: Lindsay Lagman
TELEPHONE NO. 204 – 451-4185

THIS ADDENDUM SHALL BE INCORPORATED INTO THE REQUEST FOR PROPOSAL AND SHALL FORM A PART OF THE CONTRACT DOCUMENTS

Template Version: Ar20160708

Please note the following and attached changes, corrections, additions, deletions, information and/or instructions in connection with the Request for Proposal, and be governed accordingly. Failure to acknowledge receipt of this Addendum in Paragraph 10 of Form A: Proposal may render your Proposal non-responsive.

PART B – BIDDING PROCEDURES

Revise: B2.1 to read: The Submission Deadline is 12:00 noon Winnipeg time, May 18, 2021

PART E – SPECIFICATIONS

Revise: E1.4 to read: The following are applicable to the Work:

<u>Drawing No.</u>	<u>Drawing Name/Title</u>
M.18-H1-R0	Existing Conditions & Removals
M.18-H2-R0	Materials Plan
M.18-H3-R0	Layout Plan
SCD-119-R4	Waste Receptacle Side Opening Metal Slat Type
SCD-121A-R3	Tache Bench Composite with Arms
SCD-153-R3	English Park Sign w/ Address
SCD-646-R1	Parkway Path Crushed Limestone
SCD-650-R1	Engineered Wood Fibre Safety Surfacing Drainage Diagram
SCD-651A-R5	Double Tier Timber Edging
SCD-651C-R2	Double Tier Timber Edging with Cap at accessible entrance
SCD-659-R3	Multi-flow Drainage
SCD-660-R1	Painted Wooden Sandbox on Granular Pad
SCD-661-R0	Perforated Pipe w/ Filter Cloth Drainage System
M.18-H0-CAD-R0	CAD file of proposed site layout

Revise: E20.3.1 to read: Installation shall be in accordance with Manufacturers specifications and in accordance with the most recent Canadian Standards Association Standards within the designated play equipment area on the Drawings.

- (a) Contractor shall use threadlock, per E20.2.4, on all hardware for swing components assembled on site by Contractor, as per Manufacturer's written specifications and instructions.
- (b) Top rail is to be level and posts securing anchored in concrete.
- (c) Swing seats shall not be installed until the protective surfacing, has been installed.

Delete: E21.4.2

Delete: E21.4.3

Delete: E21.4.4

Delete: E21.4.5

Add: E21.4.7 **Playground Equipment Footing**

- (a) Holes for concrete footing for play equipment and swings must be inspected and approved by the Contract Administrator prior to installation of concrete. Contractor to provide min. two (2) business days' notice for inspection.**
- (b) All concrete footings for play equipment and swing sets shall be in accordance with Manufacturer's specifications. Proponents are to include drawings showing Manufacturer's Footing Specification in their Bid Submission.**
- (c) All posts and supports shall be centred in the concrete footing such that there is a complete collar of concrete around each post and support. Where posts are not perfectly centred there should be a minimum of 50 mm (2") concrete at any point around the post.**

DRAWINGS

Delete: 301-2021_Drawing_SCD-670-R1

Delete: 301-2021_Drawing_SCD-671-R1