

**NOTES:**

THESE DRAWINGS SHALL BE HELD AS CORRECT UNLESS OTHERWISE NOTED ON THESE DRAWINGS. ANY CHANGES SHALL BE MADE BY THE ARCHITECT OR HIS/HER REPRESENTATIVE BY THE DATE OF THE ISSUANCE OF THE DRAWINGS. THE ARCHITECT SHALL NOT BE RESPONSIBLE FOR THE ACCURACY OF ANY INFORMATION PROVIDED TO THE ARCHITECT BY OTHERS. THE ARCHITECT SHALL NOT BE RESPONSIBLE FOR THE ACCURACY OF ANY INFORMATION PROVIDED TO THE ARCHITECT BY OTHERS. THE ARCHITECT SHALL NOT BE RESPONSIBLE FOR THE ACCURACY OF ANY INFORMATION PROVIDED TO THE ARCHITECT BY OTHERS.

**SCOPE OF WORK:**

HATCHED AREAS ON PLAN INDICATE SCOPE OF WORK FOR FLOORING REMOVAL AND NEW FLOORING INSTALLATION.

**DEMOLITION NOTES:**

- ① REMOVE ALL EXISTING CARPET IN HATCHED AREAS, CLEAN AND MAKE GOOD. SUB FLOOR TO BE CONCRETE. REMOVE CARPET TILE. SUB FLOOR IS CONCRETE IN ALL AREAS EXCEPT COMMON CORRIDORS.
- ② REMOVE EXISTING CARPET BASE AND SUPPLY AND INSTALL NEW 1/4" RUBBER CODE BASE TO MATCH TO EXISTING TO ALL WALLS UNLESS OTHERWISE INDICATED.

**GENERAL NOTES:**

- ① CONSTRUCTION WORK TO BE COMPLETED DURING REGULAR BUSINESS HOURS. INSTALLER TO WORK WITH WPS CLIENT FOR PHS SCHEDULE OF WORK.
- ② CONTRACTOR TO SITE CONFIRM ALL DIMENSIONS.
- ③ WORKSITATIONS TO REMAIN AND BE OPERATIONAL DURING CARPET REPLACEMENT. FLOORING SPECIALISTS TO BE RESPONSIBLE FOR PROTECTING ALL EXISTING WORK AND FINISHES. CONTRACTOR TO BE RESPONSIBLE FOR PROTECTING ALL EXISTING WORK AND FINISHES. CONTRACTOR TO BE RESPONSIBLE FOR PROTECTING ALL EXISTING WORK AND FINISHES.
- ④ ALL TRANSITION STRIPS, JOINT REDUCERS TO BE REPLACED TO MATCH TO EXISTING MATERIAL AND COLOR.
- ⑤ ENGINEER AFTER CARPET INSTALLATION HAS BEEN COMPLETED THAT THE CARPET HAS BEEN LEFT FOR MAINTENANCE.
- ⑥ COLORING MATERIALS TO SITE. USE BASE DURING SITE INVESTIGATION TO ENSURE CORRECT QUANTITY OF CARPET TILES ORDERED.

**MATERIALS/FINISH LEGEND**

- CFC - MOHAWK GROUP GR445 FIRST ONE UP II 488 IMPACTANCE CARPET TILE AT 7X9" INSTALLATION 1 TURN
- FULL SPREAD POLYESTER INSTALLATION IN ALL OFFICE AREAS AS SUB-FLOOR IS CONCRETE
- RE-EXISTING RUBBER BASE TO BE REMOVED AND REPLACED WITH NEW RUBBER BASE TO MATCH RUBBER BASE. JOHNSONITE COLOR: 100; TYPING TOP SET COVER.

