

380-2021 ADDENDUM 2

2021 REGIONAL STREET RENEWAL PROGRAM – UNIVERSITY CRESCENT PAVEMENT RECONSTRUCTION

URGENT

**PLEASE FORWARD THIS DOCUMENT TO
WHOEVER IS IN POSSESSION OF THE
BID/PROPOSAL**

ISSUED: June 8, 2021
BY: Ryan Cunningham
TELEPHONE NO. 204 928-8377

**THIS ADDENDUM SHALL BE INCORPORATED
INTO THE BID/PROPOSAL AND SHALL FORM
A PART OF THE CONTRACT DOCUMENTS**

Template Version: Add 2021-03-05

Please note the following and attached changes, corrections, additions, deletions, information and/or instructions in connection with the Bid/Proposal, and be governed accordingly. Failure to acknowledge receipt of this Addendum in Paragraph 10 of Form A: Bid/Proposal may render your Bid/Proposal non-responsive.

PART E – SPECIFICATIONS

Revise E9.1 (a) (vii) to read: University Crescent from Chancellor Matheson Road to the south side of Dysart Road will be closed to all traffic except that requiring access to and from IG Field and Winnipeg Transit service. Winnipeg Transit buses will be directed through this section of University Crescent by IG Field staff or their designate.

Revise E9.1 (b) (v) to read: University Crescent from Chancellor Matheson Road to the south side of Dysart Road will be closed to all traffic except that requiring access to and from IG Field and Winnipeg Transit service. Winnipeg Transit buses will be directed through this section of University Crescent by IG Field staff or their designate.

Revise E24.1 (a) to read: Master anchor bolt templates and Oversized D top rings shall be supplied by the Contractor and used for all bases constructed under the provisions of this specification.

Add: **E28. UTILITY CLEARANCES**

E28.1 Further to CW 1120-R1, Clause 3.1, the Contractor is responsible for arranging for the location of any utilities not completed under ClickBeforeYouDigMB.com. No measurement or payment will be made for this work.

Add: **E29. WORK IN THE VICINITY OF UNIVERSITY OF MANITOBA CAMPUS**

E29.1 Rigid fencing is required around underground work excavations on the east side of University Crescent.

E29.2 All trees adjacent to the east property line of University Crescent shall be protected as per E5.2, to the satisfaction of the Contract Administrator.

E29.3 The Contractor shall complete a site walkthrough with the Contract Administrator and University of Manitoba Representative to review signage and traffic management between this Contract and the University of Manitoba pavement reconstruction project on University Crescent south of Dafoe Road.

Add: **E30. SALVAGE AND STOCKPILE OF EXISTING PAVING STONES**

E30.1 The Contractor shall salvage and stockpile existing paving stones located within the sidewalk renewal area on the west side of University Crescent from Chancellor Matheson Road to Bohemier Trail. Paving stones shall be stockpiled at a location identified by the Contract Administrator. No measurement or payment will be made for this work.