



# 347-2022 ADDENDUM 2

## KIRBY SETTER PARK PLAYGROUND REDEVELOPMENT

### **URGENT**

**PLEASE FORWARD THIS DOCUMENT TO  
WHOEVER IS IN POSSESSION OF THE  
BID/PROPOSAL**

ISSUED: May 19, 2022  
BY: Ian Macdonald  
TELEPHONE NO. 204 451-3069

**THIS ADDENDUM SHALL BE INCORPORATED  
INTO THE BID/PROPOSAL AND SHALL FORM  
A PART OF THE CONTRACT DOCUMENTS**

Template Version: Add 2021-03-05

**Please note the following and attached changes, corrections, additions, deletions, information and/or instructions in connection with the Bid/Proposal, and be governed accordingly. Failure to acknowledge receipt of this Addendum in Paragraph 10 of Form A: Bid/Proposal may render your Bid/Proposal non-responsive.**

### **FORM B: PRICES**

Replace: 347-2022 Form B: Prices\_R1 with 347-2022 Form B: Prices\_R2. The following is a summary of changes incorporated in the replacement Bid/Proposal Submission:

Form B(R2): Option to use CIP concrete edge instead of timber edge (Item 3)

Page numbering on some forms may be changed as a result.

### **PART E – SPECIFICATIONS**

Revise: E1.4 to read:

E1.4 The following are applicable to the Work:

<u>Specification No.</u>	<u>Specification Title</u>
CW-1110	General Instructions
CW-1130	Site Requirements
CW-2160	Concrete Underground Structures and Works
CW-3110	Sub-Grade, Sub-Base and Base Course Construction
CW-3130	Supply and Installation of Geotextile Fabrics
CW-3170	Earthwork and Grading
CW-3510	Sodding
CW-3520	Seeding
CW-3540	Topsoil and Finish Grading for Establishment of Turf Areas

<u>Drawing No.</u>	<u>Drawing Name/Title</u>
K.48-1A	Existing Conditions and Removals
K.48-1B	Materials Plan
K.48-1C	Layout Plan
K.48-1D	Path Layout Plan

SCD-119-R4	Waste Receptacle Side Opening Metal Slat Type
SCD-121A-R3	Tache Bench Composite with Arms
SCD-122A -R3	Tache Style Wheelchair Metal Frame Picnic Table
SCD 153-R3	English Double-Sided Park Sign w/ Address
<b>SCD 643-R2</b>	<b>Concrete Playsurface Edging Detail</b>

SCD-646-R1	Parkway Path Crushed Limestone
SCD-650-R1	Engineered Wood Fibre Safety Surfacing Drainage Diagram
SCD-651A-R5	Double Tier Timber Edging
SCD-659-R3	Multi-Flow Drainage
SCD-661	Perforated Pipe w/ Filter Cloth Drainage System

K.48-1-CAD CAD file of proposed site layout

Add E21:

## **E21. CAST IN PLACE CONCRETE PLAY EDGING**

### **E21.1 General Description**

E21.1.1 This section shall cover the supply and installation of cast in place concrete play edging as per the Drawings. It shall amend and supplement the most up-to-date version of City of Winnipeg Standard Construction Specifications section 3310 and as per SCD-643 and details in Drawings.

### **E21.2 Materials**

E21.2.1 Concrete shall be Type 1 as per the most up-to-date version of City of Winnipeg Standard Construction Specifications section 3310 and shall adhere to the dimensions on the Drawings.

E21.2.2 Granular base shall be 19mm diameter crushed limestone.

E21.2.3 Reinforcing steel for play edging shall be 10m with 10m ties at 600 mm O.C.

### **E21.3 Construction Methods**

E21.3.1 Layout is to be established on Site, after excavation and grading operations and reviewed by Contract Administrator prior to formwork being completed.

- (a) Contractor is to confirm and warrant that play equipment and swings (complete with required safety surfacing zones) will fit within curbs as laid out on Site.

E21.3.2 Granular base, formwork and reinforcing are to be reviewed on Site by the Contract Administrator prior to pouring of concrete.

E21.3.3 Concrete is to be trowel finish. All exposed edges are to be bull nose as shown on the Drawings. Front, top and back of curb are to be finished.

E21.3.4 Concrete edging shall have saw cut control joints at 1.5m intervals.

### **E21.4 Method of Measurement and Basis of Payment**

E21.4.1 Method of Measurement shall be as follows:

- (a) Concrete edging will be measured on a Linear Metre basis for:

- (i) **“Supply & install double tier timber edging OR CIP concrete edging” on Form B-R2: Prices.**

E21.5 Basis of Payment Shall be as follows:

E21.5.1 Concrete edging will be paid for at the Contract Unit Prices. The amount to be paid for shall be the total number of units, as indicated on Form B: Prices. This price shall be full payment for supplying all labour, equipment and materials, and performing all operations herein described and all other items incidental to the Work and as accepted by the Contract Administrator.

E21.5.2 This payment shall be understood to include all concrete, excavation, base, reinforcing, compaction, placement and finishing.

## **DRAWINGS**

Add: 347-2022\_Drawing\_SCD-643-R2

Replace: 347-2022\_ Drawing\_K.48-1B with 347-2022\_Addendum\_2\_Drawing\_K.48-1B\_R1