



CONTROL CHAMBER - LOWER LEVEL DEMOLITION PLAN
SCALE: 1 : 100

GENERAL NOTES

1. CONTRACTOR TO SITE VERIFY ALL EXISTING HYDRONIC FLUSHING WATER, AND DOMESTIC POTABLE WATER BEFORE COMMENCING ANY WORK.
3. CONTRACTOR TO PLACE ISOLATION VALVES ON ALL NEW HYDRONIC, FLUSH WATER, AND DOMESTIC POTABLE WATER TIE-INS TO EXISTING PLANT PIPING.
4. CONTRACTOR TO REMOVE ALL UN-USED EXISTING HYDRONIC PIPING AFTER TIE-IN OF NEW HYDRONIC SYSTEM FOR SCUM BUILDING.

GENERAL DRAWING NOTES

- ① EXISTING 63 HYDRONIC HOT WATER SUPPLY TO ABANDONED HEAT EXCHANGER LOCATION TO BE REMOVED. ALL ASSOCIATED ACCESSORIES TO THIS PIPE TO BE REMOVED.
- ② EXISTING 63 HYDRONIC HOT WATER RETURN TO ABANDONED HEAT EXCHANGER LOCATION TO BE REMOVED. ALL ASSOCIATED ACCESSORIES TO THIS PIPE TO BE REMOVED.
- ③ EXISTING 150 DOMESTIC POTABLE WATER TO REMAIN.
- ④ CUT EXISTING 150 HYDRONIC LINE AND TIE-IN NEW HYDRONIC LINES FOR NEW HYDRONIC SYSTEM FOR THE SCUM BUILDING. PROVIDE ISOLATION VALVES. ALL PIPING TO BE FLANGED FOR NEW TIE-IN.
- ⑤ EXISTING 150 HOT WATER SUPPLY TO REMAIN.
- ⑥ EXISTING 150 HOT WATER RETURN TO REMAIN.

Sheet List_City Drawing Number Fix			
Sheet Number	Consultant Drawing Number	Client Drawing Number	Page Number
P1-M101	P1-M101	1-0101-MGAD-P601	001
P1-M102	P1-M101		
P1-MD101	P1-MD101	1-0101-MGAD-PD01	001

<p>AECOM</p> <p>DESIGNED BY: BW / DJP CHECKED BY: BW</p> <p>DRAWN BY: DJP APPROVED BY: NW</p> <p>SCALE: 1 : 100 RELEASED FOR CONSTRUCTION BY:</p> <p>DATE: 2020-12-09 DATE:</p>		ENGINEER'S SEAL	
		<p>CONSULTANT NO.: P1-MD101</p>	
		<p>ISSUED FOR ADDENDUM 5</p>	
		<p>NO. REVISIONS</p>	
<p>2023-11-10</p>		<p>BW</p>	<p>BP</p>
<p>DATE</p>		<p>DESIGN</p>	<p>CHECK</p>

THE CITY OF WINNIPEG
WATER AND WASTE DEPARTMENT

Winnipeg

NORTH END SEWAGE TREATMENT PLANT
PRIMARY CLARIFICATION PROJECT
MECHANICAL
CONTROL CHAMBER BUILDING
DEMOLITION FLOOR PLAN

CITY DRAWING NUMBER	SHEET	REV.	SIZE
1-0101-MGAD-PD01	001	01	A1