



986-2022 ADDENDUM 3

SUPPLY OF RECYCLED CONCRETE AGGREGATE

URGENT

**PLEASE FORWARD THIS DOCUMENT TO
WHOEVER IS IN POSSESSION OF THE
BID/PROPOSAL**

ISSUED: January 30, 2023
BY: Andrew Condon, P.Eng.
TELEPHONE NO. 204 986-7940

**THIS ADDENDUM SHALL BE INCORPORATED
INTO THE BID/PROPOSAL AND SHALL FORM
A PART OF THE CONTRACT DOCUMENTS**

Template Version: Add 2021-03-05

Please note the following and attached changes, corrections, additions, deletions, information and/or instructions in connection with the Bid/Proposal, and be governed accordingly. Failure to acknowledge receipt of this Addendum in Paragraph 10 of Form A: Bid/Proposal may render your Bid/Proposal non-responsive.

PART B – BIDDING PROCEDURES

Revise: B2.1 to read: The Submission Deadline is 4:00 p.m. Winnipeg Time, February 2, 2023

PART D – SUPPLEMENTAL CONDITIONS

Add: D14 **Production Schedule**

Add: D14.1 The City is anticipating the use of approximately 11,000 tonne of 50 mm Granular B Recycled Concrete Aggregate in 2023. The majority of this material is anticipated to be utilized in connection with local street reconstructions. A detailed quantity schedule cannot be established until after these projects have been awarded and construction schedules have been determined. In order to meet the demands for this material, the City requires the following production schedule:

Add: D14.1 (a) 2,100 cubic meters (approximately 4,000 tonne) by May 1st, 2023.

Add: D14.1 (a) A cumulative total of 4,200 cubic meters (approximately 8,000 tonne) by June 1st, 2023.

Add: D14.1 (a) A cumulative total of 6,300 cubic meters (approximately 12,000 tonne) by July 1st, 2023.

Add: D14.2 From time to time, the Contract Administration may request the Contractor produce material in 2,100 cubic meter increments. The request will be made based on the anticipated future needs and available space at the Contractors Yard. The Contractor shall have 5 days to commence production of the material and shall produce the material at a rate of 2,100 cubic meters per 30 Calendar Days.

Add: D14.3 The Contractor must be capable of stockpiling up to 6,300 cubic meters of Goods at their Yard unless otherwise agreed to in writing by the Contract Administrator.

Add: D14.4 The Contract Administrator shall make a reasonable effort to minimize the amount of Goods stockpiled in the Contractors yard between the 2023 and 2024 construction seasons.

Add: D14.5 The Contract Administrator shall inform the Contractor of the anticipated quantity required in 2024 by January 31st, 2024.

Revise Numbering: D14 Liquidated Damages to D15. Liquidated Damages

Revise Numbering: D14.1 to D15.1

Revise: D15.1 to read: If the Contractor fails to make available for loading a minimum of 2,100 cubic meters of Goods by May 1st, 2023, the Contractor shall pay the City one thousand dollars (\$1,000.00) per Calendar Day for each and every Calendar Day until the Goods are available for loading in accordance with D13 and E3.

Revise Numbering: D14.2 to D15.2

Revise: D15.2 to read: If the Contractor fails to make available for loading a minimum cumulative total of 4,200 cubic meters of Goods by June 1st, 2023, the Contractor shall pay the City one thousand dollars (\$1,000.00) per Calendar Day for each and every Calendar Day until the Goods are available for loading in accordance with D13 and E3.

Revise Numbering: D14.3 to D15.3

Revise: D15.3 to read: If the Contractor fails to make available for loading a minimum cumulative total of 6,300 cubic meters of Goods by July 1st, 2023, the Contractor shall pay the City one thousand dollars (\$1,000.00) per Calendar Day for each and every Calendar Day until the Goods are available for loading in accordance with D13 and E3.

Revise Numbering: D14.4 to D15.4

Revise: D15.4 to read: If the Contractor fails to make available for loading 2,100 cubic meters of Goods within 30 Calendar Days of a request by the Contract Administrator in accordance with D14.2, the Contractor shall pay the City one thousand (\$1,000) per Calendar Day for each and every Calendar Day until the Goods are available for loading in accordance with D13 and E3.

Revise the Numbering for the remainder of the tender accordingly.

PART E – SPECIFICATIONS

Revise: E3.8 to read: Further to CW 3110, the Contract Administrator will be responsible for conducting Quality Assurance sampling at the Contractors Yard. The Contract Administrator shall conduct Quality Assurance Testing at the frequency outlined in Table CW 3110.3 – Quality Control Testing Frequency During Production.

Revise: E3.10 to read: Quality Assurance testing will be accepted on the basis of CW 3110 Section 5.

Revise: E3.11.1 to read: Seventy-Five (75%) percent of quantity following the production of Recycled Concrete Aggregate that has been accepted by the Contract Administrator. This quantity shall be calculated by measuring the volume of the stockpiles produced and converting it to weight with an assumed density of 1.9 tonne/m³. This quantity will be adjusted to the actual weight measured on a certified scale as it is loaded in accordance with D13