



## 553-2023 ADDENDUM 2

### SUPPLY, DELIVERY AND INSTALLATION OF AIR COMPRESSOR

#### **URGENT**

**PLEASE FORWARD THIS DOCUMENT TO  
WHOEVER IS IN POSSESSION OF THE  
BID/PROPOSAL**

ISSUED: July 17, 2023  
BY: Jeff Jones  
TELEPHONE NO. 204 619-0542

**THIS ADDENDUM SHALL BE INCORPORATED  
INTO THE BID/PROPOSAL AND SHALL FORM  
A PART OF THE CONTRACT DOCUMENTS**

Template Version: Add 2021-03-05

---

**Please note the following and attached changes, corrections, additions, deletions, information and/or instructions in connection with the Bid/Proposal, and be governed accordingly. Failure to acknowledge receipt of this Addendum in Paragraph 10 of Form A: Bid/Proposal may render your Bid/Proposal non-responsive.**

---

#### **PART E – SPECIFICATIONS**

- Revise E6.5 to read: External fill point shall have a non-regulated rated output of 6000 PSIG.
- Delete: E6.10
- Delete: E6.12
- Add: E6.19 Fill station shall be plumbed to existing remote panel
- Add: E6.20 Eight (8) 4500 PSIG fill whips shall terminate in MSA G1 quick connect fittings.
- Add: E10.5 The Contractor shall complete the initial air sampling and order expedited services for this sampling.
- Add: E10.6 All stainless plumbing from air compressor to fill station and air storage shall be 3/8" Swagelok.
- Add: E10.7 The existing room ducting/cooling system shall be matted to the cooling outlet fan of the compressor via a rubber bellow or equivalent