

PART E
SPECIFICATIONS

PART E - SPECIFICATIONS

GENERAL

E1. GENERAL

E1.1 These Specifications shall apply to the Work.

E2. GOODS

E2.1 The Contractor shall supply asphalt, hot mix for patching operations in accordance with the requirements hereinafter specified.

E2.2 All asphalt, hot mix supplied for patching operations shall be supplied at a minimum temperature of 150°C.

E3. ASPHALT CONCRETE MIXES

E3.1 Asphaltic concrete supplied as Items 1, 2, and 3 listed on Form B: Prices, must be produced and meet all the requirements and specifications of the current City of Winnipeg Standard Construction Specifications CW 3410 R5 for production. This information is available in Adobe Acrobat (.pdf) format at The City of Winnipeg Materials Management internet site <http://www.winnipeg.ca/matmgt/info.stm>;

E4. PICK UP

E4.1 Goods shall be picked up on an "as-required" basis during the term of the Contract, for various locations within the City.

E4.1.1 Goods shall be picked up on demand between the hours of 7:00 a.m. to 5:00 p.m. Monday to Friday excluding statutory holidays, except where otherwise agreed at the time of ordering.

E4.1.2 The Contractor shall load trucks promptly upon their arrival at the Contractor's plant unless otherwise notified by the City.

E4.1.3 If the City has to wait for material for over thirty (30) minutes the Contractor shall pay the City of Winnipeg \$45.00 for each thirty (30) minute period of delay and the City will reduce payment to the Contractor by that amount.