



ADDENDUM NO. 1 BID OPPORTUNITY NO. 138-2004

**2004 MAIN STREET – ROADWAY RECONSTRUCTION (SOUTHBOUND)
AND STREETSCAPING (WESTSIDE) – LOMBARD AVENUE TO DISRAELI
FREEWAY**

ISSUED: April 6, 2004
BY: Coleen Groening/CD
TELEPHONE NO. (204) 986-2491

URGENT

**PLEASE FORWARD THIS DOCUMENT TO
WHOEVER IS IN POSSESSION OF THE BID
OPPORTUNITY**

**THIS ADDENDUM SHALL BE INCORPORATED
INTO THE BID OPPORTUNITY AND SHALL
FORM A PART OF THE CONTRACT
DOCUMENTS**

Template Version: 20040128

Please note the following and attached changes, corrections, additions, deletions, information and/or instructions in connection with the Bid Opportunity, and be governed accordingly. Failure to acknowledge receipt of this Addendum in Paragraph 10 of Form A: Bid may render your Bid Submission non-responsive.

TABLE CONTENTS

Replace Table of Contents with attached Table of Contents

PART A – BID SUBMISSION

Replace: Form B: Prices with the attached Form B: Prices (R1) and

Replace: Electronic Form B: Prices with the attached Electronic Form B: Prices (R1)

PART E – SPECIFICATIONS

Revise: E1.2 to include:

ROAD RECONSTRUCTION – PART A

Drawing No.	Drawing Title	File Name	Size
P-3247-28	Details For Lighted Transit Signage	138-2004_Drawing_P-3247-28-R0.pdf	8.5"x11"

Delete: E40 HOT DIP GALVANIZING

Add: E39.11 Hot Dip Galvanizing

Steel screw anchor shall be hot dip galvanized after fabrication has been completed. Galvanizing shall be to CSA-G164.

Add: E39.12 Handling and Storage

All lifting and handling shall be done using devices that do not mark damage, or distort the assemblies or members in any way. Girders shall be stored upright, supported on sufficient skids and safely shored to maintain the proper section without buckling, twisting or in any damage or misalign the material.

Add: E39.13 Method of Measurement

The supply and installation of steel screw anchors for the Diamond Lane Overhead Sign Structures will be measured on a unit basis. The number of foundations to be paid for shall be the total number of foundations measured. The number of foundations to be paid for shall be the total number of foundations fabricated/supplied and installed in accordance with this Specification and accepted by the Contract Administrator, as computed from measurements made by the Contract Administrator.

Add: E39.14 Basis of Payment

The supply and installation of steel screw anchors for the Diamond Lane Overhead Sign Structures will be paid for at the Contract Unit Price per unit for "Supply and Install Steel Screw Anchors", measured as specified herein, which price shall be payment in full for supplying all materials and performing all operations described herein and all other items incidental to the Work included in this Specification.

Replace: Drawing - 138-2004_Drawing_P-3247-15-R0.pdf with the attached Drawing - 138-2004_Drawing_P-3247-15-R1.pdf

Add: Drawing - 138-2004_Drawing_P-3247-28-R0.pdf