



CAMEL SYS STREET

CONSTRUCTION NOTES:

- 1 REMOVE AND DISPOSE OF EXISTING FENCE (INCIDENTAL).
- 2 EXTEND BARRIER CURB, TIE INTO EXISTING CURB.
- 3 REMOVE EXISTING TREES.
- 4 SAWCUT EXISTING EDGE OF SLAB AS DIRECTED BY CONTRACT ADMINISTRATOR.
- 5 BARRIER CURB TO MODIFIED BARRIER CURB TRANSITION.
- 6 REMOVE EXISTING BERM.
- 7 CONNECT TO EXISTING MANHOLE.
- 8 ALL DIMENSIONS MEASURED TO BACK OF CURB.
- 9 ADJUST ALL MANHOLES AND VALVES.
- 10 ALL CATCHBASINS AS PER SD-024 UNLESS OTHERWISE NOTED.
- 11 PROPOSED CONCRETE SIDEWALK ON 100mm - 19mm DOWN LIMESTONE BASE.
- 12 250mm - DR35 SEWER SERVICE.
- 13 27m - 600mm - 1.6mm GAUGE CORRUGATED STEEL PIPE.
- 14 RAILROAD CROSSING AS PER SD-231A.
- 15 RAILROAD SIDEWALK CROSSING AS PER SD-231B.
- 16 PLACE SUITABLE SITE MATERIAL IN EXISTING DITCH AS PER COW 3170-14.
- 17 REMOVE EXISTING CULVERT.
- 18 LOWER EXISTING CULVERT TO INVERTS SHOWN AND EXTEND 2m S.

LOCATION APPROVED UNDERGROUND STRUCTURES		B.M.	30-005
NO.	ISSUED FOR BIDDING	ELEV.	233.321
0			
NO. REVISIONS		F.B.	1988
		DATE	04.04.16
		BY	
		DATE	

WARDROP Engineering Inc.		DESIGNED	GMD	CHECKED	
		BY		BY	
		DRAWN	GMD/MR4/PS	APPROVED	
		BY		BY	
		HOR. SCALE:	1 : 250	RELEASED FOR CONSTRUCTION	
		VERTICAL:	1 : 10	DATE	

CONSULTANT DRAWING NO. 031294-01-00

THE CITY OF WINNIPEG
PLANNING, PROPERTY AND DEVELOPMENT

2004 SAINT BONIFACE INDUSTRIAL PARK ROADWORKS
CAMEL SYS STREET
STA. 5+00 TO STA. 6+50

CITY DRAWING NUMBER
SHEET 4 OF 16
C0004

APACIN
Certificate of Authorization
Wardrop Engineering Inc.
No. 195 Expiry: April 30, 2004